



12112 St. Rt. 185  
Versailles, OH 45380

# Estimate

**Tel:** 937-278-6680  
**Fax:** 419-336-1032  
**E-mail:** sales@hessfencing.com

Date	Estimate No
6/13/2022	11095

**To:**

City of Celina OH  
P.O.Box 297  
Celina, OH 45822

**Project Location:**
**Customer Contact:**
**Customer Phone:**
**Customer Fax:**

P.O. No.	Terms	Rep	Project
	Net 15		
Description			Total
Supply materials,equipment and labor to construct a 6' high black vinyl coated chain link fence around Pickle ball courts measuring 130X64' for total of 382 lin ft with 2-3' wide gates. Figuring full weight post 3" terminals and 2.5" line post, 1 5/8",top and bottom rails. Note fabric to be 1 3/4" weave to inhibit ball pass through.			27,930.00
Add one 8' wide DD gate system.			600.00
<b>Total</b>			<b>\$28,530.00</b>

This is an estimate based on current prices and is good for 15 days from the date above.

ACCEPTED BY: \_\_\_\_\_, Date: \_\_\_\_/\_\_\_\_/\_\_\_\_  
I HAVE REVIEWED AND DO ACCEPT THIS ORDER AS QUOTED.  
Please reference Purchase Order #: \_\_\_\_\_  
Please return this signed proposal by faxing to 419.336.1032.

Instructions:



**QUOTE/CONTRACT**  
**REVISION #1**

510 N St Marys Road  
Spencerville, OH 45887  
419-604-0698  
sales@dm-fencing.com

Attn: Garrett Lutz  
Phone: 419-586-1144  
Project: City Park/Pickleball Court  
Email: [engasst2@celinaohio.org](mailto:engasst2@celinaohio.org)

**Quote Date: 06/10/2022**

D&M Fencing is pleased to quote all labor and materials to perform the following work as described at the following location in **Celina**, Ohio. All work will be done in a professional manner & per the American fence association standards. Warranties are through the manufacturer.

**Option #1 - 6' Tall Black Coated Chain Link:**

- Install Approx. 388' Linear Feet of Fence
- Bracing at All Terminals
- Bottom Tension Wire (+\$4,500 to have Bottom Rail Installed)
- Install (2)-4' Walk Gates
- Install (1)-8' Double Swing Gate

All Posts Augured & Concreted Into Ground.

**Project Total: \$38,750**

**Option #2 - 10' Tall Black Coated Chain Link:**

- Install Approx. 388' Linear Feet of Fence
- Install Top - Mid - Bottom Rails
- Install (2)-4' Walk Gates (4' Fence Above Gates)
- Install (1)-Double Swing Gate

All Posts Augured & Concreted Into Ground.

**Project Total: \$40,300**

Please Initial \_\_\_\_\_

**PLEASE REVIEW & SIGN ATTACHED "TERMS & CONDITIONS" PAPERWORK PROVIDED SEPARATELY WITH THIS ESTIMATE.**

**THIS QUOTE IS VALID FOR 5 DAYS**

By signing below you have read and understand the quote/contract as stated above. Anything not listed in this document is not included in the project.

Signature of Acceptance: \_\_\_\_\_ Printed Name: \_\_\_\_\_

DATE: \_\_\_\_\_ Position or Title With Company: \_\_\_\_\_