

TRAILER(S) SHIPPED FACTORY DIRECT TO DEALER OR CUSTOMER, REQUIRE THE BELOW TASKS COMPLETED PRIOR TO FIRST USE

Lug nuts must be torqued to 65 lb/ft

Bolt on draw bar

Installation of hub caps

Seam sealer must be applied to all seams

Fabric repellent must be applied to fabric (not seams)

Tire pressure must be adjusted to appropriate PSI Rating as per rating on tires AND as per trailer weight with accessories and cargo.

Lubricate coupler

Check all lights

Safe Travels 😊