

Addendum No 001 Narrative

March 07, 2024

To Drawings and Specifications dated <u>October 5, 2023</u>

Walnut Grove Intermediate School – Science Classroom Modernization West Covina Unified School District

Prepared by: PBK

8363 Rochester Ave

Rancho Cucamonga, CA 91730

PBK Project No.: 202117

DSA A#: <u>A# 03-123048</u>

DSA File No.: 19-110

Notice to Bidders:

- A. Receipt of this addendum shall be acknowledged on the bid form.
- B. This addendum forms part of the contract documents for the above-referenced project and shall be incorporated integrally therewith.
- C. Each bidder shall make necessary adjustments and submit his bid with full knowledge of all modifications, clarifications, and supplemental data included therein. Where provisions of the following supplemental data differ from those of the original contract documents, this addendum shall govern.

Drawings: (Refer to revision clouds and Delta 1)

- 1. Item No. AD1-G0.02:
 - A) Keynote 22.10 Added detail reference 6/A2.21.
- 2. Item No. AD1-G0.021:
 - B) Populated the empty Occupant Load Room Tag for Classroom 22 and centered it in the room.
- 3. Item No. AD1-D2.01:
 - A) Fixed spelling on Keynote D46 "Mountain" to "Mounting"
 - B) Classroom 18, East wall Added "TYP. Of 4" at the end of keynote D14 "(E) Structure column and footing to remain, protect in place."
 - C) Room 19, North wall Replaced keynote D75 "Demolish existing wall, door, and frame" with keynote D67 "Demolish Wall, (E) Columns to protect in place (Where Occurs)."
 - D) Modified Dimensions on trenching from 4'-0" to 6'-0" and added +/- to trench dimensions.
 - E) Added Demolition note 32, which states "trenching demolition is approximate and needs to be coordinated with actual field conditions and detail requirements. see the remodel plan for additional information.
- 4. Item No. AD1-A1.01:
 - A) Edited keynote 02.09 to state "(E) Planting area protect in place."
 - B) Edited keynote 02.18 to state "(E) Concrete walkway to remain protect in place."
 - C) Detail 15 Sign Post Footing Note 2% slope on top of the footing to divert water away from the sign post.

- D) Added keynote 32.06 which states "Parking Bumper per detail 16/A1.01"
- E) Added keynote 32.07 which states "Accessible parking symbol per detail 17/A1.01"
- F) Detail 5 Enlarged Partial Remodel Parking Lot #1 Added keynote 32.06 and 32.07.

5. Item No. AD1-A2.01:

- A) Wall between rooms 19 and 22 Added wall tag for a new wall partition.
- B) Modified General construction notes numbering.
- C) Added note 16, which states "trenching demolition is approximate and needs to be coordinated with actual field conditions and detail requirements."

6. <u>Item No. AD1-A2.21:</u>

- A) Details 3 and 5 Edited bubble callout view reference on the remodel plan legend to 10/A10.01 instead of 21/A10.01
- B) Details 3 and 5
 - a. Added keynote 02.04 which states "(E) Floor finish to remain, protect in place."
 - b. Added keynote 02.52 "(E) Grab bars to be removed and reinstall at accessible height per detail 5/A10.01.
 - Added keynote 02.53 (E) toilet paper dispenser to be removed and relocated per detail 5/A10.01"
- C) Details 9A & 11A "Added Keynote 2.53, (E) toilet paper dispenser to be removed and relocated per detail 5/A10.01"
- D) Detail 11C Added keynote 02.48 which states "(E) Furred wall protect in place".
- E) Details 11, 11A & 11B added keynote 02.52 which states "(E) Grab bars to be removed and reinstall at accessible height per detail 5/A10.01
- F) Details 9, 9A & 9D added keynote 02.52 which states "(E) Grab bars to be removed and reinstall at accessible height per detail 5/A10.01.
- G) Fixed spelling on keynote 22.04 to state "Mounting" instead of Mountain.
- H) Edited viewport 11 title to "Interior Elevations Girls restroom 104.
- I) Added Crosshatch region to Viewports 9A, 9D, 11A, and 11B to indicate areas that will need patch and repair as needed.
- J) Added a dimension from face-to-face wall on viewport 5.
- K) Added note 11 which states "Remove (E) Accessories affected by work" on the notes section.

7. Item No. AD1-A6.01:

- A) Edited details 16 and 17 by removing the upper cabinets from the details.
- B) Added bubble callout view references (14/A6.01, 15/A6.01, 16/A6.01, and 17/A5.01) to viewport 5.

8. Item No. AD1-M6.01:

- A) Detail 19 Modified note 1 and added note 2
- B) Added Detail 4 Flexible Ductwork Hanger Detail
- **C)** Added Detail 6 Typical Hanger Support Detail.

9. <u>Item No. AD1-P6.01:</u>

A) Detail 2 – Modified detail 2 to separate gas and electrical conduits as needed for trenching.

By Yong Yoo, AIA

END OF ADDENDUM NO. 01

00.35 (E) SITE ACCESS SIGN PER A#03-107514, PROTECT IN PLACE 02.01 (E) METAL FENCE 10.04 SAFE DISPERSAL SIGN PER DETAIL 18/A1.01 22.10 ACCESSABLE HILLOW CHILLED DRINKING FOUNTAIN WITH BOTTLE FILLER. SEE DTI 6/A2.21 AND STEEL PIPE RAILS AND FOOTINGS. REPAIR CONC. AS NEEDED **DEMOLITION KEYED NOTES** D73 DEMOLISH (E) DRINKING FOUNTAIN AND PIPE RAILS, SAWCUT SLAB IN PREPARATION FOR NEW PIPE RAILS ACCESSIBILITY LEGEND PATH OF TRAVEL UNER CURRENT PROJECT ●●●●●● (E) PATH OF TRAVEL (A#03 107514) PROPERTY LINE AREA IN SCOPE OF WORK (E) BUILDING NOT IN SCOPE (E) LUNCH SHELTER / (E) SOLAR PANELS E) SHADE STRUCTURE (E) ACCESSIBLE RESTROOM (E) BOYS RESTROOM (E) GIRLS RESTROOM (E) MEN RESTROOM

DSA PROJECT STATUS

(E) WOMEN RESTROOM

(E) GENDER NEUTRAL RESTROOM

ACCESSIBILITY KEYED NOTES

DSA PROJECT STATUS AS OF 2/22/2023 DSA#'S ASSOCIATED IN WITH AREA OF SCOPE OF WORK PROJECT NAME LETTER TYPE 1923 11849 16523 17928 29569 CORONADO ALTERNATIVE SCHOOL
Alterations to 1-Admin. Bldg 1; C.R. Bldgs 4,
OF FILE PER EDU ##2-CERTIFICATION & CLOSE | 1/8/2019 5, 7; M.P. Bldg 2; K.G. Bldg 3; Toilet Bldg 6; Music/Shop Bldg 8; Home Economic Bldg 9 (A#11849, A#16523, A#17928); (1) C.R. Bldg.(Relocatable) (A#29569); Site Work WALNUT GROVE MIDDLE SCHOOL CONSTRUCTION OF 1 - SHADE #1-CERTIFICATION & CLOSE | 6/21/211 STRUCTURE/S (30'X40') WALNUT GROVE INTERMEDIATE DSA 301P NOTIFICATION OF | 1/20/2021 CONSTRUCTION OF 3-SOLAR PANEL REQUIREMENT FOR STRUCTURES PC 04-115627, RELATED CERTIFICATION SITE WORK.

PATH OF TRAVEL

PATH OF TRAVEL PATH OF TRAVEL (P.O.T.) AS INDICATED MEETS THE FOLLOWING REQUIREMENTS:

1. IS A BARRIER-FREE ACCESSIBLE ROUTE WITHOUT ANY ABRUPT LEVEL CHANGES EXCEEDING 1/2" BEVELED AT A SLOPE NOT STEEPER THAN 1:2 EXCEPT THAT LEVEL CHANGES ARE 1/4" MAX. VERTICAL & IS AT LEAST 48" WIDE. 2. SURFACE SHALL BE STABLE, FIRM AND SLIP RESISTANT. 3. CROSS-SLOPE SHALL NOT BE STEEPER THAN 1:48 AND RUNNING SLOPE SHALL NOT BE STEEPER THAN 1:20 UNLESS OTHERWISE INDICATED (CBC 11B-403.3) (CBC 11B-307.4) AND PROTRUDING OBJECTS GREATER THAN 4" PROJECTION FROM WALL SURFACE BETWEEN 27" AND 80" ABOVE FINISH FLOOR OR GROUND (CBC 11B-307.2) 5. PROVIDE FLUSH TRANSITIONS AT ANY ADJOINING JOINTS BETWEEN DIFFERENT WALK SURFACES IN P.O.T. 6. ARCHITECT TO VERIFY THERE ARE NO BARRIERS IN THE P.O.T. AND ALL P.O.T. COMPLY WITH CBC 11B-206.

"DESIGN PROFESSIONAL IN GENERAL RESPONSIBLE CHARGE STATEMENT: THE POT INDENTIFIED IN THESE CONSTRUCTION DOCUMENTS IS COMPLIANT WITH THE CURRENT APPLICABLE CALIFORNIA BUILDING CODE ACCESSIBILITY PROVISIONS FOR PATH OF TRAVEL REQUIREMENTS FOR ALTERATIONS, ADDITIONS AND STRUCTURAL REPAIRS. AS PART OF THE DESIGN OF THIS PROJECT, THE POT WAS EXAMINED AND ANY ELEMENTS, HAVE BEEN IDENTIFIED AND 2) THE CORRECTIVE WORK NECESSARY TO BRING THEM INTO COMPLIANCE HAS BEEN INCLUDED WITHIN THE SCOPE OF THIS PROJECT'S WORK THROUGH DETAILS, DRAWINGS AND SPECIFICATIONS INCORPORATED INTO THESE CONSTRUCTION DOCUMENTS. ANY NONCOMPLIANT ELEMENTS, COMPONENTS OR PORTIONS OF THE POT THAT WILL NOT BE CORRECTED BY THIS PROJECT BASED ON VALUATION THRESHHOLD LIMITATIONS OR A FINDING OF UNREASONABLE HARDSHIP ARE SO INDICATED IN THESE CONSTRUCTION DOCUMENTS.

DURING CONSTRUCTION, IF POT ITEMS WITHIN THE SCOPE OF THE PROJECT REPRESENTED AS CODE COMPLIANT ARE FOUND TO BE NONCONFORMING BEYOND REASONABLE CONSTRUCTION TOLERANCES, THEY SHALL BE BROUGHT INTO COMPLIANCE WITH THE CBC AS A PART OF THIS PROJECT BY MEANS OF A CONSTRUCTION CHANGE DOCUMENT."


E) PARKING LOT 1 (A# 16523 & 03-107514):	
STANDARD STALLS	12
VAN ACCESSIBLE STALLS	1
STD ACCESSIBLE STALLS	0
TOTAL P-LOT 1 STALLS	13
E) DADKING LOT 2 VISITOD (A# 18522 9 02 107514).	
E) PARKING LOT 2 VISITOR (A# 16523 & 03-107514): STANDARD STALLS	16
VAN ACCESSIBLE STALLS	1
STD ACCESSIBLE STALLS	0
TOTAL P-LOT 2 STALLS	17
E) PARKING LOT 3 (STAFF):	
STANDARD STALLS	30
VAN ACCESSIBLE STALLS	0
STD ACCESSIBLE STALLS	0
TOTAL P-LOT 3 STALLS	30
TOTAL STALLS ON SITE	60




RANCHO CUCAMONGA 8163 Rochestser Avenue, Suite 100 Rancho Cucamonga California 91730 P 909-987-0909

CIENCE


IUT GROVE I





NORTH: PLAN TRUE





WEST COVINA USD PROJECT NUMBER 05/09/2023 220117 **DSA BACKCHECK ACCESSABLE SITE**














D2.01







GENERAL CONSTRUCTION NOTES

VERIFY DIMENSIONS AND EXISTING CONDITIONS BEFORE COMMENCING WORK. REPORT DISCREPANCIES TO THE ARCHITECT PRIOR TO PROCEEDING WITH AFFECTED WORK. REFLECTED CEILING PLAN DIMENSIONS ARE REFERENCED FROM FINISHED SURFACES UNLESS NOTED OTHERWISE. CEILING HEIGHTS ARE DIMENSIONED FROM FLOOR TO FINISHED CEILING

WALL-MOUNTED FIRE EXTINGUISHER PER TITLE 19 CLR, DIVISION 1, CH 1 & 3

PULL SIDE

PUSH SIDE

18" MIN. @ INTERIOR 24" MIN. @ EXTERIOR

FRONT APPROACH, DOOR PROVIDED WITH BOTH

LATCH AND CLOSER —

- DIMENSIONS NOTED AS "FIELD VERIFY" SHALL BE CHECKED AT THE SITE BY THE CONTRACTOR AND REVIEWED WITH THE ARCHITECT BEFORE INCORPORATING INTO THE WORK. DO NOT SCALE DRAWING. WRITTEN DIMENSIONS TAKE PRECEDENCE. IF CLARIFICATION IS REQUIRED IN ORDER TO DETERMINE THE INTENT OF THE CONTRACT DOCUMENTS, CONTACT
- 5. NOTES OR DIMENSIONS LABELED "TYPICAL" SHALL APPLY TO SITUATIONS THAT ARE THE SAME OR SIMILAR. 6. ALL DIMENSIONS ARE TO FACE OF FINISHED WALL. UNLESS NOTED OTHERWISE
- 7. ALL FLOORS FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. ALL FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCER STRIPS.
- 8. PATCH AND REPAIR FINISHES AFFECTED BY DEMOLITION AND INSTALLATION OF NEW WORK, MATCH EDJACENT FINISH, COLOS AND WALL ASSEMBLIES


9. REFER TO FINISH PLAN FOR FINISHES (RENUMBER THE REST)
10 REFER TO MECHANICAL PLANS FOR DUCT PENETRATIONS THROUGH EXISTING WALLS. 11₹5% MINIMUM ACCESS COMPLIANT FURNISHINGS SHALL BE PROVIDED BY THE DISTRICT, N.I.C. 123 PROVIDE INSULATION AS FOLLOWS (AT NEW WALLS ONLY - OR AS OTHERWISE NOTED) A. EXTERIOR STUD WALLS: R-19 BATT - MIN

B. INTERIOR STUD PARTITIONS: ACOUSTICAL BATT (FULL HT) C. FLOORS: R-19 BATT - MIN 3. FOR TYPICAL SYMBOLS AND ABBREVIATIONS, REFER TO SHEET G0.01

14. REFER TO MECHANICAL ELELCTRICAL, FIRE ALARM AND TECHNOLOGY DRAWINGS FOR ADDITIONAL REMODEL REQUIREMENTS, TYPICAL. 5. \rarrow FOR TYPICAL TOILET ACCESSORY MOUNTING HEIGHTS & DIMENSIONS SEE dash

16. TRENCHING DEMOLITION IS APPROXIMATE AND NEEDS TO BE COORDINATED WITH ACTUAL FIELI

CONDITIONS AND DETAIL REQUIREMENTS.



WEST COVINA USD

PROJECT NUMBER

220117

DATE


05/09/2023


REVISIONS

NORTH: PLAN TRUE

KEY PLAN

No.	Description	Date
1	ADDENDUM 001	03-07-2024
	DSA BACKCHECK	
	DSA BACKCHECK	
	OVER ALL REMO	DEL
_		
F	Loor Plan - Bl	DG. 7
•		





(E) PLYWOOD SHTG. ——

(E) 3 X 4 PURLINS @ 2'-0"

(E) 5" X 14 5/8" GLU-LAM BM. BEYOND @ 8'-0" O.C. —

(E) 3 X 4 PURLINS @ 2'-0" O.C.

(E) 5" X 14 5/8" GLU-LAM BM. BEYOND @ 8'-0" O.C.

6 TYPICAL HANGER SUPPORT DETAIL
NOTE TO SCALE

(E) PLYWOOD SHTG. -

- 3 X 4 BLKG. W/(2)

- 3 X 4 BLKG. W/(2)

#10X5" W.S. EA. ´ END


- 2 X 2 X14 Ga. ANGLE CLIP W/ 3/8 Ø X 2.5" LAG SCREW

CABLE OR SPLAY WIRE AS REQUIRED FOR MECHANICAL DUCT OR EQUIPMENT BRACING USE 2-CABLE CLIPS FOR CABLE OR 4 TIGHT TURNS FOR SPLAY WIRE


#10X5" W.S. EA.

- 3/8" MIN. HANGER ROD W/ WASHER & NUT T&B OF BLKG.

1 75# MAX



19 LAY IN DIFFUSER CONNECTION DETAIL NOT TO SCALE



4 FLEXIBLE DUCTWORK HANGER DETAIL
NOT TO SCALE

COLUMNIA DE LA COLUMNIA DEL LA COLUMNIA DEL LA COLUMNIA DE LA COLUMNIA DEL LA COLUMNIA DELLA COLUMNIA DELL


				TRANSVE	RSE REINFORCING	(1)	
					AT JOINTS		
DIMENSION OF LONGEST SIDE, INCHES	SHEET METAL GAGE (ALL FOUR SIDES)	MINIMUM REINFORCING ANGLE SIZE AND MAXIMUM LONGITUDINAL SPACING BETWEEN TRANSVERSE JOINTS &/OR INTERMEDIATE REINFORCING	MIN. HT. IN.	DRIVE SLIP PLAIN S SLIP	HEMMED S SLIP	ALTER'NT BAR SLIP	REINFORCED BAR SLIP
				RECOM- MENDED GAGE	RECOM- MENDED GAGE	RECOM- MENDED GAGE	RECOM- MENDED GAGE
UP THRU 12	26	NONE REQUIRED	1	26	26	24	24
13 - 18	24	NONE REQUIRED	1	24	24	24	24
19 - 30	24	1" X 1" X 1/8" @ 60 IN.	1		24	24	24
31 - 42	22	1" X 1" X 1/8" @ 60 IN.	1			22	22
43 - 60	20	1" X 1" X 1/8" @ 60 IN.	1				20
61 & ABOVE	18	1" X 1" X 1/8" @ 60 IN.	1				18

(1) TRANSVERSE REINFORCING SIZE IS DETERMINED BY DIMENSION OF SIDE TO WHICH ANGLE IS APPLIED.


2 DUCT CONSTRUCTION STANDARDS

8163 Rochestser Avenue, Suite 100 Rancho Cucamonga California 91730 P 909-987-0909 CONSULTANT LEAF 8163 Rochester Avenue, Suite 100 Rancho Cucamonga, CA 91730 909.987-0909 leafengineers.com

IUT GROVE







No. Description 1 ADDENDUM 001	Date 03-01-202
1 ADDENDUM 001	03-01-202
DSA BACKCI	IECK
	DETAILO
MECHANICAL	DETAILS

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 91743-0223-0002 Schema Version: rev 20220101 Report Generated: 2023-02-27 16:33:15

School buildings < 25,000 ft² and < 4 stories must install a heat pump water heating system per 140.5(a)1. Water heating systems serving an individual bathroom space may be an instantaneous electric water heater.

CERTIFICATE OF COMPLIANCE

WALNUT GROVE I.S. - Science Lab Modernization | Report Page: (Page 5 of 8) |
Date Prepared: 2023-02-27T19:33:14-05:0

G. DOMESTIC HOT WATER DISTRIBUTION SYSTEM

Mandatory Pipe Insulation All Occupancies

| For systems serving dwelling units, pipe insulation must meet the minimum insulation requirements in Table 160.4-A (see blow) except:
| Piping that penetrates framing members shall not be required to have pipe insulation for the distance of the framing penetration. Piping that penetrates metal framing members
| Piping installed in interior or exterior walls shall not be required to have pipe insulation if all of the requirements are met for compliance with Quality Insulation Installation (QII) as specified in the Reference Residential Appendix RA3.5.
| Piping surrounded with a minimum of 1 inch of wall insulation, 2 inches of cravipspace insulation, or 4 inches of attic insulation, shall not be required to have pipe insulation.

| For systems serving nonresidential spaces, pipe insulation for the following applications is specified to comply with Table 120.3-A (see below) per 120.3:
| Recirculating system piping, including supply and return piping of the water heater
| Piping that perfected from damage, including between storage tank and heat trap, for a nonrecirculating storage system
| Piping that perfected from damage, including that due to sunlight, moisture, equipment maintenance, and wind. Insulation exposed to weather shall be installed with a cover suitable for outdoor service per 120.3(b) / 160.4(f). Pipe insulation buried below grade must be installed in a water proof and non-crushable casing or sleeve.

| TABLE 120.3-A / 160.4-A PIPE INSULATION THICKNESS
| Nominal Pipe Diameter (in) | Insulation Required | Insula

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Report Generated: 2023-02-27 16:33:15

STATE OF CALIFORNIA

Domestic Water Heating System

CERTIFICATE OF COMPLIANCE

Project Name:

WALNUT GROVE I.S. - Science Lab Modernization Report Page:

Date Prepared:

2023-02-27T19:33:14-05:00

J. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE
There are no forms required for this project.

K. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION
There are no forms required for this project.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 91743-0223-0002

Schema Version: per 20220101 Report Generated: 2023-02-27 16:33-15

STATE OF CALIFORNIA

Domestic Water Heating System

CERTIFICATE OF COMPLIANCE

Project Name:

WALNUT GROVE I.S. - Science Lab Modernization

Report Page:
Date Prepared:

2023-02-27T19:33:14-02

Date Prepared:

Date Prepared:

Date Prepared:

E. ADDITIONAL CONDITIONS

This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

E. ADDITIONAL REMARKS

This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

[General Remarks] REPLACEMENT WATER HEATER EQUIPMENT.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Report Generated: 2023-02-27 16:33:15

Domestic Water Heating System

Domestic Water Heating System

Domestic Water Heating System

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

CERTIFICATE OF COMPLIANCE

G. DOMESTIC HOT WATER DISTRIBUTION SYSTEM

This table is used to demonstrate compliance for nonresidential occupancies with distribution requirements in 120.3 and 140.5. For multifamily and hotel/motel occupancies, compliance is demonstrated with requirements 110.3(c), 160.4, 170.2(d).

Recirculation Loops in Central Systems Serving Dwelling Units or Nonresidential Spaces

Yes No Applicable

OLICIA Applicable

Air release valve or vertical pump installation per 110.3(c)4A

OLICIA Applicable

OLICIA APPLICA APPLIC

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 91743-0223-0002 Schema Version: rev 20220101 Report Generated: 2023-02-27 16:33:15

WALNUT GROVE I.S. - Science Lab Modernization Report Page:


Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace


CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 91743-0223-0002 Schema Version: rev 20220101 Report Generated: 2023-02-27 16:33:15

CERTIFICATE OF COMPLIANCE
Project Name: WALNUT GROVE I.S. - Science Lab Modernization | Report Page: (Page 8 of 1 Project Address: Date Prepared: 2023-02-27T19:33:14-05:02 |

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT
I certify that this Certificate of Compliance documentation is accurate and complete.
Documentation Author Name:
Joel Baldovino
Company:
LEAF ENGINEERS
Signature Date: 02/27/2023
LEAF ENGINEERS
Address: CEA/ HERS Certification identification (if applicable):
City/State/Zip: Phone:
RESPONSIBLE PERSON'S DECLARATION STATEMENT
I certify the following under penalty of perjury, under the laws of the State of California:
1. The information provided on this Certificate of Compliance is true and correct.
2. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer)
3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirement of Title 24, Part 1 and Part 6 of the California Code of Regulations.
4. The building design features or system design dentified on othis Certificate of Compliance conform to the requirement of Title 24, Part 1 and Part 6 of the California Code of Regulations.
4. The building design features or system design dentified on this Certificate of Compliance documents, worksheets, calculations, plans and specifications submitted to the enf

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace







8163 Rochestser Avenue, Suite 100
Rancho Cucamonga
California 91730
P 909-987-0909


CONSULTANT

LEAF Engineers

8163 Rochester Avenue, Suite 100
Rancho Cucamonga, CA 91730
909.987-0909
leafengineers.com


UT GROVE I.S. - SCIENCE LAB MOD.


DDRESS:
No.
CA 91790



KEY PLAN







6.01