



SERVICE PROCEDURES:

Materials will not be ordered, and the work will not be scheduled until a payment in full has been received and a contract has been accepted and signed. After the payment is received and the contract has been signed, we will schedule a date to pump down and measure your pool.

Once the pool is measured, we will fax the specifications to the manufacturer and your liner will be ordered. After your new liner has been received at our store, we will call you for an installation appointment.

Liner installations generally take about two days depending on water refilling techniques and present weather conditions. After your new liner is completely installed, we will add the start-up chemicals and return your pool to the proper operating condition provided all the pool equipment is functional.

INSTALLATION INCLUDES:

Draining pool, removing, and disposing of old liner, properly measuring the pool for a custom fit liner, minor preparation of pool walls and bottom, providing and installing a new liner, supervising the refilling of the pool.

Installing new face plates for the skimmers, wall fittings, and floor drains, if your pool has plastic face plates, any metal faceplates are not included. Step seals and light rings are also not included. We will install all new gaskets where the existing gaskets are not usable and replace all stainless-steel screws where necessary.