

PROJECT DESCRIPTION

Project: **Sacred Heart Medical Center Parking Structure #2**
Location: **Springfield, OR**
Design Team: **Structural Engineer - KPFF**
Geotechnical Engineer - Foundation Engineering Inc.
Contractor: **Turner Construction Company**



Construction Notes

Rammed Aggregate Pier® Elements Installed: **680**
Expected Days on Site: **32**
Actual Days on Site: **24**

Soil Profile Summary:

Up to 4' of "Bar Run" fill (cobbles to 4") over variable silty, sandy alluvium, growing softer/looser with depth.
Piers terminated in dense sandy gravel at 10'-16' below grade.

