

Vincent J. Polistina, PE, PP, CME
Craig R. Hurlless, PE, PP, CME
Ronald N. Curcio, PE, PP
Jennifer L. Heller, PP, AICP
Charles J. Kaenzig, PE



Civil / Municipal Engineering
Site Plan and Subdivision Design
Surveying
Land Use Planning
Water and Wastewater Design
Environmental Consulting
Inspection / Construction Management

**CITY OF LINWOOD
ATLANTIC COUNTY, NEW JERSEY**

**ALL WARS MEMORIAL PARK
FIELD HOUSE**

CONTRACT NO. 40

BID DOCUMENT ADDENDUM NO. 5

February 6, 2024

To All Planholders:

Please note the following changes / modifications to the contract documents for the above referenced project. The following addendum is hereby made part of the Bid Documents for the ALL WARS MEMORIAL PARK FIELD HOUSE, CONTRACT NO. 40, as fully and completely as if the same were set forth herein.

**The date for bids to be received for this project is
Wednesday, February 21, 2024 at 10:00 AM.**

Addendum No. 5 includes a modification to the demolition of the existing building, modifications to the lighting control building, clarification on the existing field lighting service feed and revision to the proposed sanitary sewer main installation. Revised architectural plans and revised site plans (Sheets 3, 4 and 5) are attached. Technical Specification No. 19 and new price proposal sheets have been included in this addendum.

The responses below are in reply to questions submitted for the project not previously addressed in Addendum No. 3.

Question #1:

Please provide a drawing reflecting locations / size for any temp fence that will be required due to the foot traffic

PA Response #1:

All work areas shall be enclosed in the temporary construction fence. Trenches shall be backfilled at the end of each work day. All areas to be secured.

Question #2:

It appears on drawing 4 of 6 the existing site light power runs under the new building / Does it remain / relocate

PA Response #2:

See Revised Sheet 4 (Utility Plan) for updated information for electrical work and Item No. 19 Relocation of Existing Field Lighting Service Feed.

Question #3:

Can the Lighting Control Building be designed to re-use existing slab and partial CMU walls holding Electrical Equipment. The amount of underground utilities / others may make it impossible for a new 6" DGA Base with haunch footing and slab along with limited the damage to the existing root system of the adjacent tree.

PA Response #3:

The demolition of the existing building has been revised to address this issue. The architectural plans have been revised accordingly.

Question #4:

The existing electric equipment, at building to be demolished, needs to be protected during construction. Would it be feasible to keep the (1) portion of wall and o.h. door opening to create the new space for equipment? - Suggests to add (2) additional walls, (1) door, and a roof to protect all electrical equipment. – Please Consider/Provide All Details.

PA Response #4:

The demolition of the existing building has been revised to address this issue. The architectural plans have been revised accordingly.

Any additional costs associated with this addendum are to be included in the appropriate costs bid in the proposal.

Please acknowledge your receipt of this clarification by signing below and faxing this form to (609) 646-2949 or via email to jen@polistina.net

Acknowledgment must be received ASAP.

I acknowledge receipt of Addendum No. 4 to Contract No. 40 of the City of Linwood.

Signature

Date

Print Name

Print Name of Company

PROPOSAL

to the

CITY OF LINWOOD
ATLANTIC COUNTY, NEW JERSEY

ALL WARS MEMORIAL PARK FIELD HOUSE

CONTRACT NO. 40

Item 1 MOBILIZATION & PERMITS

1 LUMP SUM @ \$ _____

(Write Unit Price)

\$ _____

Item 2 CLEARING SITE

1 LUMP SUM @ \$ _____

(Write Unit Price)

\$ _____

Item 3 CONSTRUCTION LAYOUT

1 LUMP SUM @ \$ _____

(Write Unit Price)

\$ _____

Item 4 SAWCUTTING

200 LINEAR FEET @ \$ _____ per LF

(Write Unit Price)

\$ _____

Item 5 8" PVC SDR-35 SANITARY SEWER MAIN

518 LINEAR FEET @ \$ _____ per LF

(Write Unit Price)

\$ _____

Item 6 6" PVC SDR-35, SANITARY SEWER LATERAL WITH CLEANOUT RISERS

1 UNIT @ \$ _____ per UNIT

\$ _____

(Write Unit Price)

Item 7 SANITARY SEWER DOGHOUSE MANHOLE (0-6' DEEP)

1 UNIT @ \$ _____ per UNIT

\$ _____

(Write Unit Price)

Item 8 SANITARY SEWER MANHOLE (0' - 6' DEEP)

3 UNITS @ \$ _____ per UNIT

\$ _____

(Write Unit Price)

Item 9 8" DIA. CORE DRILL CONNECTION

1 UNIT @ \$ _____ per UNIT

\$ _____

(Write Unit Price)

Item 10 3/4" CRUSHED STONE BEDDING, IF & WHERE DIRECTED

50 CY @ \$ _____ per CUBIC YARD

\$ _____

(Write Unit Price)

Item 11 SELECT BACKFILL, IF & WHERE DIRECTED

500 CY @ \$ _____ per CUBIC YARD

\$ _____

(Write Unit Price)

Item 12 TEMPORARY ROAD RESTORATION

ELIMINATED FROM CONTRACT

_____ \$ _____
(Write Unit Price)

Item 13 CONCRETE GUTTER, 8" THICK

ELIMINATED FROM CONTRACT

_____ \$ _____
(Write Unit Price)

Item 14 HOT MIX ASPHALT WALKWAY, 2" THICK

660 SQUARE YARDS @ \$ _____ per SY

_____ \$ _____
(Write Unit Price)

Item 15 CONCRETE PAVERS

555 SQUARE YARDS @ \$ _____ per SY

_____ \$ _____
(Write Unit Price)

Item 16 TRAFFIC MARKINGS, THERMOPLASTIC

ELIMINATED FROM CONTRACT

_____ \$ _____
(Write Unit Price)

Item 17 TOP SOIL, FERTILIZE & SEED

200 SQUARE YARDS @ \$ _____ per SY

_____ \$ _____
(Write Unit Price)

Item 18 FIELDHOUSE BUILDING

1 LUMP SUM @ \$ _____

(Write Unit Price)

\$ _____

Item 19 RELOCATION OF EXISTING FIELD LIGHTING SERVICE FEED

1 LUMP SUM @ \$ _____

(Write Unit Price)

\$ _____

**TOTAL BASE BID (Items 1 through 19)
THE TOTAL PRICE OF:**

(Write Total Price in Words and Numbers)

\$ _____

ITEM NO. 19 – RELOCATION OF EXISTING FIELD LIGHTING SERVICE FEED

DESCRIPTION

The scope of work included under this item shall include the excavation and installation of all electrical conduits, fittings, junction boxes and wiring from the existing recreational building to the closest field light pole. The Contractor shall be responsible to de-energize the electrical feed servicing the recreational building, including coordination with Atlantic City Electrical if necessary.

As shown on the design plans, the Contractor shall extend an rigid PVC Schedule 40 conduit from the existing building to the approximate location of the existing in-ground junction box situated near the closest field light pole. The existing in-ground junction box shall be replaced with a new in-ground junction box, a Quazite type or approved equal. The Contractor shall provide and install the properly sized conductors for the required load, between the existing field house building and the new in-ground junction box. The Contractor shall re-route the existing wiring from the field light pole to the new Quazite type in-ground junction box. All connections made between the wiring from the field light pole and new conductors installed from the existing recreational building shall be made and secured in water-tight connections. All electrical terminations and connections shall be made in accordance with the latest revision of the NEC.

The routing of the proposed conduit shall be aligned to avoid the footprint of the proposed field house building and any other structures, or decorative structures located within the immediate area of the work.

The Contractor shall acquire all necessary permits and furnish all necessary bonds, fees, etc. as required to satisfy the respective local, county, state or federal governing agencies. The Contractor shall be responsible to coordinate the electrical service interruption with Atlantic City Electric, as required.

All wiring shall be type THHN/THWN and properly sized to accommodate the anticipate electrical load.

The Contractor shall be responsible to provide signed and sealed engineering drawings to the City for electrical review and approval by the Building Code Official. The Contractor is to obtain the services of an Electrical Engineer to provide the required documentation for submission to the City.

All work shall be completed to the lines, grades and elevations as shown on the Contract Drawings.

The work shall be completed in accordance with the following specifications and in compliance with the latest version of the NEC.

SECTION 260543

UNDERGROUND DUCTS AND RACEWAYS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 1. Conduit, ducts, and duct accessories for duct banks.
 2. Handholes and pull boxes.
 3. Manholes.

1.3 DEFINITION

- A. RNC: Rigid nonmetallic conduit.
- B. PVC: Polyvinyl Chloride conduit.

1.4 SUBMITTALS

- A. Product Data: For the following:
 1. Duct-bank materials, including separators and miscellaneous components.
 2. Ducts and conduits and their accessories, including elbows, end bells, bends, fittings, and solvent cement.
 3. Accessories for manholes, handholes, pull boxes, and other utility structures.
 4. Warning tape.
 5. Warning planks.
- B. Shop Drawings for Precast or Factory-Fabricated Underground Utility Structures: Include plans, elevations, sections, details, attachments to other work, and accessories, including the following:
 1. Duct entry provisions, including locations and duct sizes.
 2. Reinforcement details.
 3. Frame and cover design and manhole frame support rings.
 4. Grounding details.
 5. Dimensioned locations of cable rack inserts, pulling-in and lifting irons, and sumps.
 6. Joint details.
- C. Shop Drawings for Factory-Fabricated Handholes and Pull Boxes Other Than Precast Concrete: Include dimensioned plans, sections, and elevations, and fabrication and installation details, including the following:
 1. Duct entry provisions, including locations and duct sizes.
 2. Cover design.
 3. Grounding details.
 4. Dimensioned locations of cable rack inserts, and pulling-in and lifting irons.

- D. Duct-Bank Coordination Drawings: Show duct profiles and coordination with other utilities and underground structures.
 - 1. Include plans and sections, drawn to scale, and show bends and locations of expansion fittings.
 - 2. Drawings shall be signed and sealed by a qualified professional engineer.
- E. Product Certificates: For concrete and steel used in precast concrete manholes, pull boxes and handholes, comply with ASTM C 858.
- F. Qualification Data: For qualified professional engineer and testing agency.
- G. Source quality-control reports.
- H. Field quality-control reports.

1.5 QUALITY ASSURANCE

- A. Comply with IEEE C2.
- B. Comply with NFPA 70.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver ducts to Project site with ends capped. Store nonmetallic ducts with supports to prevent bending, warping, and deforming.
- B. Store precast concrete and other factory-fabricated underground utility structures at Project site as recommended by manufacturer to prevent physical damage. Arrange so identification markings are visible.
- C. Lift and support precast concrete units only at designated lifting or supporting points.

1.7 PROJECT CONDITIONS

- A. Interruption of Existing Electrical Service: Do not interrupt electrical service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electrical service according to requirements indicated:
 - 1. Notify Engineer no fewer than two days in advance of proposed interruption of electrical service.
 - 2. Do not proceed with interruption of electrical service without Engineer's written permission.

1.8 COORDINATION

- A. Coordinate layout and installation of ducts, manholes, handholes, and pull boxes with final arrangement of other utilities, site grading, and surface features as determined in the field.

- B. Coordinate elevations of ducts and duct-bank entrances into manholes, handholes, and pull boxes with final locations and profiles of ducts and duct banks as determined by coordination with other utilities, underground obstructions, and surface features. Revise locations and elevations from those indicated as required to suit field conditions and to ensure that duct runs drain to manholes and handholes, and as approved by Architect.

1.9 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
- B. Furnish cable-support stanchions, arms, insulators, and associated fasteners in quantities equal to 5 percent of quantity of each item installed.

PART 2 - PRODUCTS

2.1 CONDUIT

- A. Rigid Steel Conduit: Galvanized. Comply with ANSI C80.1.
- B. RNC: NEMA TC 2, Type EPC-40-PVC of Type EPC-80-PVC, UL 651, with matching fittings by same manufacturer as the conduit, complying with NEMA TC 3 and UL 514B.

2.2 NONMETALLIC DUCTS AND DUCT ACCESSORIES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- B. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
 - 1. AFC Cable Systems.
 - 2. ARNCO Corporation.
 - 3. Beck Manufacturing.
 - 4. Cantex, Inc.
 - 5. CertainTeed Corp.
 - 6. Condux International, Inc.
 - 7. DCX-CHOL Enterprises, Inc.; ELECSYS Division.
 - 8. Electri-Flex Company.
 - 9. IPEX Inc.
 - 10. Lamson & Sessions; Carlon Electrical Products.
 - 11. Manhattan Wire Products; a Belden company.
- C. Underground Plastic Utilities Duct: NEMA TC 6 & 8, Type EB-20-PVC, ASTM F 512, UL 651A, with matching fittings by the same manufacturer as the duct, complying with NEMA TC 9.
- D. Underground Plastic Utilities Duct: NEMA TC 6 & 8, Type DB-60-PVC and Type DB-120-PVC, ASTM F 512, with matching fittings by the same manufacturer as the duct, complying with NEMA TC 9.

- E. Duct Accessories:
1. Duct Separators: Factory-fabricated rigid PVC interlocking spacers, sized for type and sizes of ducts with which used, and retained to provide minimum duct spacings indicated while supporting ducts during concreting or backfilling.
 2. Warning Tape: Underground-line warning tape specified in Division 26 Section "Identification for Electrical Systems."
 3. Concrete Warning Planks: Nominal 12 by 24 by 3 inches in size, manufactured from 6000-psi concrete.
 - a. Color: Red dye added to concrete during batching.
 - b. Mark each plank with "ELECTRIC" in 2-inch- high, 3/8-inch- deep letters.

2.3 PRECAST CONCRETE HANDHOLES AND PULL BOXES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Christy Concrete Products.
 2. Cretex Concrete Products West, Inc.; Riverton Division.
 3. Elmhurst-Chicago Stone Co.
 4. Oldcastle Precast Group.
 5. Oldcastle Precast Inc.; Utility Vault Division.
 6. Utility Concrete Products, LLC.
 7. Wausau Tile Inc.
- B. Comply with ASTM C 858 for design and manufacturing processes.
- C. Ferrous metal hardware shall be hot-dip galvanized in accordance with ASTM A153 and ASTM A123.
- D. Description: Factory-fabricated, reinforced-concrete, monolithically poured walls and bottom unless open-bottom enclosures are indicated. Frame and cover shall form top of enclosure and shall have load rating consistent with that of handhole or pull box.
1. Frame and Cover: Weatherproof cast-iron frame, with cast-iron cover with recessed cover hook eyes and tamper-resistant, captive, cover-securing stainless-steel bolts.
 2. Frame and Cover: Weatherproof steel frame, with steel cover with recessed cover hook eyes and tamper-resistant, captive, cover-securing stainless-steel bolts.
 3. Frame and Cover: Weatherproof steel frame, with hinged steel access door assembly with tamper-resistant, captive, cover-securing stainless-steel bolts.
 - a. Cover Hinges: Concealed, with hold-open ratchet assembly.
 - b. Cover Handle: Recessed.
 4. Frame and Cover: Weatherproof aluminum frame with hinged aluminum access door assembly with tamper-resistant, captive, cover-securing stainless-steel bolts.
 - a. Cover Hinges: Concealed, with hold-open ratchet assembly.
 - b. Cover Handle: Recessed.
 5. Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
 6. Cover Legend: Molded lettering, "ELECTRIC."

7. Configuration: Units shall be designed for flush burial and have closed bottom unless otherwise indicated.
8. Extensions and Slabs: Designed to mate with bottom of enclosure. Same material as enclosure.
 - a. Extension shall provide increased depth of 12 inches Slab: Same dimensions as bottom of enclosure, and arranged to provide closure.
9. Windows: Precast openings in walls, arranged to match dimensions and elevations of approaching ducts and duct banks plus an additional 12 inches vertically and horizontally to accommodate alignment variations.
 - a. Windows shall be located no less than 6 inches from interior surfaces of walls, floors, or frames and covers of handholes, but close enough to corners to facilitate racking of cables on walls.
 - b. Window opening shall have cast-in-place, welded wire fabric reinforcement for field cutting and bending to tie in to concrete envelopes of duct banks.
 - c. Window openings shall be framed with at least two additional No. 4 steel reinforcing bars in concrete around each opening.
10. Duct Entrances in Handhole Walls: Cast end-bell or duct-terminating fitting in wall for each entering duct.
 - a. Type and size shall match fittings to duct or conduit to be terminated.
 - b. Fittings shall align with elevations of approaching ducts and be located near interior corners of handholes to facilitate racking of cable.
11. Handholes 12 inches wide by 24 inches long and larger shall have inserts for cable racks and pulling-in irons installed before concrete is poured.

2.4 HANDHOLES AND PULL BOXES OTHER THAN PRECAST CONCRETE

A. Description: Comply with SCTE 77.

1. Color: Gray.
2. Configuration: Units shall be designed for flush burial and have closed bottom unless otherwise indicated.
3. Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure.
4. Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
5. Cover Legend: Molded lettering,
 - a. "ELECTRIC."
 - b. Tier level number, indicating that the unit complies with the structural load test for that tier according to SCTE 77.
6. Direct-Buried Wiring Entrance Provisions: Knockouts equipped with insulated bushings or end-bell fittings, retained to suit box material, sized for wiring indicated, and arranged for secure, fixed installation in enclosure wall.
7. Duct Entrance Provisions: Duct-terminating fittings shall mate with entering ducts for secure, fixed installation in enclosure wall.
8. Handholes 12 inches wide by 24 inches long and larger shall have factory-installed inserts for cable racks and pulling-in irons.

- B. Polymer Concrete Handholes and Pull Boxes with Polymer Concrete Cover: Molded of sand and aggregate, bound together with a polymer resin, and reinforced with steel or fiberglass or a combination of the two. Handholes and pull boxes shall comply with the requirements of SCTE 7 Tier 5 loading.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 2. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
 - a. Armorcast Products Company.
 - b. Carson Industries LLC.
 - c. CDR Systems Corporation.
 - d. Hubbell Power Systems; Lenoir City Division.
 - e. NewBasis.
- C. Fiberglass Handholes and Pull Boxes with Polymer Concrete Frame and Cover: Complying with SCTE 77 Tier 5 loading. Sheet-molded, fiberglass-reinforced, polyester resin enclosure joined to polymer concrete top ring or frame.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 2. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
 - a. Armorcast Products Company.
 - b. Carson Industries LLC.
 - c. Christy Concrete Products.
 - d. Synertech Moulded Products, Inc.; a division of Oldcastle Precast.
- D. Fiberglass Handholes and Pull Boxes: Molded of fiberglass-reinforced polyester resin, with covers of polymer concrete, complying with SCTE 77 Tier 5 loading.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 2. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
 - a. Carson Industries LLC.
 - b. Christy Concrete Products.
 - c. Nordic Fiberglass, Inc.
- E. High-Density Plastic Pull Boxes: Injection molded of high-density polyethylene or copolymer-polypropylene, complying with SCTE 77 Tier 5 loading. Cover shall be polymer concrete.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

2. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
 - a. Carson Industries LLC.
 - b. Nordic Fiberglass, Inc.
 - c. Pencil Plastics.

2.5 PRECAST MANHOLES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 1. Christy Concrete Products.
 2. Cretex Concrete Products West, Inc.; Riverton Division.
 3. Elmhurst-Chicago Stone Co.
 4. Oldcastle Precast Group.
 5. Oldcastle Precast Inc.; Utility Vault Division.
 6. Utility Concrete Products, LLC.
 7. Wausau Tile Inc.
- B. Comply with ASTM C 858, with structural design loading as specified in "Underground Enclosure Application" Article, and with interlocking mating sections, complete with accessories, hardware, and features.
 1. Windows: Precast openings in walls, arranged to match dimensions and elevations of approaching ducts and duct banks plus an additional 12 inches vertically and horizontally to accommodate alignment variations.
 - a. Windows shall be located no less than 6 inches from interior surfaces of walls, floors, or roofs of manholes, but close enough to corners to facilitate racking of cables on walls.
 - b. Window opening shall have cast-in-place, welded wire fabric reinforcement for field cutting and bending to tie in to concrete envelopes of duct banks.
 - c. Window openings shall be framed with at least two additional No. 4 steel reinforcing bars in concrete around each opening.
 2. Duct Entrances in Manhole Walls: Cast end-bell or duct-terminating fitting in wall for each entering duct.
 - a. Type and size shall match fittings to duct or conduit to be terminated.
 - b. Fittings shall align with elevations of approaching ducts and be located near interior corners of manholes to facilitate racking of cable.
- C. Concrete Knockout Panels: 1-1/2 to 2 inches thick, for future conduit entrance and sleeve for ground rod.
- D. Joint Sealant: Asphaltic-butyl material with adhesion, cohesion, flexibility, and durability properties necessary to withstand maximum hydrostatic pressures at the installation location with the ground-water level at grade.

2.6 CAST-IN-PLACE MANHOLES

- A. Description: Underground utility structures, constructed in place, complete with accessories, hardware, and features. Include concrete knockout panels for conduit entrance and sleeve for ground rod.
- B. Materials: Comply with ASTM C 858 and with Division 03 Section "Cast-in-Place Concrete."
 - 1. Concrete shall have a minimum compressive strength of 3000 psi.
- C. Structural Design Loading: As specified in "Underground Enclosure Application" Article.

2.7 UTILITY STRUCTURE ACCESSORIES

- A. Manufacturers: Subject to compliance with requirements available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Bilco Company (The).
 - 2. Campbell Foundry Company.
 - 3. Christy Concrete Products.
 - 4. Cretex Concrete Products West, Inc.; Riverton Division.
 - 5. East Jordan Iron Works.
 - 6. Elmhurst-Chicago Stone Co.
 - 7. Hubbell Power Systems; Lenoir City Division.
 - 8. McKinley Iron Works.
 - 9. Neenah Foundry Company.
 - 10. NewBasis.
 - 11. Oldcastle Precast Group.
 - 12. Oldcastle Precast Inc.; Utility Vault Division.
 - 13. Osburn Associates, Inc.
 - 14. Pennsylvania Insert Corporation.
 - 15. Underground Devices, Inc.
 - 16. Utility Concrete Products, LLC.
 - 17. Wausau Tile Inc.
- B. Ferrous metal hardware, where indicated, shall be hot-dip galvanized complying with ASTM A 153 and A 123.
- C. Manhole Frames, Covers, and Chimney Components: Comply with structural design loading specified for manhole.
 - 1. Frame and Cover: Weatherproof, gray cast iron complying with ASTM A 48/A 48M, Class 30B with milled cover-to-frame bearing surfaces; diameter, 29 inches.
 - a. Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
 - b. Special Covers: Recess in face of cover designed to accept finish material in paved areas.

2. Cover Legend: Cast in. Retained to suit system.
 - a. Legend: "ELECTRIC-LV" for duct systems with power wires and cables for systems operating at 600 V and less.
 - b. Legend: "ELECTRIC-HV" for duct systems with medium-voltage cables.
 - c. Legend: "SIGNAL" for communications, data, and telephone duct systems.
 3. Manhole Chimney Components: Precast concrete rings with dimensions matched to those of roof opening.
 - a. Mortar for Chimney Ring and Frame and Cover Joints: Comply with ASTM C 270, Type M, except for quantities less than 2.0 cu. ft. where packaged mix complying with ASTM C 387/C 387M, Type M, may be used.
- D. Manhole Sump Frame and Grate: ASTM A 48/A 48M, Class 30B, gray cast iron.
- E. Pulling Eyes in Concrete Walls: Eyebolt with reinforcing-bar fastening insert, 2-inch-diameter eye, and 1-by-4-inch bolt.
 1. Working Load Embedded in 6-Inch, 4000-psi Concrete: 13,000-lbf minimum tension.
- F. Pulling Eyes in Nonconcrete Walls: Eyebolt with reinforced fastening, 1-1/4-inch-diameter eye, rated 2500-lbf minimum tension.
- G. Pulling-In and Lifting Irons in Concrete Floors: 7/8-inch- diameter, hot-dip galvanized, bent steel rod; stress relieved after forming; and fastened to reinforcing rod. Exposed triangular opening.
 1. Ultimate Yield Strength: 40,000-lbf shear and 60,000-lbf tension.
- H. Bolting Inserts for Concrete Utility Structure Cable Racks and Other Attachments: Flared, threaded inserts of noncorrosive, chemical-resistant, nonconductive thermoplastic material; 1/2-inch ID by 2-3/4 inches deep, flared to 1-1/4 inches minimum at base.
 1. Tested Ultimate Pullout Strength: 12,000 lbf minimum.
- I. Expansion Anchors for Installation after Concrete Is Cast: Zinc-plated, carbon-steel-wedge type with stainless-steel expander clip with 1/2-inch bolt, 5300-lbf rated pullout strength, and minimum 6800-lbf rated shear strength.
- J. Cable Rack Assembly: Steel, hot-rolled galvanized except insulators.
 1. Stanchions: T-section or channel; 2-1/4-inch nominal size; punched with 14 holes on 1-1/2-inch centers for cable-arm attachment.
 2. Arms: 1-1/2 inches wide, lengths ranging from 3 inches with 450-lb minimum capacity to 18 inches with 250-lb minimum capacity. Arms shall have slots along full length for cable ties and be arranged for secure mounting in horizontal position at any vertical location on stanchions.

3. Insulators: High-glaze, wet-process porcelain arranged for mounting on cable arms.
- K. Cable Rack Assembly: Nonmetallic. Components fabricated from nonconductive, fiberglass-reinforced polymer.
1. Stanchions: Nominal 36 inches high by 4 inches wide, with minimum of 9 holes for arm attachment.
 2. Arms: Arranged for secure, drop-in attachment in horizontal position at any location on cable stanchions, and capable of being locked in position. Arms shall be available in lengths ranging from 3 inches with 450-lb minimum capacity to 20 inches with 250-lb minimum capacity. Top of arm shall be nominally 4 inches wide, and arm shall have slots along full length for cable ties.
- L. Duct-Sealing Compound: Nonhardening, safe for contact with human skin, not deleterious to cable insulation, and workable at temperatures as low as 35 deg F. Capable of withstanding temperature of 300 deg F without slump and adhering to clean surfaces of plastic ducts, metallic conduits, conduit coatings, concrete, masonry, lead, cable sheaths, cable jackets, insulation materials, and common metals.
- M. Fixed Manhole Ladders: Arranged for attachment to roof of manhole. Ladder and mounting brackets and braces shall be fabricated from nonconductive.
- N. Portable Manhole Ladders: UL-listed, heavy-duty wood specifically designed for portable use for access to electrical manholes. Minimum length equal to distance from deepest manhole floor to grade plus 36 inches.
- O. Cover Hooks: Heavy duty, designed for lifts 60 lbf and greater] [Light duty, designed for lifts less than 60 lbf.

2.8 SOURCE QUALITY CONTROL

- A. Test and inspect precast concrete utility structures according to ASTM C 1037.
- B. Nonconcrete Handhole and Pull Box Prototype Test: Test prototypes of manholes and pull boxes for compliance with SCTE 77. Strength tests shall be for specified Tier ratings of products supplied.
 1. Testing Agency: Engage a qualified testing agency to evaluate nonconcrete handholes and pull boxes.
 2. Testing machine pressure gages shall have current calibration certification complying with ISO 9000 and ISO 10012, and traceable to NIST standards.

PART 3 - EXECUTION

3.1 CORROSION PROTECTION

- A. Aluminum shall not be installed in contact with earth or concrete.

3.2 UNDERGROUND DUCT APPLICATION

- A. Ducts for Electrical Cables over 600 V: RNC, NEMA Type EPC-80-PVC, in concrete-encased duct bank unless otherwise indicated.

- B. Ducts for Electrical Feeders 600 V and Less: RNC, NEMA Type EPC-80-PVC, in concrete-encased duct bank unless otherwise indicated.
- C. Ducts for Electrical Feeders 600 V and Less: RNC, NEMA Type EPC-80-PVC, in direct-buried duct bank unless otherwise indicated.
- D. Ducts for Electrical Branch Circuits: RNC, NEMA Type EPC-80-PVC, in direct-buried duct bank unless otherwise indicated.
- E. Underground Ducts for Telephone, Communications, or Data Utility Service Cables: RNC, NEMA Type EPC-40-PVC, in concrete-encased duct bank unless otherwise indicated.
- F. Underground Ducts for Telephone, Communications, or Data Utility Service Cables: RNC, NEMA Type EPC-40-PVC installed in direct-buried duct bank unless otherwise indicated.
- G. Underground Ducts for Telephone, Communications, or Data Circuits: RNC, NEMA Type EPC-40-PVC, in direct-buried duct bank unless otherwise indicated.
- H. Underground Ducts for Telephone, Communications, or Data Circuits: RNC, NEMA Type EB-20-PVC, in concrete-encased duct bank unless otherwise indicated.
- I. Underground Ducts Crossing Paved Paths, Walks and Driveways: RNC, NEMA Type EPC-40-PVC, encased in reinforced concrete.

3.3 UNDERGROUND ENCLOSURE APPLICATION

- A. Handholes and Pull Boxes for 600 V and Less
 - 1. Units in Roadways and Other Deliberate Traffic Paths: Precast concrete, AASHTO HB 17, H-20 structural load rating.
 - 2. Units in Driveway, Parking Lot, and Off-Roadway Locations, Subject to Occasional, Nondeliberate Loading by Heavy Vehicles: Precast concrete, AASHTO HB 17, H-20 structural load rating.
 - 3. Units in Sidewalk and Similar Applications with a Safety Factor for Nondeliberate Loading by Vehicles: Precast concrete, AASHTO HB 17, H-10 structural load rating.
 - 4. Units Subject to Light-Duty Pedestrian Traffic Only: Fiberglass-reinforced polyester resin, structurally tested according to SCTE 77 with 3000-lbf "Light-Duty" vertical loading.
- B. Manholes: Precast concrete.
 - 1. Units Located in Roadways and Other Deliberate Traffic Paths by Heavy or Medium Vehicles: H-20 structural load rating according to AASHTO HB 17.
 - 2. Units Not Located in Deliberate Traffic Paths by Heavy or Medium Vehicles: H-10 load rating according to AASHTO HB 17.

3.4 EARTHWORK

- A. Excavation and Backfill: Comply with Division 31 Section "Earth Moving," but do not use heavy-duty, hydraulic-operated, compaction equipment.
- B. Restore surface features at areas disturbed by excavation and reestablish original grades unless otherwise indicated. Replace removed sod immediately after backfilling is completed.

- C. Restore areas disturbed by trenching, storing of dirt, cable laying, and other work. Restore vegetation and include necessary topsoiling, fertilizing, liming, seeding, sodding, sprigging, and mulching. Comply with Division 32 Sections "Turf and Grasses" and "Plants."
- D. Cut and patch existing pavement in the path of underground ducts and utility structures according to Division 01 Section "Cutting and Patching."

3.5 DUCT INSTALLATION

- A. Slope: Pitch ducts a minimum slope of 1:300 down toward manholes and handholes and away from buildings and equipment. Slope ducts from a high point in runs between two manholes to drain in both directions.
- B. Curves and Bends: Use 5-degree angle couplings for small changes in direction. Use manufactured long sweep bends with a minimum radius of 48 inches, both horizontally and vertically, at other locations unless otherwise indicated.
- C. Joints: Use solvent-cemented joints in ducts and fittings and make watertight according to manufacturer's written instructions. Stagger couplings so those of adjacent ducts do not lie in same plane.
- D. Duct Entrances to Manholes and Concrete and Polymer Concrete Handholes: Use end bells, spaced approximately 10 inches o.c. for 5-inch ducts, and vary proportionately for other duct sizes.
 - 1. Begin change from regular spacing to end-bell spacing 10 ft. from the end bell without reducing duct line slope and without forming a trap in the line.
 - 2. Direct-Buried Duct Banks: Install an expansion and deflection fitting in each conduit in the area of disturbed earth adjacent to manhole or handhole.
 - 3. Grout end bells into structure walls from both sides to provide watertight entrances.
- E. Building Wall Penetrations: Make a transition from underground duct to rigid steel conduit at least 10 ft. outside the building wall without reducing duct line slope away from the building and without forming a trap in the line. Use fittings manufactured for duct-to-conduit transition. Install conduit penetrations of building walls as specified in Division 26 Section "Common Work Results for Electrical."
- F. Sealing: Provide temporary closure at terminations of ducts that have cables pulled. Seal spare ducts at terminations. Use sealing compound and plugs to withstand at least 15-psig hydrostatic pressure.
- G. Pulling Cord: Install 100-lbf- test nylon cord in ducts, including spares.
- H. Concrete-Encased Ducts: Support ducts on duct separators.
 - 1. Separator Installation: Space separators close enough to prevent sagging and deforming of ducts, with not less than 5 spacers per 20 ft. of duct. Secure separators to earth and to ducts to prevent floating during concreting. Stagger

- separators approximately 6 inches between tiers. Tie entire assembly together using fabric straps; do not use tie wires or reinforcing steel that may form conductive or magnetic loops around ducts or duct groups.
2. Concreting Sequence: Pour each run of envelope between manholes or other terminations in one continuous operation.
 - a. Start at one end and finish at the other, allowing for expansion and contraction of ducts as their temperature changes during and after the pour. Use expansion fittings installed according to manufacturer's written recommendations, or use other specific measures to prevent expansion-contraction damage.
 - b. If more than one pour is necessary, terminate each pour in a vertical plane and install 3/4-inch reinforcing rod dowels extending 18 inches into concrete on both sides of joint near corners of envelope.
 3. Pouring Concrete: Spade concrete carefully during pours to prevent voids under and between conduits and at exterior surface of envelope. Do not allow a heavy mass of concrete to fall directly onto ducts. Use a plank to direct concrete down sides of bank assembly to trench bottom. Allow concrete to flow to center of bank and rise up in middle, uniformly filling all open spaces. Do not use power-driven agitating equipment unless specifically designed for duct-bank application.
 4. Reinforcement: Reinforce concrete-encased duct banks where they cross disturbed earth and where indicated. Arrange reinforcing rods and ties without forming conductive or magnetic loops around ducts or duct groups.
 5. Forms: Use walls of trench to form side walls of duct bank where soil is self-supporting and concrete envelope can be poured without soil inclusions; otherwise, use forms.
 6. Minimum Space between Ducts: 3 inches between ducts and exterior envelope wall, 2 inches between ducts for like services, and 4 inches between power and signal ducts.
 7. Depth: Install top of duct bank at least 24 inches below finished grade in areas not subject to deliberate traffic, and at least 30 inches below finished grade in deliberate traffic paths for vehicles unless otherwise indicated.
 8. Stub-Ups: Use manufactured duct elbows for stub-ups at poles and equipment and at building entrances through the floor unless otherwise indicated. Extend concrete encasement throughout the length of the elbow.
 9. Stub-Ups: Use manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through the floor.
 - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches of concrete.
 - b. Stub-Ups to Equipment: For equipment mounted on outdoor concrete bases, extend steel conduit horizontally a minimum of 60 inches from edge of base. Install insulated grounding bushings on terminations at equipment.
 10. Warning Tape: Bury warning tape approximately 12 inches above all concrete-encased ducts and duct banks. Align tape parallel to and within 3 inches of the centerline of duct bank. Provide an additional warning tape for each 12-inch increment of duct-bank width over a nominal 18 inches. Space additional tapes 12 inches apart, horizontally.

- I. Direct-Buried Duct Banks:
 1. Support ducts on duct separators coordinated with duct size, duct spacing, and outdoor temperature.
 2. Space separators close enough to prevent sagging and deforming of ducts, with not less than 5 spacers per 20 ft. of duct. Secure separators to earth and to ducts to prevent displacement during backfill and yet permit linear duct movement due to expansion and contraction as temperature changes. Stagger spacers approximately 6 inches between tiers.
 3. Excavate trench bottom to provide firm and uniform support for duct bank. Prepare trench bottoms as specified in Division 31 Section "Earth Moving" for pipes less than 6 inches in nominal diameter.
 4. Install backfill as specified in Division 31 Section "Earth Moving."
 5. After installing first tier of ducts, backfill and compact. Start at tie-in point and work toward end of duct run, leaving ducts at end of run free to move with expansion and contraction as temperature changes during this process. Repeat procedure after placing each tier. After placing last tier, hand-place backfill to 4 inches over ducts and hand tamp. Firmly tamp backfill around ducts to provide maximum supporting strength. Use hand tamper only. After placing controlled backfill over final tier, make final duct connections at end of run and complete backfilling with normal compaction as specified in Division 31 Section "Earth Moving."
 6. Install ducts with a minimum of 3 inches between ducts for like services and 6 inches between power and signal ducts.
 7. Depth: Install top of duct bank at least 36 inches below finished grade unless otherwise indicated.
 8. Set elevation of bottom of duct bank below the frost line.
 9. Install manufactured duct elbows for stub-ups at poles and equipment and at building entrances through the floor unless otherwise indicated. Encase elbows for stub-up ducts throughout the length of the elbow.
 10. Install manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through the floor.
 - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches of concrete.
 - b. For equipment mounted on outdoor concrete bases, extend steel conduit horizontally a minimum of 60 inches from edge of equipment pad or foundation. Install insulated grounding bushings on terminations at equipment.
 11. Warning Planks: Bury warning planks approximately 12 inches above direct-buried ducts and duct banks, placing them 24 inches o.c. Align planks along the width and along the centerline of duct bank. Provide an additional plank for each 12-inch increment of duct-bank width over a nominal 18 inches. Space additional planks 12 inches apart, horizontally.

3.6 INSTALLATION OF CONCRETE MANHOLES, HANDHOLES, AND PULL BOXES

A. Cast-in-Place Manhole Installation:

1. Finish interior surfaces with a smooth-troweled finish.
2. Windows for Future Duct Connections: Form and pour concrete knockout panels 1-1/2- to 2- inches- thick, arranged as indicated.
3. Cast-in-place concrete, formwork, and reinforcement are specified in Division 03 Section "Cast-in-Place Concrete."

B. Precast Concrete Handhole and Manhole Installation:

1. Comply with ASTM C 891 unless otherwise indicated.
2. Install units level and plumb and with orientation and depth coordinated with connecting ducts to minimize bends and deflections required for proper entrances.
3. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.

C. Elevations:

1. Manhole Roof: Install with rooftop at least 15 inches below finished grade.
2. Manhole Frame: In paved areas and trafficways, set frames flush with finished grade. Set other manhole frames 1 inch above finished grade.
3. Install handholes with bottom below the frost line, 36" below grade.
4. Handhole Covers: In paved areas and trafficways, set surface flush with finished grade. Set covers of other handholes 1 inch above finished grade.
5. Where indicated, cast handhole cover frame integrally with handhole structure.

D. Drainage: Install drains in bottom of manholes where indicated. Coordinate with drainage provisions indicated.

E. Manhole Access: Circular opening in manhole roof; sized to match cover size.

1. Manholes with Fixed Ladders: Offset access opening from manhole centerlines to align with ladder.
2. Install chimney, constructed of precast concrete collars and rings to support frame and cover and to connect cover with manhole roof opening. Provide moisture-tight masonry joints and waterproof grouting for cast-iron frame to chimney.

F. Waterproofing: Apply waterproofing to exterior surfaces of manholes and handholes after concrete has cured at least three days. Waterproofing materials and installation are specified in Division 07 Section "Elastomeric Sheet Waterproofing" After ducts have been connected and grouted, and before backfilling, waterproof joints and connections and touch up abrasions and scars. Waterproof exterior of manhole chimneys after mortar has cured at least three days.

G. Dampproofing: Apply dampproofing to exterior surfaces of manholes and handholes after concrete has cured at least three days. Dampproofing materials and installation are specified in Division 07 Section "Bituminous Dampproofing." After ducts have been connected and grouted, and before backfilling, dampproof joints and connections and

touch up abrasions and scars. Dampproof exterior of manhole chimneys after mortar has cured at least three days.

- H. Hardware: Install removable hardware, including pulling eyes, cable stanchions, and cable arms, and insulators, as required for installation and support of cables and conductors and as indicated.
- I. Fixed Manhole Ladders: Arrange to provide for safe entry with maximum clearance from cables and other items in manholes.
- J. Field-Installed Bolting Anchors in Manholes and Concrete Handholes: Do not drill deeper than 3-7/8 inches for manholes and 2 inches for handholes, for anchor bolts installed in the field. Use a minimum of two anchors for each cable stanchion.
- K. Warning Sign: Install "Confined Space Hazard" warning sign on the inside surface of each manhole cover.

3.7 INSTALLATION OF HANDHOLES AND PULL BOXES OTHER THAN PRECAST CONCRETE

- A. Install handholes and pull boxes level and plumb and with orientation and depth coordinated with connecting ducts to minimize bends and deflections required for proper entrances. Use pull box extension if required to match depths of ducts, and seal joint between box and extension as recommended by the manufacturer.
- B. Unless otherwise indicated, support units on a level 6-inch- thick bed of crushed stone or gravel, graded from 1/2-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.
- C. Elevation: Set so cover surface will be flush with finished grade.
- D. Install handholes and pull boxes with bottom below the frost line, 36" below grade.
- E. Install removable hardware, including pulling eyes, cable stanchions, cable arms, and insulators, as required for installation and support of cables and conductors and as indicated. Retain arm lengths to be long enough to provide spare space for future cables, but short enough to preserve adequate working clearances in the enclosure.
- F. Field-cut openings for ducts and conduits according to enclosure manufacturer's written instructions. Cut wall of enclosure with a tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.
- G. For enclosures installed in asphalt paving and subject to occasional, nondeliberate, heavy-vehicle loading, form and pour a concrete ring encircling, and in contact with, enclosure and with top surface screeded to top of box cover frame. Bottom of ring shall rest on compacted earth.

1. Concrete: 3000 psi, 28-day strength, complying with Division 03 Section "Cast-in-Place Concrete," with a troweled finish.
2. Dimensions: 10 inches wide by 12 inches deep.

3.8 GROUNDING

- A. Ground underground ducts and utility structures according to Division 26 Section "Grounding and Bonding for Electrical Systems."

3.9 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 1. Demonstrate capability and compliance with requirements on completion of installation of underground ducts and utility structures.
 2. Pull aluminum or wood test mandrel through duct to prove joint integrity and test for out-of-round duct. Provide mandrel equal to 80 percent fill of duct. If obstructions are indicated, remove obstructions and retest.
 3. Test manhole grounding to ensure electrical continuity of grounding and bonding connections. Measure and report ground resistance as specified in Division 26 Section "Grounding and Bonding for Electrical Systems."
- B. Correct deficiencies and retest as specified above to demonstrate compliance.
- C. Prepare test and inspection reports.

3.10 CLEANING

- A. Pull leather-washer-type duct cleaner, with graduated washer sizes, through full length of ducts. Follow with rubber duct swab for final cleaning and to assist in spreading lubricant throughout ducts.
- B. Clean internal surfaces of manholes, including sump. Remove foreign material.

Payment

All work under this item shall be completed on a Lump Sum basis.

Pay Item

Pay Unit

Relocation of Existing Field Lighting Service Feed

Lump Sum