

# Test Certificate      Continuous Test



Test Number: 1  
Setpoint tested: 22.0000 kg/h

Date: Thursday, August 20, 2018

Page 2 / 2

## Continuous Test Results

Test Time: 10 min  
 Setpoint: 22.0000 kg/h  
 Testscale Range: 24.0 kg      Span: 0.99900      SFT Configuration: -1-----  
 SFT: 1  
 S/N:  
 S/W: S9700-20080-V

Base Time	1 Sec	5 Sec	10 Sec	15 Sec	30 Sec	60 Sec
Sample Count	600	120	60	40	20	10
Std. Deviation [g]	0.0379	0.1578	0.2672	0.3336	0.2880	0.3994
Std. Deviation [%]	0.6199	0.5160	0.4368	0.3636	0.1569	0.1088
2Sigma Std. Dev [%]	1.2398	1.0319	0.8736	0.7272	0.3139	0.2176
Sample Mean [g]	6.11743	30.5872	61.1743	91.7615	183.523	367.046
Setpoint [g]	6.11111	30.5556	61.1111	91.6667	183.333	366.667
Setpoint Dev [%]	0.1034	0.1034	0.1034	0.1034	0.1034	0.1034

## Sample Grap

