PROPOSAL Homeowner Name

December 6, 2024 Homeowner Address

The proposal is based on the work description and options described below

The owners will be living in the house during construction

The kitchen remodel is the base project, any other work is presumed to be added to the base scope

It will be the owners responsibility to clear out all spaces to be worked on

Kitchen Renovation

General Conditions

Permit and permit fee for alterations with structural work included

Verify the existing framing design, provide information on existing conditions to engineer

for final beam design

Allowance to design, stamp and certify (if needed) the new beam (2400)

Finalize the kitchen design with the cabinet order, guide and coordinate owner to select

allowance materials with vendor reps

Project coordination, site supervision and trade partner quality control included

Receiving materials deliveries, proper storage of materials and materials pickup

Protect existing interior finishes and landscaping, weather protection during construction

Daily project cleanup and final cleanup included

Remove all equipment and excess materials and restore jobsite to prior condition

Provide outside bathroom facility for two months

Price includes a 30 yd. dumpster in the driveway, remove all construction debris

Demo

Remove and save dishwasher, soap dispenser and faucet if possible for reinstallation

Remove, save and reinstall the toilet, pedestal sink, laundry appliances and HVAC register

Demo the kitchen cabinets, countertops and appliances that will not be saved

Demo the dining room wall framing and finishes from the outside wall to the stair wall

Demo the soffits above the upper cabinets

Cut and patch the subfloor to relocate (2) HVAC floor registers to new locations

Demo the kitchen ceiling above the range hood to install a new exhaust vent

Demo to post the new beam down to the main girt below at the existing corner

Demo to access the new post location in the outside wall

Temporarily support the section of the dining room wall to be demoed per plan

Demo the existing tile floor and underlayment in the dining room, kitchen and hallway

Price assumes no adhesive was used on subfloor, no repairs to subfloor included

Demo the backsplash tile, chair rail and shadow boxes in the dining room and kitchen

No work on the existing doors and windows

Framing

Install a (3) 10" LVL beam, approx. 13', posted in and connected to the existing wall framing

Install new posts, or otherwise reinforce existing framing to support the new beam Price include blocking the first floor cavities and transferring the load to the main girt

HVAC

Adjust the location of the existing registers to new locations in the new floor plan

Vent the new range hood in the ceiling cavity to the outside wall

Supply and install a make up air system on a sensor for the new range hood

Plumbing

Disconnect the kitchen, bathroom and laundry for demo at the same time

Reinstall toilet, pedestal sink and laundry in bathroom after demo

Install the kitchen sink, faucet and dishwasher on the same rough piping

Allowance to supply new sink and faucet (1000)

Cap the existing gas supply and relocate for a new 36" range

No code upgrades included

Electrical No service or panel upgrades included

Make existing wiring safe after demolition

Allowance to rewire existing circuits and upgrade existing circuit breakers to meet code (700)

Furnish, wire and install (6) LED recessed fixtures Install (2) owner supplied pendant lights over the island

Install (2) 3 way switches and (4) single pole switches for new floor plan Furnish, wire and install (3) LED undercabinet fixture on a separate switch

Wire for new GFI counter outlets with new breakers per code Wire for new GFI outlet in the island with a new breaker per code

Wire for (1) new 36" gas range

Wire for new refrigerator and dishwasher Wire for garbage disposal with a wall switch Wire for a range hood and make up air system

Countertop convection oven to plug into counter outlet

No work on the exterior lighting

No work on the doorbells

No code upgrades included unless described

Walls, Ceilings Patch insulation at open wall and ceiling areas if needed

Patch the walls, ceilings and beam to blend flush into the existing finishes

Scrape prep and patch existing walls for a new backsplash and to paint eat-in area walls

No patching in the basement

Carpentry, Cabinets Allowance to supply the kitchen, island and eat-in cabinets, pulls and knobs (22000)

Install all cabinets, knobs and handles in the allowance

Install owner supplied appliances

Allowance to supply and install the kitchen and island countertops (6500) Patch and match the existing baseboard in the kitchen, eat-in area and hallway Remove and reinstall laundry appliances as needed to remain operational

No new doors or trim included

No baseboard patching in the bathroom included

Tiling Install underlayment in the bathroom after demo to reinstall fixtures and laundry

Install 1/4" durock underlayment in the kitchen, eat-in area and hallway

Install new 24x48" porcelain tile on the kitchen, eat-in area, hallway and bathroom floors

Install tile on the kitchen backsplash in (3) areas Allowance to supply tile and grout (4400)

Flooring No new wood or existing wood floor refinishing included

Interior Painting Prep, prime and paint the kitchen, hallway and eat-in area

> Touch up the existing base trim only in the bathroom No work in the entry family room or living room

112,700 TOTAL CONTRACT PRICE

Installed by contractor	supplied by	homeowner
-------------------------	-------------	-----------

Kitchen appliances

Surface mounted light fixtures

Not included Code upgrades not described

No structural work in the basement included

Option 1 800 Set up a temporary kitchen in the family room

Option 2 2800 Demo the existing second floor framing, install the LVL beam to be flush to the subfloor above,

connect existing floor framing, includes allowance to relocate pipes and/or wires (500)

The beam may still project slightly below the ceiling

Option 2A 400 Upgrade the 10" LVL beam to become an 8" deep beam concealed in the ceiling

Option 3 2800 Demo and reframe the eat-in area wall to match the cut down wall on the opposite side

Patch and finish changes to match the existing open side

Install millwork for new newel posts, guardrails, one grip rail and balusters

Finish new millwork with stain or paint

Option 4 1600 Remove subfloor, sister (4) existing joists with LVL, includes engineering, no relocating

pipes or wires included
Patch subfloor for new tile

Option 5 7100 Demo the existing flooring in the living room, family room area

Install new oak strip flooring in the living room, family room area, finish with (3) coats of poly, no stain

Payment Schedule

10000 Upon agreement

10000 Cabinets ordered

10000 Upon starting

10000 Beam installed

15000 Electrical inspected

15000 Framing inspected

10000 Floor tile installed

10000 Cabinets delivered

5000 Countertops templated

5000 Appliances working

5000 Substantially complete (spaces usable for their intended purposes)

7700 All Complete

112,700 Total Payments