



July 24, 2023

Peter Potter
Chapman Beach Association.
Old Saybrook CT.
203-856-4466
Beach0357@gmail.com

Listed Below is pricing to repair an existing jetty for the Chapman Beach Assoc.

1. Mobilize all tools and equipment to the site.
2. Deconstruct existing Jetty set rock aside for reuse.
3. Excavate down roughly 2' along the outer side of the jetty.
4. Place filter fabric along the new trench.
5. Place new 5-7 ton toe stone along the trench.
6. Reuse large stone to build up either side of the jetty with a 1' to 1' slope.
7. Incorporate existing stone inside of the new jetty.
8. Wrap with the filter fabric.
9. Incorporate 6-8" rip rap for interlocking the jetty stone.
10. Place the flattest rocks along the top of the new jetty.
11. Do a final clean up and remove all tools and equipment.

Total for work listed above = \$96,450

Note:

Sincerely,
Ocean County Construction

OCEAN COUNTY CONSTRUCTION
166 Wintechog Hill Road – North Stonington, CT- 06359 Phone Number: 860-287-0036
Email: oceancountyadam@gmail.com
CT License # HIC.0641241