

CITADEL 324, WOLVERHAMPTON



Project Details

Type of Work Undertaken:

Earthworks, Groundworks, Demolition, Subbase

Client: Level Best Concrete Flooring

Value: £100,000

Form of Contract: JCT

Duration: 8 Weeks

Project Overview:

Our long standing relationship with our clients at Level Best Concrete Flooring, secured Alwoodley Civils Ltd yet another job this time in Wolverhampton.

Working on this unit brought us the task of breaking out a 118,400sq ft slab so it could be reinstated. We made light work of this using three 21 tonne Excavators with Peckers which lead the breakout to flow seamlessly. Once completed and we had disposed off the existing concrete, we could get to work prepping the subbase ready for steel work to commence. We utilised our Bobcat T590 with grader blade, running our 2d system, which inevitably gave us a perfect flat surface within the tolerances given. Yet another perfect example of us utilising our machine control systems to give the client that perfect finish.

