

October 9, 2018

Corinne McMahan

Phone: 951.532.5378

Email: corinne0050@gmail.com

RE: Remove and replace boat ramp 130'x30'

Sir:

I am pleased to submit herein our proposal to remove and replace your existing boat launch ramp. Please see the attached sketch and the following for what is included in your price.

Demo of existing launch ramp including disposal of concrete from on site
#4 rebar each way on 18" o.c.

Includes 2' footing at perimeter of new concrete w/2 #4 rebar continuous

6" - 4500 psi concrete

3/4" "V" grooves

Saw cut 15'x15' o.c. max.

All joints will be caulked

Create flow line on west side of ramp


(This does not include any dredging or concrete below the water level)

Bid per above

\$109,285.00

We have the resources to begin this project immediately. Thank you for allowing T.R. Orr to submit this proposal. If you have any questions please let me know.

Sincerely,



Elton Edwards
Project Manager