Lower Paxton Township Authority Construction Traffic Update for Weeks of August 3 and August 10

1. Nyes Road at Devonshire Heights Road (PennDOT Project)

- Project Location: Nyes Road at Devonshire Heights Road
- Impacted Streets: Nyes Road and Devonshire Heights Road
- Contractor(s): Pennsy Supply and Trinity Excavating
- LPT Field Contact: None. This is a PennDOT Project.
- Nature of Work: Intersection reconstruction, utility relocation.
- Additional Notes: The closure and detour of Nyes Road and Devonshire Heights Road will remain in place during this period. See the attached detour plans. Contact PennDOT for additional details.

2. <u>Eastern Linglestown Area- Mini Basins BC-2A,2B,2C,5B</u>

- Project Location: See map
- Impacted Streets (this period): Judy Lane.
- Contractor(s): DOLI Construction Corporation
- **LPT Field Contact:** Eric Morgan (717-554-9052) or Tim Nolt (717-278-5423).
- Nature of Work: Sanitary sewer mainline and lateral replacement
- Additional Notes: Portions of Judy Lane will be closed during this period. Work will take place during the hours of 6:30 am and 5:00 pm Monday through Thursday. Detours will be in place and all roads will be reopened at the end of each working day. Contractor will be required to maintain access to properties and allow refuse trucks through the work zone. Some coordination could be required at times.

3. Devonshire Area- Mini Basins BC-7A,7B,7C,7D,8C,8D


- Project Location: See map
- Impacted Streets (this period): Merivale Court
- Contractor(s): Lower Paxton Township I/I Crew
- **LPT Field Contact:** Glenn McCoy (717-554-9045) or Jim Wetzel (717-554-9051).
- Nature of Work: Sanitary sewer lateral replacement
- Additional Notes: During this period, Merivale Court will be closed from Devon Drive to the Cul-de-sac. Work will take place during the hours of 6:30 am and 2:30 pm. All roads will be reopened at the end of each working day. Crew will maintain access to properties on Merivale Court and allow refuse trucks through the work zone.


1 of 1 Issued: July 31, 2020

SR 2029

SEE DETAIL "B" -

RD







SIGN SIGN NO.

-SEE DETAIL "A"

STERLING

RD

SOUTH

HANOVER

TWP

KNIGHT

UNION

HILL

PINE

— DETOUR ROUTE

PROJECT LOCATION


DES: J.R.F. CHK: R.B.S.
DWN: W.G.R. CHK: T.S.M. DATE: 5/2/2019

TRAFFIC CONTROL PLAN DETOUR MAP

K I	DISTRICT	COUNTY	ROUTE	SECTION	SHE	ET			
N	8-0	8-0 DAUPHIN		017	11 0	F 13			
	LOWER PAXTON TOWNSHIP								
	REVISION NUMBER	REVISIONS			DATE	BY			

MA	BULATION OF INTENANCE AN DURING CO I NO. 0901-0	QUANTITY	REMARKS			
NO.	LEGEND	STANDARD NO.	SIZE	MOUNTING	gu,	
1	⇔ ☆ ROAD cLOSED	R11-2	48 "×30 "	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	4	PLACE TYPE III BARRICADES ACROSS ENTIRE ROADWAY
2	Nyes Road DETOUR	SS-1 M4-9S	36 "X12 " 30 "X24 "	TYPE B	6	
3	Nyes Road END DETOUR	SS-1 M4-8A	36 "X12 " 24 "X18 "	TYPE B	2	
4	Nyes Road DETOUR	SS-1 M4-9SR	36 "X18 " 30 "X24 "	TYPE B	4	
5	Nyes Road DETOUR	SS-1 M4-9R	36 "X18 " 30 "X24 "	TYPE B	4	
6	Nyes Rood DETOUR	SS-1 M4-9SL	36 "X12 " 30 "X24 "	TYPE B	2	
7	Nyes Road DE TOUR	SS-1 M4-9L	36 "X12 " 30 "X24 "	TYPE B	2	
8	ROAD CLOSED 500 FT	W20-3 W30-1-1	36 "X36 "	TYPE B	2	
9	ROAD CLOSED 1000 FT	W20-3 W30-1-2	36 "X36 "	TYPE B	2	


MA	BULATION OF INTENANCE AN DURING CO I NO. 0901-00	ND PROTE()NSTRUCT))OO1 (FOR	CTION OF ON (DETO	DEVICES TRAFFIC UR) TION ONLY)	QUANTITY	REMARKS
NO.	LEGEND	STANDARD NO.	SIZE	MOUNTING	g	
10	ROAD CLOSED 1/2 MILE	W20-3 W30-1-4	36 "X36 "	TYPE B	2	
11)	ROAD CLOSED 1 1/4 WILES AHEAD LOCAL TRAFFIC ONLY DETOUR	R11-3A M4-10R	60 "X30" 48 "X18 "	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	2	INSTALL SIGNS ON BOTH LEFT AND RIGHT SIDES OF ROADWAY
(2)	ROAD CLOSED 1 1/4 MILES AHEAD LOCAL TRAFFIC ONLY DE-TOUR	R11-3A M4-10L	60 "X30 " 48 "X18 "	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	2	INSTALL SIGNS ON BOTH LEFT AND RIGHT SIDES OF ROADWAY
13	DETOUR 1500 FT	W20-2 W30-1-3	36 "X36 "	TYPE B	1	
14)	DETOUR 1000 FT	W20-2 W30-1-2	36 "X36 "	TYPE B	1	
ADVANCE NOTICE SIGN	THIS STREET TO BE CLOSED FOR CONSTRUCTION//	W23-101	96 "X48 "	TYPE III BARRICADE	2	SEE SPECIAL PROVISION FOR ITEM 0901-0001. PLACE AT BRIDGE ON BOTH SIDES.



30"X12"

SS-1

BLACK LEGEND ON
ORANGE BACKGROUND
(TYPE III REFLECTIVE MATERIAL)
NOT TO SCALE



DES:	J.R.F.	CHK:	T. S. M.
DWN:	W. G. R.	CHK:	R.B.S.

DATE: 5/2/2019

Road & Bridge Project Construction >>>



Project Report

May 08, 2020

Project Status: Under Construction

County: Dauphin

Project ID: 47521 Route: 2019

Title: Nyes/Dvnshre Hts Safety

Improvement Type: Intersection Safety Improvements

Open For Bid: 07/25/2019

Contractor

Name: Pennsy Supply, Inc.

Address: 2400 Thea Drive, Suite 3A, Harrisburg, PA 17110

District Contact - Asst. Construction Engineer

Name: Mike Deiter

Email: mdeiter@state.pa.us Phone: (717) 772-2388

Project Contact - Inspector in Charge

Name: Gregory Moore
Email: gregmoor@state.pa.us
Phone: (717) 787-5192

Community Relations Coordinator

Title: Highway Admin. CRC

Phone: 717.787.1446

Work Can Begin: 09/05/2019 (Actual) Completion Date: 05/10/2021 (Estimated)

Project Limits: Intersection of Nyes Road and Devonshire Heights Road

Lower Paxton Township

Narrative: Traffic Signal Installation along with roadway realignment

Intersection of Nyes Road and Devonshire Heights Road


Lower Paxton Township


Current Construction Cost: \$3,972,608.28

TRAFFIC CONTROL PLAN DETOUR MAP

	DISTRICT	OISTRICT COUNTY		SECTION	SHE	ΕT			
	8-0	DAUPHIN	2019	017	12 0	= 13			
1	LOWER PAXTON TOWNSHIP								
•	REVISION NUMBER	REV	DATE	BY					







T-774 DETOUR MAP

SCALE 2000 FEET

LEGEND

— STATE ROUTE ----- TOWNSHIP ROAD

SIGN

SIGN NO. PROJECT LOCATION

— — — DETOUR ROUTE




DES:	J.R.F.	CHK:	T.S.M.	_
DWN:	J.R.F.	CHK:	R.B.S.	
DATE:	5/2/2019			

TRAFFIC CONTROL PLAN DETOUR MAP

AAI	DISTRICT	COUNTY	ROUTE	SECTION	SHEET				
AN	8-0	DAUPHIN	2019	017	13 OF 13				
	LOWER PAXTON TOWNSHIP								
	REVISION NUMBER	REV		DATE	BY				

MA	BULATION OF INTENANCE AN DURING CO I NO. 0901-00	ND PROTE()NSTRUCT)	CTION OF ION (DETC		QUANTITY	REMARKS
NO.	LEGEND	STANDARD NO.	SIZE	MOUNTING	g M	
1	☼ ☆ ROAD closed	R11-2	48 "×30 "	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	4	PLACE TYPE III BARRICADES ACROSS ENTIRE ROADWAY
2	DEVONSHIRE HEIGHTS RD DETOUR	SS-2 M4-9S	36 "X18 " 30 "X24 "	TYPE B	2	
3	DEVONSHIRE HEIGHTS RD END DETOUR	SS-2 M4-8A	36 "X18 " 24 "X18 "	TYPE B	2	
4	DEVONSHIRE HEIGHTS RD DETOUR	SS-2 M4-9SR	36 "X18 " 30 "X24 "	TYPE B	3	
5	DEVONSHIRE HEIGHTS RD DETOUR	SS-2 M4-9R	36"X18" 30"X24"	TYPE B	3	
6	DEVONSHIRE HEIGHTS RD DETOUR	SS-2 M4-9SL	36 "X18 " 30 "X24 "	TYPE B	3	
7	DEVONSHIRE HEIGHTS RD DETOUR	SS-2 M4-9L	36 "X18 " 30 "X24 "	TYPE B	3	
8	ROAD CLOSED 500 FT	W20-3 W30-1-1	36 "X36 "	TYPE B	2	
9	ROAD CLOSED 1000 FT	W20-3 W30-1-2	36 "X36 "	TYPE B	1	

MA	BULATION OF INTENANCE AN DURING CO M NO. 0901-0	ND PROTE()NSTRUCT	CTION OF ION (DETC INFORMA	TRAFFIC DUR) TION ONLY)	QUANTITY	REMARKS
NO. 10	ROAD CLOSED 1500 FT	W20-3 W30-1-3	36 "X36 "	MOUNTING TYPE B	1	
11)	ROAD CLOSED 1/4 MILE AHEAD LOCAL TRAFFIC ONLY DE TOUR	R11-3A M4-10R	60 "X30 " 48 "X18 "	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	2	INSTALL SIGNS ON BOTH LEFT AND RIGHT SIDES OF ROADWAY
12)	ROAD CLOSED 1 MILE AHEAD LOCAL TRAFFIC ONLY DE-TOUR	R11-3A M4-10L	60 "X30" 48 "X18"	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	2	INSTALL SIGNS ON BOTH LEFT AND RIGHT SIDES OF ROADWAY
13	DETOUR 1500 FT	W20-2 W30-1-3	36 "X36 "	TYPE B	2	
14)	DETOUR 1000 FT	W20-2 W30-1-2	36 "X36 "	TYPE B	2	
15	ROAD CLOSED DETOUR	R11-2 M4-10L	48 "X30" 48 "X18"	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	1	
16	ROAD CLOSED DETOUR	R11-2 M4-10R	48 "X30" 48 "X18"	TYPE III BARRICADE WITH 2 TYPE B LIGHTS (AMBER)	1	
ADVANCE NOTICE SIGN	THIS STREET TO BE CLOSED FOR CONSTRUCTION//	W23-101	96 "X48 "	TYPE III BARRICADE	2	SEE SPECIAL PROVISION FOR ITEM 0901-0001. PLACE AT BRIDGE ON BOTH SIDES.



36"X18"


\$\$ - 2

BLACK LEGEND ON

ORANGE BACKGROUND

(TYPE III REFLECTIVE MATERIAL)

NOT TO SCALE



DES:	J.R.F.	CHK:	R.B.S.	
DWN:	J.R.F.	CHK:	T. S. M.	
DATE:	5/2/2019			