

ENVIRONMENTAL
CLEARANCE



Government of India
Ministry of Environment, Forest and Climate Change
(Issued by the State Environment Impact Assessment
Authority(SEIAA), MAHARASHTRA)

To,

The Partner

GURU KRUPA BUILDERS

S. NO. 99/112B/3, Morya Colony , Near BRT Bus Stop, Vijay Nagar
Kalewadi , Pune 411017 -411017

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity
under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC)
in respect of project submitted to the SEIAA vide proposal number
SIA/MH/INFRA2/456033/2023 dated 19 Dec 2023. The particulars of the
environmental clearance granted to the project are as below.

- | | |
|---|--|
| 1. EC Identification No. | EC25B038MH110007 |
| 2. File No. | SIA/MH/INFRA2/456033/2023 |
| 3. Project Type | New |
| 4. Category | B |
| 5. Project/Activity including
Schedule No. | 8(a) Building and Construction projects |
| 6. Name of Project | Proposed Residential and Commercial
Project at Rahatani by Guru Krupa
Builders |
| 7. Name of Company/Organization | GURU KRUPA BUILDERS |
| 8. Location of Project | MAHARASHTRA |
| 9. TOR Date | N/A |

The project details along with terms and conditions are appended herewith from page
no 2 onwards.

Date: 18/07/2025

(e-signed)
Smt. Jayashree Bhoj (IAS)
Member Secretary
SEIAA - (MAHARASHTRA)

*Note: A valid environmental clearance shall be one that has EC identification
number & E-Sign generated from PARIVESH. Please quote identification
number in all future correspondence.*

This is a computer generated cover page.

PARIVESH

(Pro-Active and Responsive Facilitation by Interactive,
and Virtuous Environmental Single-Window Hub)



STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/INFRA2/456033/2023
Environment & Climate
Change Department
Room No. 217, 2nd Floor,
Mantralaya, Mumbai- 400032.

To

M/s.Guru Krupa Builders,
S. No. 99/12A/5,99/12B/4,99/2B,
99/3B, 96/1B/1, 99/12B/3,99/1/1 ,
99/2, 97/1A/1/1,99/3/2 Rahatani,
Haveli, Pune.

Subject : Environmental Clearance for Proposed Residential and Commercial Project at S. No. 99/12A/5,99/12B/4,99/2B, 99/3B, 96/1B/1, 99/12B/3,99/1/1 ,99/2, 97/1A/1/1,99/3/2 Rahatani, Haveli, Pune by M/s.Guru Krupa Builders

Reference : Application no. SIA/MH/INFRA2/456033/2023

This has reference to your communication on the above-mentioned subject. The proposal was considered by the SEAC-3 in its 191st meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 292nd (Day-2) meeting of State Level Environment Impact Assessment Authority (SEIAA) held on 8th May, 2025.

2. Brief Information of the project submitted by you is as below:-

1	Proposal Number	PARIVESH Proposal No.: SIA/MH/INFRA2/456033/2023
2	Name of Project	Proposed Residential & Commercial Project
3	Project category	B2 Category, 8(a) as per EIA Notification 2006
4	Type of Institution	Private
5	Project Proponent	- Name: Gurukrupa Builders - Address: Flat No. F -16 Devi Link Apartments, PC Link Road, Chinchwad. - Email ID: d.awatramani@gmail.com
6	Name of Consultant	- Name: Shrikrishna Environment Consultants Pvt. Ltd. - NABET Accreditation No.: NABET/EIA/21-24/SA 0213 - Validity: 10/11/2024
7	Applied for	New Greenfield Project (Fresh EC)
8	Details of Previous EC	NA
9	Location of the project	Survey No. 99/12A/5, 99/12B/4, 99/2B, 99/3B, 96/1B/1, 99/12B/3, 99/1/1, 99/2, 97/1A/1/1, 99/3/2, C.T.S No: 5997 (P), 5998 (P), 5999 (P), 6000 (P), 6001 (P), 6042 (P), 6043 (P), 6044 (P), Rahatani, Taluka-Haveli, Pune, Maharashtra.
10	Latitude and Longitude	18°37'25.85"N, 73°47'32.17"E
11	Total Plot Area	9,119.37 Sq.M
12	Deductions	1,707.91 Sq. M.
13	Net Plot Area	7,411.46 Sq. M.
14	Proposed FSI area	33,179.36 Sq.M

15	Proposed Non FSI area	17,706.30 Sq.M																					
16	Proposed Total Built up Area	50,885.66 Sq.M																					
17	Total Built up area approved by Planning Authority	In Process																					
18	Ground Coverage	--																					
19	Total Project Cost	Rs. 70 Cr.																					
20	CER as per MoEF & CC circular dated 01/05/2018	CER Shall be Implemented as a part of EMP as recommended by SEAC/SEIAA as mentioned in OM F. No. 22-65/2017-IA.III dated 30 September, 2020 and OM file No. 22-65/2017-IA.III dated 25/02/2021.																					
21	Details of Building Configuration	Proposed Building Configuration: <table border="1"> <thead> <tr> <th>Bldg. Name</th><th>Bldg. Configuration</th><th>Height</th></tr> </thead> <tbody> <tr> <td>Bldg. A</td><td>GP/Gr+1st/Park to 2nd Park to 14 Fl.</td><td>44.70m</td></tr> <tr> <td>Bldg. B</td><td>GP/Gr+1st/Park to 2nd Park to 14 Fl.</td><td>44.70m</td></tr> <tr> <td>Bldg. C</td><td>Gr+8 Floor</td><td>30m</td></tr> </tbody> </table>	Bldg. Name	Bldg. Configuration	Height	Bldg. A	GP/Gr+1st/Park to 2 nd Park to 14 Fl.	44.70m	Bldg. B	GP/Gr+1st/Park to 2 nd Park to 14 Fl.	44.70m	Bldg. C	Gr+8 Floor	30m									
Bldg. Name	Bldg. Configuration	Height																					
Bldg. A	GP/Gr+1st/Park to 2 nd Park to 14 Fl.	44.70m																					
Bldg. B	GP/Gr+1st/Park to 2 nd Park to 14 Fl.	44.70m																					
Bldg. C	Gr+8 Floor	30m																					
22	Total number of tenements	Tenements: 216 Nos. Commercial Units: 99 Nos and Multipurpose Hall: 1 Nos Expected Users: Total: 1404 Nos. (Residential: 1080 Nos. + Commercial:324 Nos.)																					
23	Water Budget	Proposed water budget <table border="1"> <thead> <tr> <th>Particular</th><th>Dry Season</th><th>Wet Season</th></tr> </thead> <tbody> <tr> <td>Fresh Water</td><td>105 KLD</td><td>105 KLD</td></tr> <tr> <td>Recycled (Flushing)</td><td>56 KLD</td><td>56 KLD</td></tr> <tr> <td>Recycled (Landscape)</td><td>6 KLD</td><td>NIL</td></tr> <tr> <td>Swimming Pool</td><td>--</td><td>--</td></tr> <tr> <td>Total</td><td>167 KLD</td><td>161 KLD</td></tr> <tr> <td>Waste water generation</td><td>144 KLD</td><td>144 KLD</td></tr> </tbody> </table>	Particular	Dry Season	Wet Season	Fresh Water	105 KLD	105 KLD	Recycled (Flushing)	56 KLD	56 KLD	Recycled (Landscape)	6 KLD	NIL	Swimming Pool	--	--	Total	167 KLD	161 KLD	Waste water generation	144 KLD	144 KLD
Particular	Dry Season	Wet Season																					
Fresh Water	105 KLD	105 KLD																					
Recycled (Flushing)	56 KLD	56 KLD																					
Recycled (Landscape)	6 KLD	NIL																					
Swimming Pool	--	--																					
Total	167 KLD	161 KLD																					
Waste water generation	144 KLD	144 KLD																					
24	Water Storage Capacity for Fire Fighting/ UGT	UGT details as follows: Total UGT Capacity: - Domestic UG tank Capacity: 195 Cu. M. - Fire UG tank Capacity: 150 Cu. M. - Commercial Tank: 40 Cu.M																					
25	Source of Water	Pimpri Chinchwad Municipal Corporation (PCMC) STP treated water will be reused for flushing & landscape purpose.																					
26	Rainwater Harvesting (RWH)	- Level of Ground Water Table: Pre-Monsoon: 14 m to 16 m BGL Post Monsoon: 12 m to 14 m BGL - Size & No. of RWH tanks and Quantity: NA - Quantity and size of recharge pits: 7 nos. of recharge pits are proposed. Total UGT Capacity: - Domestic UG tank Capacity: 195 Cu. M. - Fire UG tank Capacity: 150 Cu. M. - Commercial Tank: 40 Cu.M																					

27	Sewage and Wastewater	- Sewage Generation: 144 KLD - Proposed STP Capacity: 150 KLD Capacity - STP Technology: MBBR																					
28	Solid waste management during construction phase	Construction Phase: <table> <tr> <th>Type</th><th>Quantity</th><th>Treatment/Disposal</th></tr> <tr> <td>Dry Waste</td><td>Negligible</td><td>Collect & disposed through authorized agency</td></tr> <tr> <td>Wet Waste</td><td>Negligible</td><td>Provision of composting</td></tr> <tr> <td>Construction Waste</td><td>Top Soil & Debris</td><td>Top soil will be reused for landscape purpose within project site. Excavated debris will be reused for backfilling, levelling & plinth filling purpose.</td></tr> </table>	Type	Quantity	Treatment/Disposal	Dry Waste	Negligible	Collect & disposed through authorized agency	Wet Waste	Negligible	Provision of composting	Construction Waste	Top Soil & Debris	Top soil will be reused for landscape purpose within project site. Excavated debris will be reused for backfilling, levelling & plinth filling purpose.									
Type	Quantity	Treatment/Disposal																					
Dry Waste	Negligible	Collect & disposed through authorized agency																					
Wet Waste	Negligible	Provision of composting																					
Construction Waste	Top Soil & Debris	Top soil will be reused for landscape purpose within project site. Excavated debris will be reused for backfilling, levelling & plinth filling purpose.																					
29	Solid waste management during operation phase	<table> <tr> <th>Type</th><th>Quantity</th><th>Treatment/ disposal</th></tr> <tr> <td>Dry waste</td><td>265 Kg/day</td><td>Will be collected & disposed by authorized Agency</td></tr> <tr> <td>Wet waste</td><td>356 Kg/day</td><td>Treated in Organic waste composter and used as manure in landscape</td></tr> <tr> <td>Hazardous waste</td><td>--</td><td>NA</td></tr> <tr> <td>Biomedical waste</td><td>--</td><td>NA</td></tr> <tr> <td>E-waste</td><td>4 Kg/day</td><td>Will be collected & disposed by authorized Agency</td></tr> <tr> <td>STP Sludge</td><td>15 Kg/day</td><td>Dewatering and used as manure in landscape</td></tr> </table>	Type	Quantity	Treatment/ disposal	Dry waste	265 Kg/day	Will be collected & disposed by authorized Agency	Wet waste	356 Kg/day	Treated in Organic waste composter and used as manure in landscape	Hazardous waste	--	NA	Biomedical waste	--	NA	E-waste	4 Kg/day	Will be collected & disposed by authorized Agency	STP Sludge	15 Kg/day	Dewatering and used as manure in landscape
Type	Quantity	Treatment/ disposal																					
Dry waste	265 Kg/day	Will be collected & disposed by authorized Agency																					
Wet waste	356 Kg/day	Treated in Organic waste composter and used as manure in landscape																					
Hazardous waste	--	NA																					
Biomedical waste	--	NA																					
E-waste	4 Kg/day	Will be collected & disposed by authorized Agency																					
STP Sludge	15 Kg/day	Dewatering and used as manure in landscape																					
30	Green Belt Development	- Total RG Area: 741.15 Sq.M. - Existing trees on Plot: NIL - Number of trees to be required to plant: 112 Nos. - Number of trees to be cut: NIL. - Number of trees to be transplanted: NIL - Number of trees to be retained: NIL.																					
31	Power Requirement	- Source of power supply: MSEDCL - During Construction Phase (Demand Load): 30 kW - During Operation Phase (Connected Load): 1898 kW - During Operation Phase (Demand Load): 982 kW - Transformer: 2 x 630 kVA Capacity - DG Set: 1 x 320 kVA & 1 x 62.5 kVA capacity - Fuel Used: Diesel																					
32	Details of Energy Saving	Total Energy Saving: 22.97 % through proposed use of Solar Energy and Energy saving measures.																					

33	Environment Management Plan during Construction phase	<table><tr><th>Sr. No.</th><th>Parameter</th><th>Total Cost/ year (Rs. Lakhs)</th></tr><tr><td>1.</td><td>Personnel Protective Equipment</td><td>5.83</td></tr><tr><td>2.</td><td>Site Sanitation Facility</td><td>3.50</td></tr><tr><td>3.</td><td>Water Provision</td><td>8.14</td></tr><tr><td>4.</td><td>Solid waste management</td><td>5.40</td></tr><tr><td>5.</td><td>Awareness to workers</td><td>4.00</td></tr><tr><td>6.</td><td>Health Check up</td><td>1.0</td></tr><tr><td>7.</td><td>Disaster Management</td><td>18.31</td></tr><tr><td>8.</td><td>Environmental Monitoring</td><td>4.04</td></tr><tr><td colspan="2">Total Cost</td><td>50.22</td></tr></table>	Sr. No.	Parameter	Total Cost/ year (Rs. Lakhs)	1.	Personnel Protective Equipment	5.83	2.	Site Sanitation Facility	3.50	3.	Water Provision	8.14	4.	Solid waste management	5.40	5.	Awareness to workers	4.00	6.	Health Check up	1.0	7.	Disaster Management	18.31	8.	Environmental Monitoring	4.04	Total Cost		50.22																																								
Sr. No.	Parameter	Total Cost/ year (Rs. Lakhs)																																																																						
1.	Personnel Protective Equipment	5.83																																																																						
2.	Site Sanitation Facility	3.50																																																																						
3.	Water Provision	8.14																																																																						
4.	Solid waste management	5.40																																																																						
5.	Awareness to workers	4.00																																																																						
6.	Health Check up	1.0																																																																						
7.	Disaster Management	18.31																																																																						
8.	Environmental Monitoring	4.04																																																																						
Total Cost		50.22																																																																						
34	Environment Management Plan Operation phase	<table><tr><th>Sr. No.</th><th>Component</th><th>Details</th><th>Capital Cost (Rs. Lakh)</th><th>O &M Cost (Rs. Lakh)</th></tr><tr><td>1</td><td>Storm water</td><td>NA</td><td>--</td><td>--</td></tr><tr><td>2</td><td>Sewage Treatment Plant</td><td>STP of 150 KLD Capacity</td><td>18.0</td><td>9.32</td></tr><tr><td>3</td><td>Water treatment</td><td>--</td><td>--</td><td>--</td></tr><tr><td>4</td><td>RWH</td><td>7 Nos of Recharge Pits</td><td>21.0</td><td>1.5</td></tr><tr><td>5</td><td>Swimming Pool</td><td>--</td><td>--</td><td>--</td></tr><tr><td>6</td><td>Solid waste management</td><td>OWC</td><td>13.50</td><td>2.84</td></tr><tr><td>7</td><td>Hazardous waste</td><td>NA</td><td>--</td><td>--</td></tr><tr><td>8</td><td>E-waste</td><td>Collection & Disposal with authorized agency</td><td>--</td><td>--</td></tr><tr><td>9</td><td>Green Belt Development</td><td>112 No of Trees</td><td>3.43</td><td>0.84</td></tr><tr><td>10</td><td>Energy Saving</td><td>Energy saving</td><td>70.20</td><td>1.40</td></tr><tr><td>11</td><td>Environment Monitoring</td><td>Air, Water, Noise, Soil, STP, DG set, Compost Monitoring</td><td>--</td><td>5.0</td></tr><tr><td>12</td><td>Disaster Management</td><td>---</td><td>51.0</td><td>10.50</td></tr><tr><td></td><td>TOTAL</td><td></td><td>177.13</td><td>31.4</td></tr></table>	Sr. No.	Component	Details	Capital Cost (Rs. Lakh)	O &M Cost (Rs. Lakh)	1	Storm water	NA	--	--	2	Sewage Treatment Plant	STP of 150 KLD Capacity	18.0	9.32	3	Water treatment	--	--	--	4	RWH	7 Nos of Recharge Pits	21.0	1.5	5	Swimming Pool	--	--	--	6	Solid waste management	OWC	13.50	2.84	7	Hazardous waste	NA	--	--	8	E-waste	Collection & Disposal with authorized agency	--	--	9	Green Belt Development	112 No of Trees	3.43	0.84	10	Energy Saving	Energy saving	70.20	1.40	11	Environment Monitoring	Air, Water, Noise, Soil, STP, DG set, Compost Monitoring	--	5.0	12	Disaster Management	---	51.0	10.50		TOTAL		177.13	31.4
Sr. No.	Component	Details	Capital Cost (Rs. Lakh)	O &M Cost (Rs. Lakh)																																																																				
1	Storm water	NA	--	--																																																																				
2	Sewage Treatment Plant	STP of 150 KLD Capacity	18.0	9.32																																																																				
3	Water treatment	--	--	--																																																																				
4	RWH	7 Nos of Recharge Pits	21.0	1.5																																																																				
5	Swimming Pool	--	--	--																																																																				
6	Solid waste management	OWC	13.50	2.84																																																																				
7	Hazardous waste	NA	--	--																																																																				
8	E-waste	Collection & Disposal with authorized agency	--	--																																																																				
9	Green Belt Development	112 No of Trees	3.43	0.84																																																																				
10	Energy Saving	Energy saving	70.20	1.40																																																																				
11	Environment Monitoring	Air, Water, Noise, Soil, STP, DG set, Compost Monitoring	--	5.0																																																																				
12	Disaster Management	---	51.0	10.50																																																																				
	TOTAL		177.13	31.4																																																																				

35	Traffic Management	Type	Required as per UDCPR	Actual Provided	Area per Parking
		4-Wheeler	246 No.	260 Nos.	12.5 Sq.M.
		2-Wheeler	476 No.	490 Nos.	-- Sq.M.
36	Details of Court Cases/ litigations w.r.t. the project and project location if any	NA			

3. Proposal has been considered by SEIAA in its 292nd (Day-2) meeting held on 8th May, 2025 and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

1. PP to obtain IOD/IOA/Concession Document/Plan Approval or any other form of documents as applicable clarifying its conformity with local planning rules and provisions indicating all required RG area as per prevailing Hon'ble Supreme Court Order. PP to obtain all mandatory NOCs from the concerned planning authority and the planning authority shall not issue occupation certificate unless PP obtains the same.
2. PP to prepare and implement plan to make proposed project a plastic free zone.
3. PP to ensure to achieve the standard parameters of the treated sewage as per order issued by the Hon'ble National Green tribunal on 30.04.2019. PP to ensure that, the water proposed to be used for construction phase should not be drinking water.
4. PP and the planning authority shall ensure that, the construction and demolition waste (C & D waste) is collected and treated at designated places as per Construction and Demolition Waste Management Rules, 2016 amended from time to time.
5. PP to provide electric charging facility by providing charging points at suitable places as per Maharashtra Electric Vehicle Policy, 2021.
6. PP to ensure to achieve minimum 5% energy saving by using non-conventional energy source.

B. SEIAA Conditions-

1. PP has provided mandatory RG area of 765.14 m² on mother earth without any construction. Local planning authority to ensure the compliance of the same.
2. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
3. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
4. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA III dt.04.01.2019.

5. SEIAA after deliberation decided to grant EC for- FSI-33,179.36 m2, Non FSI-17,706.30 m2, total BUA-50,885.66 m2. (Plan approval No-BP/EC/Rahatani/03/24 dated 10.07.2024).

General Conditions:

a) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to..
- XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle

shall be adequately covered to avoid spillage/leakages.

- XVII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- XVIII. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
- XIX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

B) Operation phase:-

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.
- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including

- selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
 - X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
 - XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at parivesh.nic.in
 - XII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
 - XIII. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC& SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to

assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.

VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.

6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.

7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.

8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.



Jayashree Bhoj
(Member Secretary, SEIAA)

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Pune.
6. Commissioner, Pimpri Chinchwad Municipal Corporation
7. Regional Officer, Maharashtra Pollution Control Board, Pune.

