

# Precon Environmental Products LLC

6868 FM 730 South  
Azle, Texas 76020  
817-448-9718  
www.precon-tx.com


## FACTORY RECOMMENDED TESTING PROCEDURE FOR GREASE TRAPS

If project specifications require testing of vaults, use the following testing procedures.

---

- After completing the piping, the unit shall be properly backfilled.
- **DO NOT FILL TANKS WITH WATER UNTIL THEY HAVE BEEN PROPERLY BACKFILLED.** Filling tanks prior to backfilling may cause abnormal stress on the casting and may result in leakage and/or damage to the precast unit and will void the manufacturer's warranty.
- Fill the tank with water to the normal operating flow line level. (Recommended)
- Filling the tank with water up to and/or past the lid may cause hydraulic lifting and will void the warranty.
- Record this level and let stand for 24 hours then recheck the water level. A 5% or less variance is generally acceptable

NOTE: Precast concrete tanks are designed for below grade installation with an earthen backfill to avoid hydraulic lifting.



09/24/20