
## **Expandable Container House**

We self-develop the expandable container house , which is preassemble 95% before leaving the factory , fast and easy to assemble . And it can be moved frequently with the larger living area comparing with the flat pack container house .

### **Expandable Container House**



20ft: Expanded Size: 6390\*5850\*2530 mm Closed Size: 2250\*5850\*2530 mm 40ft: Expanded Size: 6390\*11800\*2530 mm Closed Size: 2250\*11800\*2530 mm




### **Detail Specification**

ltem	Expandable container house
Size	Overall size : 20ft: 6390*5850*2530 mm 40 ft : 6390*11800*2530 mm
Wall	50/75 mm EPS / Rockwool / PU sandwich panel
Roof	Keel : square tube pipe Insulation : 50 mm eps sandwich panel Drainage : water flows to the four corners
Floor	MGO board + PVC floor
Window	Double glazed PVC / Aluminium alloy windows with bathroom window
Door	Double glass sliding door , bathroom door , wood door etc
Load ( KN/m2)	Base plate : 3.0 Roof panel : 1.5 wind force : 0.6
Heat transfer confficient (W /m2 K)	Base plate : 0.46 Roof panel : 0.64 wind force : 0.47
Sound insulation (db)	Base plate : 30-35 Roof panel : 30-35 wind force : 20-25

### **Product Show**


#### Material Diagram







Light



3

Switches

wood door

Steel frame

243















200831

Steel Frame

It is welded by the black square tube and then painted with white color as standard Optional Color is green , blue , black or as the RAL No.







Wall Panel / Roof Panel


Standard is 50 mm EPS sandwich panel, tongue-and-groove connection







OptionI panel : rockwool sandwich panel / PU sandwich panel





Door


#### Entry Door Double Sliding door 1920\*2260 mm



#### Bedroom Door Wood door 800\*2030 mm



#### Bathroom Door Titanium magnesium alloy door 730\*2030 mm



#### **Optional Entry Door**

#### Steel Door



#### Safety Door



Window

#### 930\*1110mm W\*H



45-degree cutting angle for 4 corners



600\*600 mm W\*H for bathroom



Window frame is together with the window



Standard is PVC double glazed winows Optional : 1.window screen 2. Window frame Material : Aluminium alloy Bathroom

Pre-assembled Shower Room, Toilet and wash basin with mirrior







#### Kitchen





Stanard is I shape 1500 mm long . L shape is custommade as request size . OptionI table material is black marble , white quartz stone and stainless steel







### Assemble

It will take half day by 3-4 skilled workers

Finished



# **Flat Pack Container House**

### Flat Pack Container House



#### **Basic Information**

Size : 1) 2400 \*6000\*2800 mm 2) 2200\*5800\*2800 mm

Standard container house is 1 open room with 1 door, 2 window with electrical system

### **Optional Color**

RAL 5015, RAL 9016 or as RAL color NO.

RAL 5015


**RAL 9016** 








### Structure System




### **Detail Specification**

ltem	20ft Flat pack container house
Size	1) 2400*6000*2800 mm 2) 2200*5800*2800 mm
Steel frame	2.3/2.5 mm thick steel frame , white color or any RAL No.
Wall	50/75 mm EPS/ glass fiber /PU sandwich panel
Roof	<ul><li>0.5 mm color steel sheet roof cover</li><li>50 mm glass fiber with single side aluminum foil</li><li>0.3 mm Profiled steel plate ceiling</li></ul>
Floor	MGO board + PVC floor
Window	Double glazed PVC / Aluminium alloy windows
Door	Safety door / sandwich panel door or as request
Electrical	China / Australia / American Standard or as request



Top : 0.5 mm thickness galvanized steel plate, white grey Insulation : 50 mm thickness with single side aluminum foil Ceiling panel : 0.3 mm thick corrugated steel sheet Steel frame : 2.3 /2.5 mm thick Industrial sockets : mounted in the frame at the short side






Floor : 15 mm MGO board + 1.6 mm PVC floor in blue color Combustion performance : flame retardant





2.3/2.5 mm hot rolled steel , formed by one time By bolts connection , to make the roof , floor together



### Wall panel

Thickness : 50 /75 mm thick

Optional : EPS sandwich panel, Rockwool sandwich panel, Glass fiber sandwich panel

### Window & Door





UPVC double glazed windows ,optional for screens and rails



Hinged single steel door , standard size 800\* 2035 mm or as request

Another optional : Sandwich panel door



### **Drainage System**

#### White color , PVC pipes , which is assembed in 4 corners



Insert the pipe bottom into rainwater pipe clamp





Place the U shape drainage channel on the bulge of bottom structure and make sure the drain hole outward






Joint the top with the preformed pipe hole of top container cast

Finished




## **Optional Layout**





















### Transport

Flat pack packages is suitable to transport by truck and loading in the container to shipping by sea . It save the transport cost

By truck
14 sets per truck
(17.5 meter long )



2. By Sea
8 sets /40 HQ
4 set / 20ft container

### Transport

3. By sea The material is packed well, then loading in the 40 HQ









### Assemble

Easy and fast to assemble, It will take half day by 3-4 skilled workers each unit.











- 1. The column fixed on the chassis with screw in vertical space. As Figure 1 shown.
- 2. Connected the housetop of container house with the 4 columns slowly, fixed with screw, as the Figure 2 shown.
- 3. Adjust the chassis and the roof in the same horizontal level, then Tighten bolts, as the Figure 3 shown.
- Installing the wall panel according to the item No. on the panel. The panel which with the socket, switch, should put the wires into the junction box firstly.
- 5. After finishing the installation of wall panel in one side, fixed them together with screw and binder plate, as the picture shown.
- Installing the other walls with the same method of No.4 and No.5 points.
- 7. Here finishing the installation of container house, the complete container house as the Figure shown.









Hospital Use Container House











# **Foldable Container House**



#### Fast assemble

It will take 15 minutes by 3-4 skilled workers to assemble 1 unit



#### Green

Repeatly to use , save cost and green to enviorment . 100% fire-proof and water resistance



#### Low transport cost

It can load 10 set in 40 HQ, 20 sets per truck.

#### **Production**

Standard design to produce and assemble, stable and durable, newest design



### **Detail Specifications**

ltem	Fodable Container House			
External Size	5800*2500*2500 mm L*W*H			
Internal Size	5650*2370*2350 mm L*W*H			
Floor Frame	270*2.5 mm profiled steel			
Roof Frame	170*2.5 mm profiled square tube			
Corner Post	155*2.0 profiled square tube			
Wall Panel	50 mm glass fiber sandwichpanel			
Floor panel	15 mm fire-proof board			
Window	Double glazed PVC window , 2 pcs per set			
Door	Standard fire-proof door, 1 pcs per set			
Electrical	Sockets, switches, LED lights, wires etc.			

### **Product Show**



Standard Packages 5800\*2500\*400 mm L\*W\*H



#### Material Diagram



### **Optional Layout**


Container house with no patition




Container house with one bedroom and bathroom




Container toilet



Container Shower room



### **Installation Method**



## Loading

#### 10 sets loading in 40 HC

















AS302 1 开双控 1 G 2 way switch

0	Gen	16	
0	0		

AS304 2 开双控 2 G 2 way switch



AS322-1

电视 + 网络插座

TV socket+ Data socket

112


Socket with SAA certificate


#### Switch box 4-6 ways

1.5-2.5 m2 electrical wire with SAA certificate TPS flat / round wire









暗盒 04 回路 Surface Mounted MCB Enclosure 04ways

100

Industry socket/ plug 3P , 32A ,250V Comply with AS/NZS 3100, AS/NZS3112, AS/NZS 3123

