

# HOMEOWNER CHECKLIST

Once all the items on this checklist have been completed, we are ready to schedule your template appointment. This ensures accuracy and the highest-quality finished product.

---

☐

## **Sinks & Faucets On Site**

If you are providing your own sink, it needs to be at the home at the time of template. If you are using a farm sink (also called an apron sink), it needs to be installed in its final location before we arrive to template.

☐

## **Cook Top or Stove on Site**

In addition to your sink and faucet being on site, we need your cooktop and/or stove on site as well, in addition to the downdraft if you have one. If you are still waiting on your appliances to be delivered, we request that you send the model number in to our office.

☐

## **Cabinet Install Completed**

Before we will make a visit to your home, all the cabinets for your project need to be fully installed and secured in their final locations.

☐

## **Clear Work Space**

If you are not having new cabinets installed and we are templating over your existing countertops, we need the counter space completely clear. This includes small appliances like your coffee pot.

☐

## **Decision Maker On Site & Pets in the Home**

While we are on site conducting the final measurement, it is required to have a decision maker on site with our technician. We will confirm the details like backsplash height and edge detail while we are on site. All pets need to be put away while we are on site as well.