

OVERLAND EXPLORER CAMP - X

Slide In Pop Up CAMPER

2019 Specification Sheet

\$26 800 USD

External Dimensions: 140" L x 81" W x 62" H
(closed)/84" (open)

Internal Dimensions: 137" L x 78" W x 82" H
(open)

powder coated aluminum extrusions
OEV gen 3 composite floor, walls and roof (>=R8)
fire rated & insulated soft walls (>=R4)
locking roof supports
gas strut assist for lift
DOT LED lighting
dry weight: ~ 1300 lbs (*TBC)

what's included:

Plumbing/Heating/Cooling;

- truma hot water
- forced air heat w/thermostat
- (1)-10 speed roof vent
- 20 gal fresh water tank w/12v pump
- bullfinch outside shower
- smev s/s sink w/flush mount glass top

Electrical;

- 12V G27 agm battery
- USB plugs
- (2)-12V auxiliary connection
- LED side light
- LED interior lighting

Other;

- o/c bed area
- side window

- heki skylight with escape hatch
- rear roof access steps w/grab handle
- rear fixed window
- screen door
- entrance door grab handle
- aluminum propane cabinet w/20 lb bottle
- C-shaped dinette folds down into bed
- quick atch valve and hose for cooktop
- sunbrella fabrics
- 3" medium density foam cushions
- high traffic grade vinyl flooring
- structural powder coated aluminum interior cabinetry
- fire extinguisher
- LP detector
- smoke/CO detector

what's available:

Partner Steel 18" 2 burner stove = \$530
Dometic CFX 65 2.2 cu ft. (53 liter) fridge = \$852
Dometic CF 50 1.7 cu ft. (48 liter) fridge = \$722
100W solar panel w/MPPT 100/30 controller = \$960
120W Go Power Portable Solar Panel w/controller and case = \$550
1500W Go Power Pure Sign Inverter ISW1500 (no charger) = \$823
Shore Power w/Samalex/ Smart Charger = \$432
Victron Battery Monitor bmv-700 = \$441
Battle Born 100Ah Lithium Iron Phosphate Battery (includes an upgraded charger) = \$1959
Easy Hitch Step = \$685
Cabinet w/cushions to house porta potti, creates a "C shaped" dinette = \$741
Back Up Camera with housing = \$472
Cargo Tracking on the roof (both sides,

flat section of roof only) = \$395
fiamma or batwing awning = \$1700
Installation kit (includes); =1923
a) (4) - manual jacks
b) Truck Bed Camper Mounting Brackets
c) (4) - Tork Lift Tie Down latches
d) 1/2" Rubber Bed Mat
e) Electrical tie in for DOT lighting and charger
Ford Installation Labour = \$1020
Chev/GMC, Dodge, Nissan &Toyota Installation Labour = \$1210

OVERLAND EXPLORER



www.overlandindex.com