

SCREEN WALL ON SLOPING GROUND

1) Class 1 cement/lime/sand or cement/sand mortar to be used in accordance with Table 1, B.S. 5628: Part 1: 1992 with cement/lime/sand in proportions of 1:0 to 0.25:4.3

- Finished ground level

2) Plasticised or masonry cement mortars are not to be used.

B385 structural mesh fabric laid with main bars running longitudinally with the strip foundations and having a bottom and side cover of 50mm shall be incorporated in accordance with the Structural Engineer's Design.

8) Walls constructed in stretcher bond shall have Galv. or stainless steel fishtail of spoon ties spaced at 450mm centres both horizontally and vertically


9) For walls constructed using clay bricks of 7-12% water absorption a wall thickness of 215mm will be satisfactory up to 1.75m height above finished ground level.

10) For walls constructed using concrete bricks a wall thickness of 215mm will be satisfactory up to 1.8m above finished ground level.

11) For walls constructed using concrete bricks and a wall thickness of 215mm with a height in excess of 1.8m above finished ground level then integral 328mm thick piers are to be built in at the panel ends and midpoints as indicated on Dwg. No. F7(2).

12) Movement joints are to be constructed at approximately 6m centres to suit brick gauge or changes in direction. Joints must be full height from the foundation, through any DPC's and copings/cappings.

13) All walls on sloping ground to be a min 1800mm high and stepped at 225mm intervals.







10 Gold Tops Newport NP20 4PH

01633 844970 e. info@hammond-ltd.co.uk

www.hammond-ltd.co.uk

© Hammond Architectural Limited 2021 Figured dimensions must be taken in preference to scaled dimensions and any discrepancies are to be referred to Hammond Architectural Ltd. Contractors. subcontractors and suppliers must verify all dimensions on site before commencing any work or making any workshop drawings.