

EOARD OF DIRECTORS
CARL W. SCHLAPPI, Chairman
DENISE TOBIN, Vice Chairwoman
LARRY FRY
JOSEPH H. RADLEY
WILLIAM MESSERSMITH
PAUL WENTZLER
ERNEST LARSON, Commissioner

542 County Farm Road, Suite 202 Montoursville, PA 17754

> Phone: 570-433-3003 Fax: 570-433-3907

> > www.lyco.org

STAFE
MARK N. DAVIDSON, Manager
DENISE MOSER, Sec./Treasurer
RODNEY MOREHART, CBP Tech.
CHAD BOWER Ag. Cons. Te.ch.
CURTIS SWANGER, District Tech,
CAREY ENTZ, Watershed Specialist
JOSEPH AGNONI, E&S Technician

Erosion and Sediment Control for Earth Moving Activities

When is an Erosion and Sedimentation (E&S) plan required?

Any earth disturbance is required to protect the site from accelerated erosion through the use of Best Management Practices (BMPs). Some of these BMPs include, but are not limited to such things as filter fabric fence (silt fence), rock filters, stabilized entrances to the site, grass buffers, diversion of upslope water, and seeding and mulching of disturbed areas.

Any disturbance over 5,000 square feet requires a written E&S plan to be developed and kept on site. Most construction generally that takes place disturbs more than 5,000 sq. ft whether it is building a garage or putting in a driveway.

Additional permits may be required if the earth disturbance is over 1 acre (43,560 sq. ft) over the life of the project. Contact the Lycoming County Conservation District for regulations and guidance.

An E&S plan minimizes sediment runoff from an earthmoving activity. This in turn reduces sediment polluting nearby waterways and water bodies.

The implementation and maintenance of erosion and sediment control BMP's (best management practices) are required to minimize the potential for accelerated erosion and sedimentation, including those activities which disturb less than 5,000 square feet. This means that regardless if a plan is reviewed by the conservation district, best management practices (E&S controls) must be in place, operating properly, and maintained throughout the life of the project.

What does an E&S Plan consist of?

- E&S Plans outline BMPs used to minimize erosion problems associated with earthmoving activities.
- · A complete plan may include:
 - o Topographical maps
 - o Project site sketches
 - o Details for E&S Controls
 - o Soils maps
 - o Narrative description of the project

Please print: Complete all spaces in the application district for assistance.	on. If there are questions, please contact the conservation
Landowner Name:	
Mailing Address	. 1978 t lande de 2000 (1979)
City/State/Zip code	
Contact Information	A AMERICAN SECTION AND ASSESSMENT OF THE SECTION ASSESSMENT OF THE SEC
Excavator Name:	
Mailing Address	
City/State/Zip code	
Contact Information	
Project location	
Has the municipality been contact?	_
Total project (acres) Disturb	ped acres
Name of watershed or nearest receiving stream in watershed or nearest receivin	n. Include distances, landmarks, or special features. Also
77.47.478.534.74.44.44.44.44.44.44.44.44.44.44.44.44	
Briefly describe the project:	
Is the earth disturbance within a floodway or 50 ft fro	om a stream or waterway?
Yes No	

Estimated dates for start and Start date: Total amount of disturbed		-	nd date:	
	Total length	X	Total width	= Area (sq ft)
Access roads/Driveways:		X		Tendar of the Control
Foundation/Building:		Х	and the description of the control o	······································
Lawn/Landscaping:		X		en e
Other:		X	<u> </u>	
			Total area =	sq. ft.
Total area	_ sq ft ÷ 43,560 =		Disturbe	ed acres
occur from this construction Soil Type: List the type(s) of	off from the site? e to surface waters site? Yes of soil found on the	Yess of the (No	of soil locations and a topographic
Sequence of Construction: sheets if needed.	Be specific and pr	rovide st	eps from beginning o	of work to the end. Attach additional
-				

	Rock Construction Entrance	*** 	_Temporary Seeding
	Filter Fabric Fence (Silt fence)	A	_Mulching
· 	Straw Bale Barrier	did i de l'ille de l'ille de l'est e de l'este de l'est	_ Channel lining (netting)
	Rock filters	, and the second se	Diverting upslope water
	Rock outlet protection		Other
	Sediment trap		Other
heck:	_ All items checked above will be to DEP specif	ications.	
	_ Alternative controls will be maintained as per r	nanufacture	r's specifications and are attached.
rior to the sturbance dimentar ompletion) uniform	nt Best Management Practices: e completion of the project, state law requires the e activity requires immediate seeding, mulching tion. Implementation and maintenance of BMP's n of permanent stabilization of the disturbed area n 70% perennial vegetative cover, with density of permanently minimize accelerated erosion and s	or other prot (Best Manag . Types of positions apable of resections sedimentations	tection from accelerated erosion and gement Practices) are required until the ermanent stabilization include: sisting erosion or (2) other acceptable


Maintenance Program: All erosion control practices require maintenance to function properly. Please note the following required maintenance procedures and check other applicable procedures for control measures you will be using.

Until the site is stabilized, all erosion controls must remain in place and be maintained properly. Maintenance must include weekly inspections and inspections after each runoff event. All preventative and remedial maintenance work, including clean out, repair, and replacement must be done immediately.

After final stabilization has been achieved temporary erosion and sedimentation controls may be removed. Any disturbance created by the removal of these controls shall be stabilized. Stabilization is a uniform 70% vegetative cover or another type of type of cover that prevents accelerated erosion from the site (i.e. stone, pavement, etc.)

Sketch Plan: Pease provide a sketch of the project showing the location of all BMPs. Direction of slope should be indicated as well as the entire project and surrounding areas. (Use back of the sheet or additional sheets if necessary.)

Rock Construction Entrance




Topsoil should be removed prior to installation of rock construction entrance.

Runoff shall be diverted from roadway to a suitable sediment removal BMP prior to entering Rock Construction Entrance.

Mountable berm should be installed wherever optional culvert pipe is used. Pipe to be sized appropriately for size of ditch being crossed.


MAINTENANCE: Rock Construction Entrance thickness shall be constantly maintained to the specified dimensions by adding rock. A stockpile shall be maintained on site for this purpose. All sediment deposited on paved roadways shall be removed and returned to the construction site immediately. If excessive amounts of sediment are being deposited on roadway, extend length of rock construction entrance by 50 feet increments until condition is alleviated or install wash rack. Washing the roadway or sweeping the deposits into roadway ditches, sewer, culverts, or other drainage ways is not acceptable.

Sediment Barrier Alignment




Standard Silt Fence (18" High)

*STAKES SPACED @ 8' MAX. USE 2" x 2" (± 3/8") WOOD OR EQUIVALENT STEEL (U OR T) STAKES



JOINING FENCE SECTIONS



ELEVATION VIEW

Fabric shall be 30" minimum.


Silt Fence must be placed at level existing grade. Both ends of the barrier must be extended at least 8 feet up slope at 45 degrees to the main barrier alignment.

Sediment must be removed when accumulations reach 1/2 the above ground height of the fence.


Any section of Silt Fence which has been undermined or topped must be immediately replaced with a Rock Filter Outlet. See standard detail below.

Fence shall be removed and properly disposed of when tributary area is permanently stabilized.

COMPOST FILTER SOCK



SECTION VIEW NTS



Adapted from Filtrexx

Compost Filter Sock shall be placed at existing level grade. Both ends of the sock shall be extended at least 8 feet up slope at 45 degrees to the main sock alignment (see Figure 4.1). Maximum slope length above any sock shall not exceed that shown on Figure 4.2.

Traffic shall not be permitted to cross filter socks.


Accumulated Sediment shall be removed when it reaches $\frac{1}{2}$ the above ground height of the sock and disposed in the manner described elsewhere in the plan.

Socks shall be inspected weekly and after each runoff event. Damaged socks shall be repaired according to manufacturer's specifications or replaced within 24 hours of inspection.


Biodegradable filter sock shall be replaced after 6 months; photodegradable socks after 1 year. Polypropylene socks shall be replaced according to manufacturer's recommendations.

Upon stabilization of the area tributary to the sock, stakes shall be removed. The sock may be left in place and vegetated or removed. In the latter case, the mesh shall be cut open and the mulch spread as a soil supplement

Rock Filter Outlet



OUTLET CROSS-SECTION



UP-SLOPE FACE

A Rock Filter Outlet shall be installed where failure of a Straw Bale Barrier or Filter Fabric Fence has occurred due to concentrated flow.

Sediment must be removed when accumulations reach 1/3 the height of the outlet.

Seeding and Mulching:

Recommended Seed Mixtures

TO OUT	Seeding Rate -	- Pure Live Seed ¹	
Species	Most Sites	Adverse Sites	
Spring oats (spring), or	64	96	
Annual ryegrass (spring or fall), or	10	15	
Winter wheat (fall), or	90	120	
Winter rye (fall)	5 6	112	
Tall fescue, or	60	75	
Fine fescue, or	35	40	
Kentucky bluegrass, plus	25	30	
Redtop ⁴ , or	3	3	
Perennial ryegrass	15	20	
Birdsfoot trefoll, plus	6	10	
Tall fescue	30	35	
Birdsfoot trefoil, plus	6	10	
Reed canarygrass	10 .	15	
Crownvetch, plus	10	15	
Tall fescue, or	20	25	
Perennial ryegrass	20	25	
Crownvetch, plus	10	15	
Annual ryegrass	20	25	
Birdsfoot trefoil, plus	6	10	
Crownvetch, plus	10	15	
Tall fescue	20	30	
Flatpea, plus	20	30	
Tall fescue, or	20	30	
Perennial ryegrass	20	25	
Serecia lespedeza, plus	10	20	
Tall fescue, plus	20	25	
Redtop ⁴	3	3	
Tall fescue, plus	40	60	
Fine fescue	10	15	
Deertongue, plus	15	20	
Birdsfoot trefoil	6	10	
Switchgrass, or	15	20	
Big Bluestem, plus	15	20	
Birdsfoot trefoil	6	10	
Orchardgrass, or	20	30	
Smooth bromegrass, plus	25	35	
Birdsfoot trefoil	Nongraphend 3	10	

Penn State, "Erosion Control & Conservation Plantings on Noncropland,"

Pure Live Seed (PLS) is the product of the percentage of pure seed times percentage germination divided by 100. For example, to
secure the actual planting rate for switchgrass, divide 12 pounds PLS shown on the seed tag. Thus, if the PLS content of a given
seedlot is 35%, divide 12 PLS by 0.35 to obtain 34.3 pounds of seed required to plant one acre. All mixtures in this table are
shown in terms of PLS.

2. If high-quality seed is used, for most sites seed spring oats at a rate of 2 bushels per acre, winter wheat at 11.5 bushels per acre, and winter rye at 1 bushel per acre. If germination is below 90%, increase those suggested seeding rates by 0.5 bushel per acre.


- 3. This mixture is suitable for frequent mowing. Do not cut shorter than 4 inches.
- 4. Keep seeding rate to that recommended in table. These species have many seeds per pound are very competitive. To seed small quantities of small seeds such as weeping lovegrass and redtop, dilute with dry sawdust, sand, rice hulls, buckwheat hulls, etc.
- 5. Use for highway slopes and similar sites where the desired species after establishment is crownvetch.

(Notes continued on following page)

- 6. Use only in extreme southeastern or extreme southwestern Pennsylvania. Serecia lespedeza is not well adapted to most of Pa.
- 7. Do not mow shorter than 9 to 10 inches.
- Seed mixtures containing crown vetch should not be used in areas adjacent to wetlands or stream channels due to the invasive nature of this species.

MULCHING - Mulches absorb rainfall impact, increase the rate of infiltration, reduce soil moisture loss due to evaporation, moderate soil temperatures, provide a suitable environment for germination, and protect the seedling from intense sunlight. All seeded areas shall be mulched or blanketed to minimize the potential for failure to establish an adequate vegetative cover. Mulching may also be used as a temporary stabilization of disturbed areas in non-germinating seasons. Apply clean straw as a mulch at a rate of 3T/acre.

Straw Mulch at Various Rates of Application



EPA-625/3-76-006

Rule of Thumb: If you are seeing bare ground, there is not enough straw.

(Caution: Too much straw can be as harmful as too little straw.)

Apply mulches at the rates shown in Table below.

Straw and hay mulch should be anchored immediately after application to prevent being windblown. A tractor-drawn implement may be used to "crimp" the straw or hay into the soil (about 3"). This method should be limited to slopes no steeper than 3H;1V. The machinery should be operated on the contour. (Note: Crimping of hay or straw by running over it with tracked machinery is not recommended.)


Mulch on slopes of 8% or steeper should be held in place with netting. Lightweight plastic, fiber, or paper nets may be stapled over the mulch according to manufacturer's recommendations.

Shredded paper hydromulch should not be used on slopes steeper than 5%. Wood fiber hydromulch may be applied on steeper slopes provided a tackifier is used. The application rate for any hydromulch should be 2,000 lb/acre (min.).

Mulch Application Rates

	Application Rate (Min.)			
Mulch Type	Per Acre	Per 1,000 sq. ft.	Per 1,000 sq. yd.	Notes
Straw	3 tons	140 lb.	1,240 lb.	Either wheat or oat straw, free of weeds, not chopped or finely broken
Hay	3 tons	140 lb.	1,240 lb.	Timothy, mixed clover and timothy or other native forage grasses
Wood Chips	4 - 6 tons	185 - 275 lb.	1,650 - 2,500 lb.	May prevent germination of grasses and legumes
Hydromulch	l ton	47 lb.	415	See limitations above

Typical On-lot BMPs for Lot above Roadway



If project is below roadway or on a side slope, BMP's should be placed down slope of earth disturbance.