



# ScaleUp Micro Data Center; enabling Data Sovereignty

Savings | Reliability | Intelligence



- Is cloud cost killing you?
- Are hyperscalers scaling up your bills?
- Unsure where your IT budget is really going?



**Cost Savings**  
40-60%



**Uptime**  
99.95%



**AI-Driven**  
Reduce downtime by 70%



**24/7 NOC Monitoring**



**Green and Sustainable Technology**

Website: [www.scaleupinftratech.com](http://www.scaleupinftratech.com)

Contact us:



+91-9811548432



[contact@scaleupinftratech.com](mailto:contact@scaleupinftratech.com)

## Introducing ScaleUp MDC

- Space Optimization
- Speed & Low Latency
- Enhanced Security
- Simplified Deployment
- Plug & Play Data Center
- On-Premises Infrastructure with Cloud Agility

start saving  
today.



## Key Features of ScaleUp POD

- Prefabricated One-in-All Rack
- Precision Cooling
- 6KVA UPS with Lithium Battery
- Fire Precision Systems
- Inbuilt DCIM + SIMS – Monitor, Control & Manage Everything at One Place
- 24/7 NOC Operations

## Who Is It For?

- Government & PSU
- NBFCs & Banks
- Retail Chains
- Real Estate & Smart Cities
- Medical Clinics & Hospitals
- AI/ML Enterprises

## SIMS – Scaleup Infrastructure Management Suite

- DCIM+ – Temp | Humidity | Alerts | Rack View
- IT & Network – CPU | RAM | Disk | Bandwidth
- Billing – Per-U | kWh | Auto Invoices
- Remote Control – SSH | RDP | PDU Reboot
- Multi-Site Dashboard + Auto Escalation

*“From Monitoring to Monetization – Powered by SIMS”*

## Technical Specifications

### Rack & Mechanical Specs

- **Rack Sizes:** 22U – 42U (Customizable)
- **Material:** Powder coated Steel
- **Static Load:** 1000 Kg
- **Dimensions:** 800mm (W) x 1200mm (D)
- **Ingress Protection:** IP54
- **Doors:** Front: Glass
- **Side Panels:** Secured & Integrated

### Monitoring System

- **Rack level:** Environmental, Security & Safety monitoring with alarm system & auto alerts (SMS, Email & SNMP)
- **Sensors:** Temperature, Humidity, Smoke, Water Leak
- **Door Sensors:** Magnetic door sensor
- **Access Control:** RFID / Biometric / Access Card
- **Smoke Detection:** Photoelectric Smoke Sensor
- **Temperature & Humidity:** 0°C to 100°C / 0% to 100% RH
- **Water Leak:** Rope type water leak detection sensor
- **System Log:** Event logging system
- **Power Supply:** Redundant power supply

### Security Features

- **Access Control:** Biometric / Access Card / PIN
- **Emergency Access:** Door Bypass option under critical temperature rise
- **Dual Authentication:** Biometric and Access Card
- **Multi-layer Security:** Dual Authentication and Access Logs

### Power & Connectivity

- **UPS:** Rack-based UPS with 15-minute battery backup
- **PDU:** Rack-based PDU (32A, Single/Three Phase, Remote monitoring, Socket-level monitoring, Surge protection, Load balancing)

### Fire Safety System (GRLS)

- **Temperature & Humidity:** 0°C to 100°C / 0% to 100% RH
- **Smoke Detector:** Photoelectric Smoke Detector
- **Suppression Agent:** NOVEC 1230 / FK 5-1-12
- **Discharge Type:** Direct / Indirect
- **Cylinder Size:** 2L / 4L / 6L / 9L
- **Detection System:** Double Knock Detection System
- **Control Panel:** Microprocessor based control panel
- **Power Supply:** 230V AC, 50Hz
- **Compliance:** UL, LPCB, CE, RoHS

### Cooling System – Integrated 2TR Unit

- **Cooling Capacity:** 1-2TR
- **Cooling Type:** Precision cooling
- **Refrigerant:** Eco-friendly refrigerant
- **Temperature Range:** 18°C to 27°C
- **Humidity Control:** 40% - 55%
- **Airflow:** Front to back airflow
- **Compressor:** Hermetically sealed scroll type
- **Power Supply:** 230V AC, 50Hz



ScaleUp InfraTech Pvt. Ltd. – Redefining Data Center Intelligence

Website: [www.scaleupinftratech.com](http://www.scaleupinftratech.com)