

# **EAST VALLEY METROPOLITAN DISTRICT**

## **WATER LINE CONSTRUCTION NOTICE - July 1, 2025**

### **SUMMARY**

**When:** Anticipated start date is July 14, 2025.

**Where:** Along the frontage road in Algonquin Acres between South Billings Way and South Carson Street.

**What:** Added water lines and the replacement of three fire hydrants.

**Why:** To provide water line looping in this area for improved flow and fire protection pressure. This should help reduce incidences of discolored water caused by iron manganese and allow for better system isolation when shut down is needed.

**Disruption:** Some street lane closures, construction noise and water shutdowns. 72 hour notice will be provided for any water shutdowns.

### **MORE INFORMATION**

RE: Construction Notice, 2025 Capital Improvements Project  
Arapahoe Frontage Road 6" Water Line

A water line replacement project by the East Valley Metropolitan District (District) is scheduled to be performed this summer along the Arapahoe Frontage Road between South Billings Way to South Carson Street, including connections to side streets. The project will create a looping water main system for Blackhawk and Carson Streets, provide capacity for better fire flow and replace aging fire hydrants.

The project includes the installation of approximately 1,100 linear feet (LF) of 6-inch C900 PVC water lines. It also includes removal and replacement of 3 fire hydrant assemblies, connections to existing facilities, asphalt removal & replacement and concrete removal & replacement. The project is being partially funded by grants.

During construction, there will be lane closures and construction noise. We anticipate water shut-downs throughout the project. You will be notified 72-hours in advance of any water shut-downs that directly affect your residence should they occur. After a water outage there is potential for air and/or soil in the water service lines. It is recommended that residents flush their water for 5-minutes using outdoor spigots, sillcocks, hose bibs, etc..

The anticipated start date is on or after July 14, 2025 and the contractor has 60 calendar days to complete the project.

For general questions or concerns, contact the District Engineer:

Purrington Civil, LLC

Steve Homer, P.E.

303-913-6514

For specific construction related questions, contact the Contractor:

Diaz Construction Group, LLC

Luis Diaz, Managing Partner, Project Manager/Supervisor

303-883-3961

Projects of this nature bring a level of disruption to surrounding residences. The District, District Engineer and Contractor will work diligently with the residences to ensure safety, access, water service and cleanliness. Your cooperation is greatly appreciated.

Kind Regards,

East Valley Metropolitan District

