


AI + Cx = Smarter Buildings

October 2025




Introductions

- Mike Ball – Principal
 - Ohio and surrounding regions
- Ben Talbot – Analytics Group Leader
 - BalanceCx development and delivery



Holistic Building Performance



Introduction to the Commissioning Process




AI Use Cases

- Setup
 - Application Development
- Cx
 - Design Document Data Extraction
- Operations
 - Context Aware Chats
 - Energy Efficiency Measure Generator

Application Development

- Claude Code
- Cursor
- OpenAI Codex
- Gemini
- Replit



Design Data Extraction with AI

- Commissioning Data
 - Mechanical Schedules
 - Controls Points Lists
 - Controls Sequence of Operations
- AI Tools
 - Gemini
 - ChatGPT
 - Abby Fine Reader

Setpoints

Design Drawings

AHU-03 TERMINAL AIR BOX SCHEDULE - SINGLE DUCT HOT WATER REHEAT																		
VAV TAG/DAVE #	SERVICE		ROOM #	INLET SIZE	BOX OUTLET	CFM			HEATING COIL							MANUFACTURER	MODEL	MIN. NUMBER OF ROOMS
	ROOM NAMES					COOLING MAX	HEATING	MIN.	FLUID	EAT °F	LAT °F	EWI °F	LWT °F	SENS. CAPACITY MBH	GPM			
VAV-0-01	CORRIDOR A		C100	14	20x18	2500	1200	800	40% P.G.	50.0	85.0	140.0	111.8	32.7	2.50	PRICE	SDV	2
VAV-0-02	CLINICAL OFFICES STAFF TOILET ROOM NITYLING ROOM GROUP PROPLE ROOM		100 100A 100C 100A	12	16x16	1800	880	625	40% P.G.	50.0	85.0		116.8	22.5	2.00	PRICE	SDV	2
VAV-0-03	TOILET ROOM CONSULT CORRIDOR		104 101 100A	6	12x8	480	225	225	40% P.G.	50.0	85.0	140.0	119.2	5.8	0.50	PRICE	SDV	2
VAV-0-04	COMFORT ROOM		102	5	12x8	210	100	75	40% P.G.	50.0	85.0	140.0	120.0	2.6	0.50	PRICE	SDV	2
VAV-0-05	CORRIDOR B		C100	10	14x12	1540	1200	475	40% P.G.	50.0	85.0	140.0	111.8	32.7	2.50	PRICE	SDV	2
VAV-0-06	QUIET LOUNGE		110	5	12x8	230	100	75	40% P.G.	50.0	85.0	140.0	124.8	3.1	0.50	PRICE	SDV	2
VAV-0-07	CORRIDOR VESTIBULE		100B 100B-1	7	12x8	560	290	175	40% P.G.	50.0	85.0	140.0	118.7	7.4	0.75	PRICE	SDV	2
VAV-0-08	CHAIR STORAGE ROOM EQUIPMENT STORAGE ROOM QUIET LOUNGE COMFORT ROOM		112 113 114 116	7	12x8	710	350	225	40% P.G.	50.0	85.0	140.0	114.3	8.9	0.75	PRICE	SDV	2
VAV-0-09	MULTIPURPOSE ROOM		117	7	12x8	840	400	400	40% P.G.	50.0	85.0	140.0	110.6	10.2	0.75	PRICE	SDV	2
VAV-0-10	GROUP THERAPY ROOM		118	5	12x8	290	150	100	40% P.G.	50.0	85.0	140.0	120.5	3.8	0.50	PRICE	SDV	2
VAV-0-11	SALLYPORT CLEAN UTILITY ROOM MECHANICAL ACCESS CORRIDOR		100 112 111 100	9	12x10	1140	540	400	40% P.G.	50.0	85.0	140.0	110.3	13.8	1.00	PRICE	SDV	2
VAV-0-12	SOILED UTILITY ROOM STAFF LOUNGE		120 122	6	12x8	420	225	225	40% P.G.	50.0	85.0	140.0	115.2	5.8	0.50	PRICE	SDV	2
VAV-0-13	ANTE ROOM SECLUSION ROOM SECLUSION ROOM TOILET ROOM		126 128A 128B 128C	7	12x8	600	300	300	40% P.G.	50.0	85.0	140.0	114.3	8.9	0.75	PRICE	SDV	2
VAV-0-14A	FOOD SERVICE		121	6	12x8	380	375	375	40% P.G.	50.0	85.0	140.0	112.5	9.6	0.75	PRICE	SDV	2
VAV-0-14B	DINING ROOM		123	9	12x10	1000	750	750	40% P.G.	50.0	85.0	140.0	112.5	19.2	1.50	PRICE	SDV	2
VAV-0-15	PATIENT LAUNDRY ROOM HOUSEKEEPING ROOM TOILET ROOM TOILET ROOM TOILET ROOM		126 130 125 127 133 100C	9	12x10	1110	730	750	40% P.G.	50.0	85.0	140.0	112.5	19.2	1.50	PRICE	SDV	2
VAV-0-16	QUIET ACTIVITY ROOM		129	5	12x8	180	90	75	40% P.G.	50.0	85.0	140.0	130.1	2.3	0.50	PRICE	SDV	2
VAV-0-17	EXAM ROOM CHARTING ROOM MEDS ROOM		132 136 136A	7	12x8	680	475	475	40% P.G.	50.0	85.0	140.0	113.8	12.1	1.00	PRICE	SDV	2
VAV-0-18	TEAM CONFERENCE ROOM NURSE STATION CORRIDOR		138B 108B	9	12x10	1020	500	400	40% P.G.	50.0	85.0	140.0	112.5	12.8	1.00	PRICE	SDV	2
VAV-0-19	ACTIVITY ROOM CORRIDOR		140 140A	9	12x10	1240	560	500	40% P.G.	50.0	85.0	140.0	109.2	14.3	1.00	PRICE	SDV	2
VAV-0-20	QUIET LOUNGE		142	5	12x8	210	100	75	40% P.G.	50.0	85.0	140.0	120.0	2.6	0.50	PRICE	SDV	2
VAV-0-21	BEDROOM BEDROOM		144 146	6	12x8	480	300	300	40% P.G.	50.0	85.0	140.0	118.0	7.7	0.75	PRICE	SDV	2
VAV-0-22	BEDROOM TOILET ROOM		151 151A	5	12x8	320	225	225	40% P.G.	50.0	85.0	140.0	115.2	5.8	0.50	PRICE	SDV	2
VAV-0-23	HC BEDROOM BEDROOM BEDROOM BEDROOM BEDROOM		141 143 145 147 148	9	12x10	1210	775	775	40% P.G.	50.0	85.0	140.0	111.5	19.8	1.50	PRICE	SDV	2
VAV-0-24	NURSE STATION MAIN TELEPHONE AREA		134 135	10	14x12	1330	680	400	40% P.G.	50.0	85.0	140.0	115.8	16.9	1.50	PRICE	SDV	2
VAV-0-25	ACTIVITY ROOM CORRIDOR		160 160A	8	12x10	960	440	400	40% P.G.	50.0	85.0	140.0	115.8	11.2	1.00	PRICE	SDV	2
VAV-0-26	QUIET LOUNGE		162	5	12x8	210	100	75	40% P.G.	50.0	85.0	140.0	120.0	2.6	0.50	PRICE	SDV	2
VAV-0-27	BEDROOM BEDROOM		164 166	6	12x8	480	300	300	40% P.G.	50.0	85.0	140.0	118.0	7.7	0.75	PRICE	SDV	2
VAV-0-28A	HC BEDROOM BEDROOM BEDROOM BEDROOM BEDROOM		161 163 165 167 168	9	12x10	1100	775	775	40% P.G.	50.0	85.0	140.0	111.5	19.8	1.50	PRICE	SDV	2
VAV-0-28B	BEDROOM TOILET ROOM		171 171A	5	12x8	300	225	225	40% P.G.	50.0	85.0	140.0	115.2	5.8	0.50	PRICE	SDV	2
VAV-0-29	ACTIVITY ROOM CORRIDOR		168 168A	9	12x10	1110	540	475	40% P.G.	50.0	85.0	140.0	115.3	13.8	1.00	PRICE	SDV	2
VAV-0-30	QUIET LOUNGE		162	5	12x8	210	100	75	40% P.G.	50.0	85.0	140.0	120.0	2.6	0.50	PRICE	SDV	2
VAV-0-31	BEDROOM BEDROOM		184 186	6	12x8	480	300	300	40% P.G.	50.0	85.0	140.0	118.0	7.7	0.75	PRICE	SDV	2
VAV-0-32	HC BEDROOM BEDROOM BEDROOM BEDROOM BEDROOM BEDROOM		181 183 185 187 189 191	10	14x12	1470	960	960	40% P.G.	50.0	85.0	140.0	113.8	24.3	2.00	PRICE	SDV	2
VAV-0-33	CHAPEL CORRIDOR		640 C000B	12	16x16	1910	875	875	40% P.G.	50.0	85.0	140.0	115.9	0.0	2.00	PRICE	SDV	2
VAV-0-34	OFFICE		844	5	12x8	200	90	75	40% P.G.	50.0	85.0	140.0	130.1	2.3	0.50	PRICE	SDV	2
VAV-0-35	ADL KITCHEN SALON QUIETCOMFORT CORRIDOR CORRIDOR		646 648 650 652C C000C	16	20x18	4125	1910	1500	40% P.G.	50.0	85.0	140.0	113.7	48.8	4.00	PRICE	SDV	2
VAV-0-36	ELECTRICAL ROOM		113	5	12x8	325	COOLING ONLY	100	-	-	-	-	-	-	-	PRICE	SDV	COOLING ONLY
VAV-0-36	MECHANICAL EQUIP. PLATFORM		AREA C	12	16x16	2050	1010	625	40% P.G.	50.0	85.0	140.0	112.2	25.8	2.00	PRICE	SDV	2
NOTES: (ALL NOTES APPLY)																		
NEITHER RADIATED NOR DISCHARGE SOUND LEVELS SHALL EXCEED NC 35 AT 1" INLET STATIC PRESSURE WHEN TESTED PER AIR STANDARD 885-68 USING 5/8" 20 LB DENSITY MINERAL FIBER CEILING TILE.																		

Digital Validation


BalanceCX		Setpoint Testing		Templates		Site Setpoints		Reports	
BT Ben Talbot Kaban Permanent Partner		Setpoint Testing / Site Setpoints							
Setpoints		VAV	Apply Tags	Template		Update		Search...	
Total Assets: 46		Pass: 175		Fail: 5		Missing or N/A: 4			
ASSET NAME		MAXIMUM COOLING AIRFLOW		MAXIMUM HEATING AIRFLOW SETPOINT		MINIMUM AIRFLOW SETPOINT		UNOCCUPIED AIRFLOW	
		Design	Actual	Design	Actual	Design	Actual	Design	Actual
VAV 1-1-01		600.0	600.0	180.0	180.0	180.0	180.0	120.0	120.0
VAV 1-1-02		390.0	390.0	15.0	15.0	15.0	15.0	80.0	80.0
VAV 1-1-03		160.0	160.0	45.0	45.0	45.0	45.0	30.0	30.0
VAV 1-1-04		330.0	330.0	100.0	100.0	100.0	100.0	65.0	65.0
VAV 1-1-05		680.0	680.0	205.0	205.0	205.0	205.0	130.0	50.0
VAV 1-1-06		890.0	890.0	245.0	245.0	245.0	245.0	160.0	160.0
VAV 1-1-07		250.0	250.0	125.0	125.0	125.0	125.0	90.0	90.0
VAV 1-1-08		260.0	260.0	80.0	80.0	80.0	80.0	50.0	50.0
VAV 1-1-09		90.0	90.0	45.0	45.0	45.0	45.0	30.0	30.0
VAV 1-1-10		400.0	400.0	125.0	125.0	125.0	125.0	85.0	85.0
VAV 1-1-11		570.0	570.0	170.0	170.0	170.0	170.0	110.0	110.0
VAV 1-1-12		480.0	480.0	140.0	140.0	140.0	140.0	95.0	95.0
VAV 1-1-13		450.0	450.0	135.0	135.0	135.0	135.0	90.0	90.0
VAV 1-1-14		890.0	N/A	175.0	N/A	175.0	N/A	120.0	N/A

Points & Sequences

Controls Submittal

Controls Readiness Dashboard

TERMINAL BOX WITH REHEAT POINTS LIST																	
TAG	DESCRIPTION	GRAPHIC	DEFAULT VALUE	HARDWARE POINTS				SOFTWARE POINTS				ALARMS				DEVICE	REMARKS
				AJ	AO	BI	BO	AV	BV	SCHEDULE	TREND	HIGH LIMIT	LOW LIMIT	DEVICE FAIL	COM FAIL		
FE001	SA AIRFLOW	X		X				X								AVERAGING PYTOT TUBE SENSOR	
FC002	DAMPER POSITION	X			X			X								MOTORIZED DAMPER ACTUATOR	
TCV003	HW CV POSITION	X			X			X								CONTROL VALVE ACTUATOR	
TE004	SA TEMPERATURE	X	55 DEG F	X				X			X	X				RTD	
TES05	ZONE TEMPERATURE SENSOR	X	72 DEG F	X				X			X	X	X			ZONE THERMOSTAT	
IZ006	ZONE TEMPERATURE ADJUST	X						X								OCCUPANT ADJUST ON ZONE THERMOSTAT	
TCV007	RADIANT FLOORING VALVE	X				X		X								VALVE ACTUATOR	
GENERAL NOTES:																	
1. PROVIDE FACTORY MOUNTED ELECTRONIC CONTROLS FOR STANDALONE TERMINAL BOX OPERATION.																	
REMARK NOTES:																	
A. THERMOSTAT SHALL BE PROVIDED WITH OCCUPANT ADJUSTMENT CAPABILITY.																	




OPERATIONAL INTENT FOR TERMINAL UNIT WITH REHEAT AND RADIANT FLOORING

SYSTEM DESCRIPTION
The system consists of a thermal control zone with embedded radiant heating tubing in the floor and a manufacturer's packaged terminal air unit with hydronic reheat coil, complete with factory mounted and wired electronic controls and return duct space temperature sensor. Setpoint adjust shall be available via the front end only. Unit shall include leaving air temperature sensor, integral flow (CFM) sensing device, and air control damper. The radiant heating system shall be utilized to offset envelope heat loss. Reheat of the VAV terminal unit is provided only to prevent over-cooling when space heat gain does not meet minimum required ventilation rate. VAV terminal unit is not intended to provide supplemental heat to the radiant system.

OPERATION
Heating - Radiant floor shall be utilized to provide heating to the space. Upon a drop in space temperature below setpoint minus differential (ie 2 deg F), open control valve of the radiant floor heat zone associated with VAV terminal unit. Upon rise in radiant floor temperature to within 1 deg (adj) of space temperature setpoint close control valve of the radiant floor heat zone associated with VAV terminal unit. Differentials of radiant zone active/inactive shall be tuned during startup/commission phase to eliminate overshoot after slab heat valve is closed. During heating mode, the VAV terminal unit shall be position at minimum CFM ventilation rate and provide neutral supply air temperature to the space. Modulate reheat valve as necessary to achieve neutral discharge air temperature.

Cooling - Upon rise in space temperature from setpoint to above setpoint. Reheat valve shall be modulated closed to reduce supply air temperature from neutral to AHU discharge temperature. Upon continued rise in space temperature above setpoint plus differential (ie 2 deg F), increase air flow setpoint (target CFM) for terminal unit, and open control damper accordingly to provide target CFM.





Gemini

2.5 Flash

Upgrade J

Level-up your Gemini app experience


Get more access to new and powerful features in the Google AI Pro plan for \$19.99 \$0/month for 1 month

Try now


Hello, Joshua

What should we do today?


Make a photo look like instant film




Create a professional headshot



Make my own custom mini figure




Give me a 90s pixie cut



Ask Gemini

+ Tools



Date Printed: 11/7/2023

PRICE

Tag	Max Primary (CFM)	Min Primary (CFM)	Reheat (CFM)	Inlet	* Max Disc NC 2008	* Max Rad NC 2008	LAT (Y)	LAT (Y)	EC Capacity (kW)	Volts	MOP	MCA	Weight (lbs)
WU-1-01	400	180	180	0	20.75	-	15	86	1.5	277.4	15	1.4	42
WU-1-02	880	115	115	0	24.25	21.05	15	87	1.0	277.4	15	4.5	38
WU-1-03	150	80	80	0	-	-	15	83	0.5	277.4	15	2.5	38
WU-1-04	410	125	125	0	-	-	15	84	1.0	277.4	15	4.5	42
WU-1-05	680	205	205	0	11.25	27.01	15	82	1.0	277.4	15	1.4	42
WU-1-06	810	240	240	10	-	-	15	78	1.0	277.4	15	1.4	42
WU-1-07	230	75	125	0	11.05	-	15	84	1.0	277.4	15	6.0	38
WU-1-08	810	100	100	0	24.05	27.01	15	86	1.0	277.4	15	6.0	38
WU-1-09	150	80	80	0	-	-	15	83	0.5	277.4	15	2.5	38
WU-1-10	420	125	125	0	-	-	15	84	1.0	277.4	15	4.5	42
WU-1-11	170	170	170	0	-	-	15	77	1.0	277.4	15	4.5	42
WU-1-12	480	140	140	0	-	-	15	80	1.0	277.4	15	4.5	42
WU-1-13	430	130	130	0	-	-	15	80	1.0	277.4	15	4.5	42
WU-1-14	180	175	175	0	20.05	-	15	76	1.0	277.4	15	4.5	42
WU-1-15	230	80	100	0	-	-	15	80	0.5	277.4	15	2.5	38
WU-1-16	780	270	270	10	-	-	15	80	1.0	277.4	15	1.4	42
WU-1-17	440	130	130	0	-	-	15	86	1.0	277.4	15	1.4	42
WU-1-18	230	80	100	0	-	-	15	82	0.5	277.4	15	2.5	38
WU-1-19	230	80	80	0	-	-	15	80	0.5	277.4	15	2.5	38
WU-1-20	1010	205	575	12	-	-	15	91	5.0	480.0	15	8.0	38
WU-1-21	730	210	590	0	21.05	25.01	15	90	0.5	480.0	15	5.7	42
WU-1-22	110	80	80	0	-	-	15	82	0.5	277.4	15	2.5	38
WU-1-23	130	130	130	0	-	-	15	90	1.0	277.4	15	1.4	42
WU-1-24	110	130	130	0	-	-	15	91	1.0	277.4	15	1.4	42
WU-1-25	110	130	130	0	-	-	15	91	1.0	277.4	15	1.4	42
WU-1-26	1400	400	400	14	-	-	15	89	4.0	480.0	15	6.0	71
WU-2-01	470	110	110	0	24.05	27.01	15	86	1.0	277.4	15	4.5	38
WU-2-02	130	130	130	0	-	-	15	80	1.0	277.4	15	1.4	42
WU-2-03	630	180	180	0	20.05	-	15	86	1.0	277.4	15	1.4	42
WU-2-04	2800	575	575	18	-	10.90	15	14	0.5	277.4	15	2.5	38
WU-2-05	640	180	180	0	21.05	-	15	79	1.0	277.4	15	4.5	42
WU-2-06	820	80	80	0	21.05	-	15	74	0.5	277.4	15	2.5	38
WU-2-07	130	75	15	0	21.05	-	15	80	0.5	277.4	15	2.5	38
WU-2-08	120	80	80	0	-	-	15	81	0.5	277.4	15	2.5	38
WU-2-09	810	240	240	10	-	-	15	76	1.0	277.4	15	1.4	42
WU-2-10	100	100	100	0	-	-	15	80	1.0	277.4	15	1.4	42
WU-2-11	1170	175	420	12	-	-	15	80	6.0	480.0	15	6.0	38
WU-2-12	100	100	100	0	-	-	15	80	0.5	277.4	15	1.4	42
WU-2-13	1100	450	750	14	-	-	15	89	7.0	480.0	15	11.0	71
WU-2-14	140	80	80	0	-	-	15	81	0.5	277.4	15	2.5	38
WU-2-15	130	80	80	0	-	-	15	81	0.5	277.4	15	2.5	38
WU-2-16	110	100	100	0	-	-	15	79	1.0	277.4	15	4.5	42
WU-2-17	740	220	220	10	-	-	15	80	1.0	277.4	15	1.4	42
WU-2-18	170	80	80	0	21.05	-	15	76	0.5	277.4	15	2.5	38
WU-2-19	230	85	85	0	21.05	-	15	77	0.5	277.4	15	2.5	38
WU-2-20	1400	400	400	14	-	-	15	76	2.0	277.4	15	12.0	71
Totals	18670	7670	8010	179									

Airflow = 5,287
 NO demand CFM Required per line.
 1. Demand (-) indicates NC values less than 0.
 2. Sound power levels are given in dBA @ 100.
 3. *** Discharge sound power levels 2008* do not include duct and reflection, for the most current data based on AHRAE Standard 130-2008 and ANSI Standard 90-2011 reference "Discharge sound power levels."
 4. Demand (-) indicates sound power levels below 10-25-28-32-35-37 for each octave band, values below these sound power levels are considered below significance per ANSI 90-2011.
 5. Minimum operating pressure in the entrance static pressure required to operate the terminal flow assembly at maximum primary flow with a wide open design.
 6. Airflow is given in cubic feet per minute (CFM).
 7. Air pressure drop is given in inches water gauge (in. w.g.), and water pressure drop is given in feet of water gauge (ft. w.g.).
 8. * NC values are derived from sound power levels obtained in accordance with ASHRAE Standard 130-2008 and ANSI Standard 90-2011.
 These values are NOT the most current method for estimating NC values because ANSI 90-2008 does not include duct and reflection corrections.

Operations




- Energy Efficiency Measure Generator (Chat GPT)
- Using AI to make sense of sensor data (BalanceCx with Chat GPT)






Energy Efficiency Measure Generator

By Ben Talbot 🧑

Upload information about HVAC equipment, and get a variety of improvement recommendations that range from capital upgrade options, to sequence of operations recommendations, to current alarms or faults.

 AHU-1 (1).csv
Spreadsheet

Electrical Phase 3 ph
Electrical Voltage 460 V
Heating Capacity 347000 BTU/hr
Heating Coil Flow 37.4 gpm
Manufacturer Trane [Show Sources](#)
Model Number CSAA030 [Show Sources](#)
Relief Motor Horsepower 5 hp
Supply Motor Horsepower 1 hp
Year Installed 2020 [Show Sources](#)



Fault Quick Look

3
HIGH21
MEDIUM37
LOW

Fault Name	Length	Quantity	Priority
CHWPrimaryLoop.Fault_CHWTemperatureSetpointTuning	40 h & 30 m	64	Low
CHWPrimaryLoop.Fault_MinimumCHWFlowNotMet	26 h & 0 m	40	Low
AHU-6.Fault_DischargeAirTemperatureControl	81 h & 0 m	26	Low
AHU-7.Fault_CoolingCoilLowDeltaT	27 h & 30 m	20	Low
AHU-5.Fault_DischargeAirTemperatureControl	49 h & 0 m	20	Low
AHU-1.Fault_DischargeAirTemperatureControl	49 h & 0 m	18	Low
AHU-2.Fault_DischargeAirTemperatureControl	36 h & 30 m	18	Low
AHU-3.Fault_DischargeAirTemperatureControl	37 h & 30 m	14	Low
AHU-4.Fault_DischargeAirTemperatureControl	35 h & 0 m	14	Low

Task List

You have no tasks assigned for this site.

Functional Testing Summary

Total Assets:

107

Assigned Template:

0/107

Data Mapping:

0/0

Data Quality:

0/0/0/0

Test Results:

0/0 (0)

Configure Tests

Test Readiness

Test Results

Data Quality Summary

Number of Assets:

111

Number of Raw Points:

425

Number of Mapped Points:

231 (54%)

Mapped Points with Recent Data:

226 (98%)

Configure Assets

Configure Points

Latest Energy Data July 2025 Performance

Site EUI:

43.2 kBtu/ft²

Median EUI:

48.1 kBtu/ft²

Change from Previous Month:

0.7%

Fault Quick Look

0
HIGH121
MEDIUM161
LOW

Fault Name	Length	Quantity	Priority
Chiller.Fail	63 h & 15 m	17	Low
CHWPrimaryLoop.Fault_CHWTemperatureSetpointTuning	5 h & 15 m	17	Low
VAV-9-20.Fault_CO2AboveOptimal	70 h & 15 m	12	Medium
AHU-5.Fault_DCVNotOperating	79 h & 30 m	12	Medium
VAV-7-06.Fault_CO2AboveOptimal	37 h & 0 m	11	Medium
VAV-9-16.Fault_CO2AboveOptimal	81 h & 45 m	11	Medium
VAV-8-05.Fault_AirflowHigh	95 h & 45 m	10	Medium
AHU-1.Opportunity_StaticPressureResetUp	70 h & 15 m	10	Medium
VAV-R-30.Fault_CO2AboveOptimal	61 h & 45 m	10	Medium

Task List

You have no tasks assigned for this site.

Functional Testing Summary

Total Assets:

118

Assigned Template:

0/118

Data Mapping:

0/0

Data Quality:

0/0/0/0

Test Results:

0/0 (0)

Configure Tests

Test Readiness

Test Results

Data Quality Summary

Number of Assets:

121

Number of Raw Points:

1372

Number of Mapped Points:

1350 (98%)

Mapped Points with Recent Data:

1343 (99%)

Configure Assets

Configure Points

Latest Energy Data July 2025 Performance

Site EUI:

48.2 kBtu/ft²

Median EUI:

54.2 kBtu/ft²

Change from Previous Month:

1.4%

Site Configuration

Site Configuration / Site Information

Raw Points

Site Assets

Auto Mapping

Asset Tags

Site Info

Site Details

Basic information about this site (read-only)

Site Name

Robinson Elementary School

Tenant/Client

Pasco School District

Timezone

US/Pacific

Geographic Details

Location and geographic information for this site

Zip Code *

99301

Look Up Location

City *

Enter city name

State *

Select State

US postal code for location lookup

Latitude

40.7128

-90 to 90 degrees

Longitude

-74.0060

-180 to 180 degrees

ASHRAE Climate Zone

Select Climate Zone

Energy code climate zone classification

Building Details

Physical characteristics and specifications of the building

Building Type

Select Building Type

Year Built

1995

Construction completion year

Square Footage

50000

Total building area in sq ft

Controls Vendor

Siemens, Johnson Controls, etc.

Primary building automation vendor

Save Changes

Reset Form



Building Performance