

RV Covers

AL, AR, GA, IN, KY, LA, MO, MS, NC, OK, SC, TN, TX, VA



STANDARD FEATURES Rated for 35PSF-140MPH (3 second austs, not sustained)

RV carports features include the following: 14 gauge galvanized steel framing, 29 gauge metal roofing with 20 year Beckers paint system, framing spaced 5' on center, double base rail, double legs, includes both peak and leg bracing for additional strength and stability. Concrete Anchors or Rebar Anchors, and Earth Auger Anchors included in base price. Base leg height is 15' tall. Please note: Eagle Carports, Inc. does not provide site work.



MORE INFO!

SCANFOR



- All cement pads must have turn down footers.
- Price does not include site preparation.
- Lot must be cleared and leveled prior to installation.

FREE EAGLE W/PURCHASE OF GABLE END OR CLOSED END FREE INSTALLATION

90 DAY WORKMANSHIP WARRANTY

FINANCING & RTO

Pricing shown below is for Risk Category I/Wind Exposure B.

18'-30'W OPTIONS	20′L	25′L	30′L	35′ L	40′ L	45′L	50′L
FLUSH MOUNT CONCRETE KIT	\$400	\$440	\$480	\$520	\$560	\$600	\$640

Flush mount kits allow cement pads to be the exact width and length of the building without requiring a 2" perimeter.

늦	HEIGHT	20′ L	25′L	30′L	35′L	40′ L	45′L	50′L
E HEIGHI	*15′	Incl.						
EAVI	*16′	\$125	\$150	\$175	\$200	\$225	\$250	\$275

* Must include lift for installation, Refer to Lift Rental Guide

BOTH ES	HEIGHT	20′L	25′L	30′L	35′L	40′L	45′ L	50′L
CLOSE BC SIDES	*15′	\$2,125	\$2,605	\$3,085	\$3,565	\$4,045	\$4,525	\$5,005
CLC	*16′	\$2,200	\$2,705	\$3,210	\$3,715	\$4,220	\$4,725	\$5,230
V. WA	INSCOTING	\$325	\$400	\$475	\$550	\$625	\$700	\$775

* 15'-16' vertical siding included

NE ind	HEIGHT	18′W	20′W	22′W	24′W	26′W	28′W	30′W
CLOSE ONE END Per End	*15′	\$1,700	\$1,875	\$2,050	\$2,125	\$2,225	\$2,375	\$2,575
98	*16′	\$1,880	\$2,070	\$2,260	\$2,360	\$2,450	\$2,625	\$2,835
V. WA	AINSCOTING Per End	\$300	\$325	\$350	\$375	\$425	\$450	\$475

* 15'-16' vertical siding included



EXTRA PANELS							
LENGTH	PRICE	*J-TRIM					
20′	\$140	Add \$75					
25′	\$160	Add \$90					
30′	\$180	Add \$105					
**35′	\$200	Add \$120					
**40′	\$225	Add \$135					
**45′	\$250	Add \$150					
**50′	\$275	Add \$165					

^{*}J-Trim price covers both sides **Not a continuous panel

ROLL UP GARAGE DOORS					
6'x7'	\$600				
8'x8'	\$800				
9'x8'	\$850				
10'x8'	\$950				
10'x10'	\$1,200				
12'x12'	\$2,100				
*14'x14'	\$3,000				
*Special o	rder door,				

lift required	for installation

45° TRIM KIT Garage Door or Frame Out Add-on					
PER OPENING	\$100				
Must close end or side					

WALK-IN DOORS - 36 ". MHD:Right H. Outswing RD: Rig	
MOBILE HOME DOOR	\$400
9 LIGHT STEEL DOOR	\$700*

WINDOWS White with Grid				
24"x36"	30"x36"			
\$200	\$220			

^{*}Special Order item. ONLY available to install on cement.

GABLE ON END Priced Per End For Vertical Gable multiply price by 1.5, for Extended Gable* multiply by 2.								
18′W	20′W	22′W	24′W	26′W	28′W	30′W		
\$290	\$320	\$350	\$380	\$425	\$475	\$525		

*Extended Gables have an additional 3' of coverage.

TRIMMED HALF PANELS 12' - 30' Kit made for both sides. Package price cannot be halved.							
20′L	25′L	30′L	35′L	40′L	45′L	50′L	
\$215	\$240	\$265	\$300	\$345	\$425	\$455	

	CORNER KIT Must add Gable					
Use f	Legs 13' - 16'	Legs 9' - 12'	Legs 6' - 8'			
WIND	\$225 \$375 \$525					
\$70	2' wide max on each side. Must pair with gable.					
	ne.	ısı pair witn qat	IVIU			

FRAME OUTS Use for framing of customer provided windows & doors						
WINDOW WALK-IN DOOR						
\$70 \$85						

STANDARD HEADERS / LARGE OPENINGS UNITS 12' - 30'							
OPENINGS ONLY		OPENING WITH DOO	OR				
ON END 6'-16' OPENING	\$125	ON END 6'-12' OPENING	\$0				
ON SIDE 6'-12' OPENING	\$225	ON END 13'-14' OPENING	\$125				
ON SIDE 13'-16' OPENING	\$300	ON SIDE 6'-12' OPENING	\$125				
		ON SIDE 13'-14' OPENING	\$200				

*Side must be 1' taller than desired door height. 14'x14' requires 2 foot taller

WELDED TRUSS UPGRADE 18' - 24'	20'L	25′L	30'L	35′L	40'L	45′L	50′L
6'TRUSS FOR 18-24'WIDTHS	\$200	\$250	\$300	\$350	\$400	\$450	\$500

EXTRA RAFTERS/	RV 12' - 24'W	RV 26'-30'W	ADDITIONAL HEIGHT
BOWS	\$600 EA.	\$675 EA.	6' standard incl. \$20 per foot up to 14' tall.

SIDE CONNECTION FEES Per Side					LEAN TO CONNEC	TION FEES On End			
20'L	25′L	30′ L	35′L	40′L	45′L	50′L	12' - 22' Wide 24' Wide		
\$120	\$140	\$160	\$180	\$200	\$220	\$240	\$300	\$400	

INSULATION		
DOUBLE BUBBLE TYPE (MOISTURE BARRIER)	R5	\$1.50 SF
2"FIBERGLASS	R7	\$2.25 SF

ROOF (Vertical Only): Add 2' to width and multiply by length. Ex. 24' wide \times 26' long $26 \times 26 = 676$ SF \times \$/per SF

SIDES: Multiply leg height by length by 2. Ex. 26' long x 10' tall $10 \times 26 = 260 \times 2 = 520 \text{ sf } x \text{ $/\text{per SF}}$

ENDS: Add 1.5 to leg height, multiply by building width. Ex. 24' wide x 10' tall $11.5 \times 24 = 276 \times 2 = 552 \text{ sf x } \text{ }$ /per SF

ADDITIONAL LABOR FEES	20' L	25′L	30′L	35′L	40′ L	45′ L	50′L
BUILD OVER FEE	\$150	\$175	\$200	\$250	\$275	\$325	\$350
CUT LEGS ON SITE*	\$100	\$125	\$150	\$175	\$200	\$225	\$250

*Cut leg fee has a maximum of 12" adjustment possible, either front to back or side to side. Please note, side to side on level lots will result in gap underneath garage doors.

CONCRETE DIMENSIONS

All stated dimensions are in reference to the frame size, not the roof dimensions.

All cement pads require 2" wider on all sides. Ex. 20' wide x 30' long unit will need a 20'4" wide x 30'4" long pad.