

Company Name: _____ Dept: _____ Location: _____ Date: _____

#215

JOB SITE TRAFFIC MANAGEMENT

GENERAL REQUIREMENTS

- Riding on any vehicle or machinery is prohibited.
- All vehicles should travel on the right hand side of the road.
- 10 mph speed limit should be observed in construction areas, slower speeds may be required due to activity.
- Observe posted speed limits when traveling outside the construction area.
- Always yield to pedestrians.
- If view is obstructed, come to a complete stop and then proceed with caution.
- At intersections where a STOP sign is not posted, slow down and look for vehicles or pedestrians.
- Always check for pedestrians and vehicles before reversing or pulling away from the curb.
- Awareness of your surroundings is the first and best line of defense when driving in a congested work zone.
- Be patient, a few minutes to ensure safe travel can prevent an accident from happening.
- Cell phone use should be prohibited when driving or working in close proximity to construction vehicles & equipment.

KEY POINTS

- Being aware of your surroundings is essential when driving in a congested work zone.
- Sub-contractors' foremen should conduct a site orientation with any new employee to the site in regards to traffic and site safety (worker or operator).
- Parking in front of fire hydrants is prohibited in construction zones.
- Sidewalks and footpaths should be kept clear whenever and wherever possible.
- For most operations, the use of signs, cones, or flagmen is all sufficient means of controlling traffic.
- Flaggers should be utilized at locations on a construction site where barricades and warning signs cannot control the moving traffic.

Meeting Conducted By:

Meeting Attended By:

Print Name

Signature

Document Filing Reference

Notes & Suggestions