



GENERAL NOTES FOR UTILITY PLATFORMS:

(1) GENERAL CONTRACTOR TO PROVIDE 121 COATS CLEAR GLOSS POLYURETHANE FLOOR SEALER FOLLOWING FINAL CLEAN AND APPROVAL OF ARCHITECT.

(2) CMU WALLS WHERE INDICATED SHALL BE RUN SOLID TO BOTTOM OF DECK, GROUTED SOLID TO DECK. ALL OTHER CMU WALLS, UNLESS OTHERWISE NOTED, SHALL BE RUN TO FULL BLOCK COURSE ABOVE CEILING. UNBRACED SECTIONS OF LESS-THAN-FULL-HEIGHT WALLS SHALL BE BRACED TO ROOF. SEE STRUCTURAL DRAWINGS.

(3) CMU WALL INTERSECTIONS SHALL BE BRACED WITH HOT DIPPED GALVANIZED HARDWARE CLOTH EACH COURSE, AND PREFORMED "T" HORIZONTAL REINFORCING AS SPECIFIED AT 16" ON CENTER.

(4) PROVIDE WALL CONTROL AND EXPANSION JOINTS WHERE SHOWN AND DETAILED OR IN PRE-APPROVED, ALTERNATING LOCATIONS 32" ON CENTER MAXIMUM PROVIDED IN ONE SIDE OF EACH OPENING IN MASONRY WALLS; BOTH SIDES IN OPENINGS WITH WIDTH EXCEEDING 5'-0". SEE DETAIL.

(5) PROVIDE WALL EXPANSION JOINTS AT POINTS AND INTERSECTIONS WHERE INDICATED. 7/8" WIDE, FILLED WITH EXPANSION JOINT MATERIAL AND CAULK, WITH BACKER ROD.

(6) ALL 45° CMU WALL BENDS SHALL BE CONSTRUCTED WITH SPECIAL PRECAST UNITS.

(7) INTERIOR CMU JOINTS SHALL BE TOOLED CONCAVE.

No.	Date	Revision
1	3/20/25	ADDED FIRE EXTINGUISHERS PER ADDENDUM #2

Hite associates
ARCHITECTURE / PLANNING / TECHNOLOGY
2800 Meridian Drive / Greenville, NC 27834 / tel (252) 757-0333



NEW CTE BUILDING FOR
Bertie High School
716 US 13 North / NCDPS Unit 080 - School 312
Windsor / Bertie County / North Carolina

Project No. 22351
Date: December 18, 2024
Drawing no. **A 103**