

ESTIMATE



Prepared For

patti griffin
3233 davis rd
marrietta, ga 30062

POOL SUPPLY ATLANTA

2900 Holcomb Bridge Road
Alpharetta, GA 30022
Phone: (678) 691-6124
Email: bryan@poolsupplyatlanta.com
Web: POOLSUPPLYATLANTA.COM

Estimate # 1058
Date 07/18/2025

Description	Total
PEBBLE -- TIER 1 AQUA WHITE, SALT & PEPPER, FRENCH GREY, AQUA BLUE, AQUA COOL, TAHOE BLUE https://photos.app.goo.gl/NSrYaauX7YWhfx18 (TIER 1) https://poolsupplyatlanta.com/pool-renovations/ (ALL FINISHES)	\$39,462.50
TILE - standard tile 6*6 LIMITED SELECTION LAGUNA, OXFORD, LAKES, OCEANSIDE, ODYSSEY, SEABREEZE, LUCIANO, NAUTILUS	\$9,000.00
TILE - SKIMMER(S) TO TILE AROUND EACH SKIMMER ADD \$100	\$400.00
SKIMMER REPLACEMENT each skimmer replacement \$1850 each	\$7,400.00
MARKING TILE (NUMBERS AND LETTERS) water line tiles numbers and letters	\$1,120.00
CHIP AROUND RACING Lanes SAVE EACH RACING LANE \$450 EACH	\$1,800.00

Vgb main drain covers 12*12	\$700.00
each drain and grate \$350	

CONCRETE - POURING NEW	\$19,200.00
------------------------	-------------



Spray deck - Resurfacing Concrete	\$11,120.00
Preparation and Installation	

1. Power wash Deck
2. Base over all surfaces with pre-blended modified cement aggregate and polymers, for bond level and repair.
3. Custom texture over the entire area for slip resistance, coolness and pattern. The coverage to be 100% and meets ASTM-C348 for flexural strength. This to comply with County Code.
4. Color of choice is to be determined.
5. Repair cracks by grinding and fill with a 2-part polyurethane caulking (If crack repairs are part of the agreement)
6. The is a deck coating and will not level the concrete

Notes: Terms and Conditions:
It would take approximately 4 to 6 days to complete this project, weather permitting.

Warranty: the work for a period of one years from the date of completion of the work, against defective material or workmanship including bonding failure, chipping or peeling of the application. Resurfacing involves sprayed materials and there will be some over- spray onto landscaping. We will keep over-spray to minimum.

Due to inherent movement of the surfaces to which we apply our product, no warranty, expressed or implied is made concerning cracks that may appear in the work.

We assumes no obligation or responsibility for deck drainage (standing water) unless the base

concrete has been installed by Pool Supply Atlanta. If available, please turn off your sprinkler system near the pool during the process.

Crack Stripping has a 30-day warranty due to the fact that cracks can be caused by settling, drainage issues, and/or soil conditions which are beyond our control. The crack filling process is not necessarily a repair as much as it is a preventative for allowing moisture to penetrate through the crack, which will cause more soil erosion and damage to the deck from settling and freeze/thaw environments. In addition, the Crack Stripping also gives your deck a beautiful look to your backyard.

The warranties are effective only if the buyer has complied with all terms, conditions and payments as specified.

Please call us with any questions or to advise scheduling. We look forward to working with you.



CONCRETE -- REMOVE	\$34,200.00
REMOVE CONCRETE	



CONCRETE - POURING NEW	\$45,600.00
------------------------	-------------



Spray deck - Resurfacing Concrete

\$26,410.00

Preparation and Installation

1. Power wash Deck
2. Base over all surfaces with pre-blended modified cement aggregate and polymers, for bond level and repair.
3. Custom texture over the entire area for slip resistance, coolness and pattern. The coverage to be 100% and meets ASTM-C348 for flexural strength. This to comply with County Code.
4. Color of choice is to be determined.
5. Repair cracks by grinding and fill with a 2-part polyurethane caulking (If crack repairs are part of the agreement)
6. The is a deck coating and will not level the concrete

Notes: Terms and Conditions:

It would take approximately 4 to 6 days to complete this project, weather permitting.

Warranty: the work for a period of one years from the date of completion of the work, against defective material or workmanship including bonding failure, chipping or peeling of the application. Resurfacing involves sprayed materials and there will be some over- spray onto landscaping. We will keep over-spray to minimum.

Due to inherent movement of the surfaces to which we apply our product, no warranty, expressed or implied is made concerning cracks that may appear in the work.

We assumes no obligation or responsibility for deck drainage (standing water) unless the base concrete has been installed by Pool Supply Atlanta. If available, please turn off your sprinkler system near the pool during the process.

Crack Stripping has a 30-day warranty due to the fact that cracks can be caused by settling, drainage issues, and/or soil conditions which are beyond our control. The crack filling process is not necessarily a repair as much as it is a preventative for allowing moisture to penetrate through the crack, which will cause more soil erosion and damage to the deck from settling and freeze/thaw environments. In addition, the Crack Stripping also gives your deck a beautiful look to your backyard.

The warranties are effective only if the buyer has complied with all terms, conditions and payments as specified.

Please call us with any questions or to advise scheduling. We look forward to working with you.



MARKING TILE (NUMBERS AND LETTERS)	\$1,440.00
-------------------------------------	------------

Deck side tiles

numbers and letters

COPING TRAVERTINE (NOCHE & IVORY)	\$12,375.00
-----------------------------------	-------------

REMOVE AND REPLACE COPING

raise the bond beam to level the pool	\$7,600.00
---------------------------------------	------------

Drainage	\$0.00
----------	--------

Drainage to be determined

fence	\$0.00
-------	--------

fence to be determined

Subtotal	\$217,827.50
-----------------	--------------

Total	\$217,827.50
--------------	---------------------

Deposit Due	\$130,696.50
--------------------	---------------------

No changes, additions, repairs, or work performed outside of initial contract are to be done verbally, must be in writing and agreed upon by homeowner, HOA boardmember, or company's decision maker and Pool Supply Atlanta

When doing any resurfacing project delamination can inspect out once the pool has been drained and if delamination is present a change may be given. _____

If purchaser causes a work stoppage and the crew pulls off the job 15% of the deposit is nonrefundable

Payment Terms: 60% Deposit at the signing of the contract and 40% upon completion

By signing this document, the customer agrees to the services and conditions outlined in this document.

patti griffin