

ADDENDUM NUMBER ONE
REPAIRS AND IMPROVEMENTS
CAPULIN FIRE STATION

March 31, 2021

Page 1 of 1

The Plans and the Project Manual both dated March 10, 2021 are revised as described in this Addendum. When in conflict with other information issued prior to the date of this addendum then this addendum takes precedence. All cost and schedule implications of these revisions are to be incorporated into the Bid.

Project Manual

No changes or additions.

Plans

Sheet 1

Altered Site Plan

At the east edge of the existing concrete floor slab add the note:

“Grind edge of existing concrete floor slab outside of the existing garage doors where the two sectional doors were widened in the past. The surface of the concrete floor was constructed tapered from the outside edge of the floor slab up to the bottom of the old doors like is still commonly constructed today. When the doors were widened the taper at the edge of the floor slab was not widened leaving a step approximately 1-1/2 inch high at part of each sectional door. Remove the steel angle approximately 1-1/2 inch x 1-1/2 inch embedded in the concrete where the siding used to contact the edge of the floor slab. The step to be removed at each door measures approximately 1-1/2 inch high x four feet wide x 8 inches inward. Grind the existing concrete surface so that the full approach to the door is tapered for the full width of the door opening instead of currently only the width of the old doors. Patch the concrete surface after grinding if needed to provide a smooth driving surface and smooth appearance.”

END OF ADDENDUM NO. ONE