

Estimate

Cottage Landscaping &
Southwest Greens

P.O. Box 895
Oakley, CA 94561

Date

Estimate #

8/1/2025

2103

Name / Address

Denise Wysocki
4845 Royal Lily Avenue
Roseville, CA 95747



SOUTHWEST GREENS

Putting Greens • Synthetic Grass • Play Areas

Project

			Project
Description	Qty	Cost	Total
Remove 4 existing Bocce courts surface and existing side boards and haul debris to dump. Install 4 new Bocce courts with synthetic sand filled Bocce surface and new 1 x 6 composite wood for side boards. Each court is 91' x 13' = 1,183 sq. ft.		76,440.00	76,440.00
Bocce courts construction includes; Approximately 2" - 3" of compacted base materials, approximately 1,183 sq. ft. of 1 1/8" sand filled Bocce Pro material for each court. New 1 x 6 composite wood for side boards.			
Install approximately 1,183 sq. ft. of SP 20 X Brock 3/4" pad under each Bocce court for impact. Total for all four courts 4,732 sq. ft		23,384.00	23,384.00
		Total	\$99,824.00