

mcgillassociates.com

DATE

DESCRIPTION


N/A


20.03019

**JANUARY 2025** 

M. HANSON


M. HANSON







### INSTALLATION NOTES

- PRIOR TO INSTALLATION, CLEAR ALL OBSTRUCTIONS INCLUDING ROCKS, CLODS, AND OTHER DEBRIS GREATER THAN ONE INCH THAT MAY INTERFERE WITH PROPER FUNCTION OF THE WATTLE.
- 2. WATTLES SHOULD BE INSTALLED PARALLEL TO THE TOE OF A GRADED SLOPE, A MINIMUM OF 10 FEET BEYOND THE TOE OF THE SLOPE, SOCKS LOCATED BELOW FLAT AREAS SHOULD BE LOCATED AT THE EDGE OF THE LAND-DISTURBANCE. THE EDGE OF THE SOCKS SHOULD BE TURNED SLIGHTLY UP SLOPE TO PREVENT RUNOFF FROM GOING AROUND THE END OF THE SOCKS.
- 3. FILL SOCK NETTING UNIFORMLY WITH COMPOST TO THE DESIRED LENGTH SUCH THAT LOGS DO NOT
- 4. OAK OR OTHER DURABLE HARDWOOD STAKES 2"X 2"IN CROSS SECTION SHOULD BE DRIVEN VERTICALLY PLUMB, THROUGH THE CENTER OF THE COMPOST SOCK. STAKES SHOULD BE PLACED AT A MAXIMUM INTERVAL OF 4 FEET, OR A MAXIMUM INTERVAL OF FEET IF THE SOCK IS PLACED IN A 4 INCH TRENCH. THE STAKES SHOULD BE DRIVEN TO A MINIMUM DEPTH OF 12 INCHES, WITH A MINIMUM OF 3 INCHES PROTRUDING ABOVE THE COMPOST SOCK.
- 5. IN THE EVENT STAKING IS NOT POSSIBLE (I.E., WHEN SOCKS ARE USED ON PAVEMENT) HEAVY CONCRETE BLOCKS SHALL BE USED BEHIND THE SOCK TO HOLD IT IN PLACE DURING RUNOFF





- 1. WATTLES MUST BE SECURED AS SHOWN, OR PER MANUFACTURER'S RECOMMENDATIONS.
- 2. ALL MATERIALS INSTALLED WITHIN NCDOT RIGHT-OF-WAY MUST MEET NCDOT STANDARDS.



STAKES W/ WRE TIES

REMOVE SEDIMENT FROM BEHIND FILTER TUBE WHEN DEPTH HAS REACHED APPROXIMATELY 6"

WATTLE- INLET PROTECTION UNPAVED CONDITION


NOT TO SCALE


# TEMPORARY INLET PROTECTION - WATTLE NOT TO SCALE

PLAN SYMBOL

# MAINTENANCE NOTE

INSPECT SEDIMENT WATTLES WEEKLY AND AFTER EACH SIGNIFICANT RAINFALL EVENT () INCH OR GREATER). REMOVE ACCUMULATED SEDIMENT AND ANY DEBRIS. THE SEDIMENT WATTLE MUST BE REPLACED IF CLOGGED OR TORN. IF PONDING BECOMES EXCESSIVE, THE WATTLE NEEDS TO BE REINSTALLED IF UNDERMINED OR DISLODGED. THE SEDIMENT WATTLE SHALL BE INSPECTED UNTIL LAND DISTURBANCE IS COMPLETE AND THE AREA ABOVE THE MEASURE HAS BEEN PERMANENTLY






#### CONSTRUCTION NOTES

- 1. CLEAR THE AREAS UNDER THE EMBANKMENT AND STRIP OF ROOTS AND OTHER OBJECTIONABLE MATERIAL. DELAY CLEANING THE RESERVOIR AREA UNTIL THE DAM IS IN
- 2. COVER THE FOUNDATION AREA INCLUDING THE ABUTMENTS WITH EXTRA-STRENGTH FILTER FABRIC BEFORE BACKFILLING WITH ROCK. IF A CUTOFF TRENCH IS REQUIRED, EXCAVATE AT CENTER LINE OF DAM, EXTENDING ALL THE WAY UP TO THE EARTH ABUTMENTS. APPLY FILTER FABRIC UNDER THE ROCKFILL EMBANKMENT FROM THE UPSTREAM EDGE OF THE DAM TO THE DOWNSTREAM EDGE OF THE APRON. OVERLAP FILL MATERIAL A MINIMUM OF 1 FOOT AT ALL JOINTS, WITH THE UPSTREAM STRIP
- 3. CONSTRUCT THE EMBANKMENT WITH WELL-GRADED ROCK AND GRAVEL TO THE SIZE AND DIMENSIONS ON THE DRAWING. IT IS IMPORTANT THAT ROCK ABUTMENTS BE AL LEAST 2 FEET HIGHER THAN THE SPILLWAY CREST AND AT LEAST 1 FOOT HIGHER THAN THE DAM, ALL THE WAY TO THE DOWNSTREAM TOE, TO PREVENT SCOUR AND
- 4. SEDIMENT-LADEN WATER FROM THE CONSTRUCTION SITE SHOULD BE DIVERTED INTO THE BASIN RESERVOIR AT THE FURTHEST AREA FROM THE DAM.
- 5. CONSTRUCT THE ROCK CHECK DAM BEFORE THE BASIN AREA IS CLEARED TO MINIMIZE SEDIMENT YIELD FROM CONSTRUCTION OF THE BASIN. IMMEDIATELY STABILIZE ALL AREAS DISTURBED DURING THE CONSTRUCTION OF THE DAM EXCEPT THE SEDIMENT POOL.


# TEMPORARY ROCK CHECK DAM

NOT TO SCALE




#### MAINTENANCE NOTES

- 1. CHECK SEDIMENT BASINS AFTER EACH RAINFALL EVENT. REMOVE SEDIMENT AND RESTORE ORIGINAL VOLUME WHEN SEDIMENT ACCUMULATED TO ABOUT ONE-HALD THE DESIGN VOLUME. SEDIMENT SHOULD BE PLAVED ABOVE THE BASIN AND ADEQUATELY
- 2. CHECK THE STRUCTURE FOR EROSION, PIPING. AND ROCK DISPLACEMENT WEEKLY AND AFTER EACH SIGNIFICANT (1 INCH OR GREATER)
  RAINSTORM AND REPAIR IMMEDIATELY.
- 3. REMOVE THE STRUCTURE AND ANY UNSTABLE SEDIMENT IMMEDIATELY AFTER THE CONSTRUCTION SITE HAS BEEN PERMANENTLY STABILIZED. SMOOTH THE BASIN SITE TO BLEND WITH THE SURROUNDING AREA AND STABILIZE. ALL WATER AND SEDIMENT SHOULD BE REMOVED FROM THE BASIN PRIOR TO DAM REMOVAL. SEDIMENT SHOULD BE PLACED IN DESIGNATED DISPOSAL AREAS AND NOT ALLOWED TO FLOW INTO STREAMS OR DRAINAGE WAYS DURING STRUCTURE REMOVAL.



8' MAX. STANDARD STRENGTH FABRIC WITH WIRE FENCE (MIN. 14 GAUGE 6"X6" WIRE) MAX EXTRA STRENGTH FABRIC WITHOUT **MRE FENCE** 



#### CONSTRUCTION NOTES:

- . ENSURE THAT THE HEIGHT OF THE SEDIMENT FENCE DOES NOT EXCEED 24 INCHES ABOVE THE GROUND SURFACE.
- SUPPORT STANDARD STRENGTH FILTER FABRIC BY WIRE MESH FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS, EXTEND THE WIRE MESH SUPPORT THE TO BOTTOM OF THE TRENCH.
- 7. PLACE 12 INCHES OF THE FABRIC ALONG THE BOTTOM AND SIDE OF THE TRENCH.
- 9. DO NOT ATTACH FABRIC TO EXISTING TREES.

NOT TO SCALE

REFERENCE NODEQ LAND QUALITY SECTION DESIGN MANUAL: 6.62.

<2%
2 TO 5%
5 TO 10%
10 TO 20%
>20%

OUTLET W/O DITCH OUTLET W/DITCH 4 X D D CLASS 'B' RIP RAP CLASS I RIP RAP CLASS 'B' RIP RAP CLASS I RIP RAP

TONS TEXTULE S.Y. TONS TEXTULE TONS TEXTULE S.Y. TONS TEXTULE 9 | 4 | 10 | 2 | 15 7 15 3 11 | 7 | 4 | 21 | 11 | 22 | 5 | 16 | 11 | 7 29 | 15 | 30 | 7 | 22 | 16 | 10 | 23 39 | 20 | 39 | 10 | 28 | 22 | 13 | 30 49 | 26 | 50 | -- 36 21 47 \_\_\_\_\_ 73 | 40 | 75 | -87 | 48 | 89 | - | - | 54 | 32 | 67 72" - | - | 102 | 57 | 104 | - | - | 64 | 38 | 78 NOTE: FOR CALCULATION PURPOSES CLASS 'B' RIP RAP = 100 LBS./FT<sup>3</sup> CLASS I RIP RAP = 105 LBS./FT<sup>3</sup> 4 X D 2 X D — A-SLOPE 112:1 OR FLATTER SECTION A-A PIPE OUTLET WITH DITCH H= RIP RAP TO TOP OF PIPE (MAX. H = D + T)T= 15" CLASS I RIP RAP, UNLESS OTHERWISE SHOWN ON PLANS SECTION B-B T= 12" CLASS 'B' RIP RAP, UNLESS OTHERWISE SHOWN ON PLANS PIPE OUTLET WITHOUT DITCH 876.02

5400 Trinity Road Raleigh, NC 27607 NC Firm License # C-0459 mcgillassociates.com





							22	
					-			
		-	 					
	6					-		11411
NO.	DATE	BY	1	1	DESCR	RIPTION	•	-

DWI# SRP-SW-ARP-0007 AUTRYVILLE STORMWATER IMPROVEMENTS

SAMPSON COUNTY, NORTH CAROLINA

NOT T	O SCALE	EROSION CONTROL DETAILS 1 OF 2					
OFFICE MANAGER M. HANSON	DESIGNER K. BEESLEY						
PROJECT MANAGER M. HANSON	REVIEWER M. HANSON	JANUARY 2025	PROJECT# 20.03019	FUNDING# N/A			

SHEET

CONSTRUCT THE FILTER FABRIC FROM A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID JOINTS. WHEN JOINTS ARE NECESSARY, SECURELY FASTEN THE FILTER CLOTH ONLY AT A SUPPORT POST WITH 4 FEET MINIMUM OVERLAP TO THE NEXT POST.

4. WHEN A WIRE MESH SUPPORT IS USED, SPACE POSTS A MAXIMUM OF 8 FEET APART. SUPPORT POSTS SHOULD BE DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24 INCHES. EXTRA STRENGTH FILTER FABRIC WITH 6 FEET POST SPACING DOES NOT REQUIRE WIRE MESH SUPPORT.

EXCAYATE A TRENCH APPROXIMATELY 4 INCHES WIDE AND 8 INCHES DEEP ALONG THE PROPOSED LINE OF POSTS AND UPSLOPE FROM THE BARRIER.

8. BACKFILL THE TRENCH WITH SOIL PLACED OVER THE FILER FABRIC AND COMPACT.

SLOPE LENGTH(FT) MAXIMUM AREA(SQFT)

**BID SET** 

# WATER PERMEABLE BAG -MADE OF NONWOVEN GEOTEXTILE DISCHARGE HOSE-FROM SEDIMENT BASIN NO. 57 STONE PAD DISCHARGE HOSE-FROM SEDIMENT BASIN 1. PLACE SILT BAG WITHIN LIMITS OF EROSIONS CONTROL

FENCE WHEN REPLACING BAG OR DECOMMISSIONING DEWATERING DEVICE(S).

MAINTENANCE REQUIREMENTS:

INSPECT INLET PIPE AND BAG FOR DAMAGE AND BLOCKAGE.
 REPLACE BAG WHEN %FULL OF SEDIMENT.

DEWATERING SILT BAG DETAIL NOT TO SCALE

# EROSION CONTROL MAINTENANCE PLAN

- 1. ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF PRODUCING RAINFALL BUT IN NO CASE NOT LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED.
- 2. SEDIMENT SHALL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES APPROX. 0.5 FEET DEEP AT THE SILT FENCE. THE SILT FENCE SHALL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER.
- 3. ALL SEEDED AREA SHALL BE FERTILIZED, RESEED AS NECESSARY, AND MULCHED ACCORDING TO SPECIFICATIONS IN THE SEEDING SPECIFICATION TO MAINTAIN A VIGOROUS AND DENSE VEGETATIVE COVER.
- 4. MAINTAIN ALL MATTING THAT HAS BEEN PLACED ON SLOPES AND IN DITCHES. CHECK FOR GOOD GROUND CONTACT AND FOR THE OCCURRENCE OF ANY EROSION UNDER THE MATTING. MONITOR AND REPAIR OR REPLACE AS NECESSARY.
- 5. THE CONTRACTOR SHALL MAINTAIN SELF INSPECTION REPORTS AS REQUIRED BY NCDEQ AND THE NPDES CONSTRUCTION STORMWATER PERMIT, SELF INSPECTIONS ARE TO BE CONDUCTED AFTER EACH PHASE OF THE PROJECT FOR THE RECORD OF THE INSTALLATION AND MAINTENANCE OF THE EROSION CONTROL MEASURERS.


# EROSION CONTROL MEASURES SELF INSPECTION

- THE FINANCIALLY RESPONSIBLE PARTY, LANDOWNER, OR THEIR AGENT SHALL CONDUCT INSPECTIONS OF ALL EROSION CONTROL DEVICES AND PRACTICES IN ACCORDANCE WITH NCDENR DIVISION OF LAND RESOURCES REQUIREMENTS FOR SELF INSPECTION.
- 2. A SELF INSPECTION SHALL BE PERFORMED AFTER EACH PHASE OF THE APPROVED SEDIMENT AND EROSION CONTROL PLAN IS COMPLETE. THIS SHALL INCLUDE BUT SHALL NOT BE LIMITED TO THE FOLLOWING:
  - 2.1. INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROL

MEASURES.


- CLEARING AND GRUBBING OF EXISTING GROUND COVER. COMPLETION OF ANY PHASE OF GRADING OF SLOPES OR
- 2.4. INSTALLATION OF STORM DRAINAGE FACILITIES.
- COMPLETION OF CONSTRUCTION OR DEVELOPMENT 2.6. ESTABLISHMENT OF PERMANENT GROUND COVER SUFFICIENT
- RESTRAIN EROSION.
- PERSON PERFORMING INSPECTION MAY USE THE STANDARD FORM PROVIDED BY NCDENR DIVISION OF LAND RESOURCES OR MAY MARK UP A SINGLE COPY OF THE APPROVED SEDIMENT AND EROSION CONTROL PLAN. ANY DOCUMENTATION OF THE SELF INSPECTIONS SHALL BE MAINTAINED ON-SITE AND MADE AVAILABLE TO THE EROSION CONTROL INSPECTOR.
- THE SEDIMENTATION POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DISTURBING ACTIVITIES INSPECT A PROJECT AFTER EACH

PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED. RULES DETAILING THE DOCUMENTATION OF THESE INSPECTIONS TOOK EFFECT OCTOBER 1, 2010. AS OF AUGUST 1 2013 THE SELF-INSPECTION PROGRAM WAS COMBINED WITH THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. THE FOCUS OF THE SELF-INSPECTION REPORT IS THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL MEASURES ACCORDING TO THE APPROVED PLAN. THE INSPECTIONS MUST BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED IN ACCORDANCE WITH NCGS 113A-54.1 AND 15A NCAC 4B.0131. A COMBINED SELF-INSPECTION / SELF-MONITORING FORM IS AVAILABLE AT THE FOLLOWING WEB ADDRESS: http://portal.ncdenr.org/web/lr/erosion . IF YOU HAVE ANY QUESTIONS OR CANNOT ACCESS THE FORM, PLEASE CONTACT THE LAND QUALITY SECTION AT (910) 433-3300.



#### TEMPORARY BYPASS NOTES

- Install all erosion control measures as shown on Erosion
- Construct impervious dike (recommended sandbag or other easily removable material) on upstream side of existing channel and install temporary bypass pump to divert water around construction area. All material shall be removed following construction.
- Construct impervious dike (recommended sandbag or other easily removable material) on downstream side of existing channel to prevent backing up of stream water into the construction area.
- Dewater the construction area using another temporary pump and discharge water into a dewatering basin or sediment bag until sediment has settled and water can be discharged back into stream. Dewatering basin must be outside any restricted buffer areas, use wattles instead of earth berm if reasonable.
- Begin construction of cross-culvert. Contractor shall inspect system daily before beginning any construction. No construction shall continue if system is not fully
- 6. Any wash material removed from bypass area should be stored outside the flood zone or regulated buffers until
- Upon completion of culvert construction, remove bypass system within (2) two calendar days..
- Stabilize all areas disturbed during construction. Stream bed and banks must be returned to pre-construction
- Contractor shall receive prior approval from engineer if choosing to use another method in lieu of bypass




MAINTENANCE NOTE

INSPECT SEDIMENT WATTLES WEEKLY AND AFTER EACH SIGNIFICANT RAINFALL EVENT ( INCH OR GREATER). REMOVE ACCUMULATED SEDIMENT AND ANY DEBRIS. THE SEDIMENT WATTLE MUST BE REPLACED IF CLOGGED OR TORN. IF PONDING BECOMES EXCESSIVE, THE WATTLE NEEDS TO BE REINSTALLED IF UNDERMINED OR DISLODGED. THE SEDIMENT WATTLE SHALL BE INSPECTED UNTIL LAND DISTURBANCE IS COMPLETE AND THE AREA ABOVE THE MEASURE HAS BEEN PERMANENTLY

WATTLE INITIAL FLO	OW RATES				
SEDIMENT WATTLE	8 INCH	12 INCH	18 INCH	24 INCH	32 INCH
DESIGN DIAMETER	(200MM)	(300MM)	(450MM)	(600MM)	(800MM)
MAXIMUM SLOPE	6 FT	750 FT	1,000 FT	1,300 FT	1,650 FT
LENGTH (<2%)	(1.83M)	(2.29M)	(3.05M)	(3.96M)	(5.00M)
HYDRAULIC FLOW	7.5 GPM/FT	11.3 GPM/FT	15.0 GPM/FT	22.5 GPM/FT	30.0 GPM/F
THROUGH RATE	94 L/M/M	(141 L/M/M)	(188 L/M/M)	(281 L/M/M)	(374 L/M/M

SEDIMENT WATTLE



ENTRENCHED INSTALLATION \*THIS APPLICATION MAY NOT BE USED WITH SEDIMENT WATTLES SMALLER THAN

### INSTALLATION NOTES

- PRIOR TO INSTALLATION, CLEAR ALL OBSTRUCTIONS INCLUDING ROCKS, CLODS, AND OTHER DEBRIS GREATER THAN ONE INCH THAT MAY INTERFERE WITH PROPER FUNCTION OF THE
- 2. SEDIMENT WATTLES SHOULD BE INSTALLED PARALLEL TO THE TOE OF A GRADED SLOPE, A MINIMUM OF 10 FEET BEYOND THE TOW OF THE SLOPE. WATTLES LOCATED BELOW FLAT AREAS SHOULD BE LOCATED AT THE EDGE OF THE LAND-DISTURBANCE. THE ENDS OF THE WATTLES SHOULD BE TURNED SLIGHTLY UP SLOPE TO PREVENT RUNOFF FROM GOING
- 3. FILL WATTLE NETTING UNIFORMLY WITH COMPOST TO THE DESIRED LENGTH SUCH THAT THE LOGS DO NOT DEFORM.
- 4. OAK OR OTHER DURABLE HARDWOOD STAKES 2"X2" IN CROSS SECTION SHOULD BE DRIVEN VERTICALLY PLUMB, THROUGH THE CENTER OF THE SEDIMENT WATTLE. STAKES SHOULD BE PLACED AT A MAXIMUM INTERVAL OF 4 FEET, OR A MAXIMUM INTERVAL OF 8 FEET IF THE WATTLE IS PLACED IN A 4 INCH TRENCH. THE STAKES SHOULD BE DRIVEN TO A MINIMUM OF 12 INCHES, WITH A MINIMUM OF 3 INCHES PROTRUDING ABOVE THE SEDIMENT WATTLE.
- 5. IN THE EVENT STAKING IS NOT POSSIBLE (I.E., PAVEMENT) HEAVY CONCRETE BLOCKS SHALL BE USED BEHIND THE WATTLE TO HOLD IT IN PLACE DURING RUNOFF EVENTS. 6. SEDIMENT WATTLES ARE NOT TO BE USED IN PERENNIAL OR INTERMITTENT STREAMS.

REVIEWER

M. HANSON

PLAN SYMBOL **BID SET** 

N/A

NC Firm License # C-0459 mcgillassociates.com



TEMPORARY STREAM BYPASS

UPDATED FEBRUARY, 2022



BEFORE	$\vdash$			 			
<b>6</b> 11.)							
						3	<b>.</b>
GGING TI	NO.	DATE	BY	 	DESCRIPTION		5

DWI# SRP-SW-ARP-0007 AUTRYVILLE STORMWATER IMPROVEMENTS

THE STORWING TER IVII ROVEMENTO	
TOWN OF AUTRYVILLE	OFFICE MANAG
SAMPSON COUNTY, NORTH CAROLINA	PROJECT MANA

NOT TO SCALE EROSION CONTROL DETAILS 2 OF 2 DESIGNER K. BEESLEY

20.03019

**JANUARY 2025** 

SHEET