

Construction fabric should be placed under the riprap at the pipe outfall into the lake. There should be 4"-6" diameter riprap 12" side around each side of the outfall.

This work is best accomplished during the dry season as it allows the vendor to properly place the outfall pipe and rip rap.