

PROJECT:

Aluminum Roof Top Condenser Stand

THE METAL SHOP


2541 W. Dunnellon Road

Dunnellon, FL 34433

www.metalshop.org

Phone: 888-441-2492

Fax: 352-522-0007





NOTES

1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE, 7TH EDITION, BUILDING VOLUME AND ASCE 7-16 MINIMUM DESIGN LOADS ON BUILDINGS AND OTHER STRUCTURES.
2. ANY CHANGE FROM THE DRAWINGS AND/OR FIELD CHANGE CONDITIONS MUST IMMEDIATELY BE BROUGHT TO THE ATTENTION OF THE STRUCTURAL ENGINEER SO THAT NECESSARY CHANGED CAN BE MADE AND THE INTENDED DESIGN IS CARRIED OUT TO ITS FULLEST EXTENT.
3. IT IS THE RESPONSIBILITY OF THE INSTALLING CONTRACTOR TO PROVIDE ADEQUATE ANCHORAGE AND A CORROSION RESISTANT SEPARATION BARRIER/COATING AT THE BOTTOM OF ALL BASE PLATES WHEN BEARING DIRECTLY ON CONCRETE AND STEEL STRUCTURES. THE SEPARATION BARRIER IS INTENDED ONLY FOR THE PREVENTION OF CORROSION.
4. MINIMUM DESIGN LOADS: DEAD LOADS AND LIVE LOADS IN ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODES, CHAPTER 16. AIR CONDENSER AND FRAME WITHSTANDS WIND SPEEDS UP TO 160 MPH PER 2020 FBC AND 7-16 STANDARDS.
5. CALCULATIONS ARE BASED ON AIR CONDENSER SURFACE AREA. THIS IS DETERMINED BY MULTIPLYING THE UNIT WIDTH BY THE UNIT HEIGHT, WITH THE RESULT BEING THE SURFACE SQUARE FOOTAGE. MAXIMUM SIZED ALLOWED FOR THE CONDENSER STAND ARE DENOTED IN THE TABLE ON SHEET RT-2.
6. 6061-T6/6005-T5 ALUMINUM ALLOY CONSTRUCTION FOR EXTERIOR EXPOSURE APPLICATIONS.
7. ROOF STAND SHALL HAVE ALL WELDED JOINTS AND SEAMS UNLESS OTHERWISE STATED.
8. WELD FILLER SHALL BE ALUMINUM ALLOY 4043 WITH TENSILE STRENGTH OF 15 KSI.
9. ALL ANCHOR/CONNECTION BOLTS SHALL BE IN ACCORDANCE WITH ASTM A-307 OR A-325F.
10. EXPANSION BOLTS AND LAG SCREWS SHALL HAVE A MINIMUM SPACING OF 25" AND MINIMUM EDGE DISTANCE OF 3" FOR EXPANSION BOLTS AND 1" FOR LAG SCREWS.
11. VIBRATION ISOLATOR PADS SHALL BE PROVIDED BY THE A/C CONTRACTOR BETWEEN THE BOTTOM OF THE CONDENSER AND THE TOP RAIL SO AS NOT TO CAUSE VIBRATION TO EXISTING SUB-STRUCTURE. SEE SHEET RT-2 FOR DETAILS.
12. BASE PLATE ANCHORING IS BASED OF A MAXIMUM ULTIMATE WIND SPEED OF 165 MPH FOR RISK CATEGORY II AND III BUILDINGS IN EXPSURE CATEGORY B AND C ONLY! CONTACT ENGINEER FOR SITE SPECIFIC ENGINEERING FOR ANY OF THE FOLLOWING CONDITIONS: ROOF MOUNTING ABOVE 60 FEET IN HEIGHT, OR EXPOSURE D LOCATIONS, RISK CATEGORY IV BUILDINGS, OR FOR WIND SPEED LOCATIONS ABOVE 165 MPH.
13. ROOF TOP STAND ARE DESIGN FOR A MAXIMUM UNIT WEIGHT OF 350 LBS. AND AN ASSUMED MINIMUM UNIT WEIGHT OF 120 LBS. SEE ENGINEER FOR SITE SPECIFIC ENGINEERING AND ROOF ANCHORING FOR 1-TON AND ALL CONDENSER UNITS UNDER 120 LBS.

This plan has been digitally signed and sealed by Joseph D. Hiller, P.E., using a Digital signature. Printed copies of this document are not considered signed and sealed and the digital signature must be verified on any electronic copies.


REVISIONS		
NO.	DESCRIPTION	DATE

PROFESSIONAL SEAL		
		
Digitally signed by Joseph D. Hiller P.E.#74583 Date: 2021.01.12 17:31:44 -05'00'		
JOSEPH D. HILLER, P.E. Florida P.E. License #74583		

	Hiller Engineering Services	
	FL COA 30596	
P.O. Box 290855	Port Orange, FL	32129
O: 386-248-1700	E: Hillerengineering@gmail.com	

PROJECT	AC Roof Top Stands	
	for	
	THE METAL SHOP	
2541 W. Dunnellon Rd.		
Dunnellon, FL 34433		
DRAWN BY:	A. NOTO	
DATE:	1/8/2021	
SCALE:	N/A	
S-1		
01 OF 04		

1 Unit System



PROVIDE ONE OF THE FOLLOWING ATTACHMENT METHODS

INSTALLATION INSTRUCTIONS:

USE 3/8" x 1-1/4" STAINLESS OR COATED BOLT, NUT & 1" WASHER AT 4 LOCATIONS THROUGH UNITS BOTTOM PAN AND TOP RAIL OF UNIT STAND.

USE 4 'METAL SHOP' ANCHOR CLIPS #771, 773, 883 AT 4 CORNERS OF UNIT AND TOP RAIL OF UNIT STAND.

WRAP UNIT AND TOP RAIL WITH 22 GA. HURRICANE COIL STRAP, GALVANIZED AT 2 LOCATIONS AND BOLT STRAP TO TOP RAIL OF STAND USING 1/4" GALVANIZED OR STAINLESS STEEL BOLTS, NUTS, & WASHERS

TABLE 1510.10
CLEARANCE BELOW RAISED ROOF
MOUNTED MECHANICAL UNITS

WIDTH OF MECHANICAL UNIT	MINIMUM CLEARANCE ABOVE SURFACES
W < 24"	14"
24" < W < 36"	18"
36" < W < 48"	24"
48" < W < 60"	30"
W > 60"	48"


DESIGN WIND PRESSURE CALCULATED PER CHAPTER 30: COMPONENTS & CLADDING OF ASCE 7-16 FOR 145 MPH, CAT. II, EXP. D, AT AN ELEVATION OF 60 FT.

A/C STAND REACTIONS TABLE

ROOF MATERIAL	ALLOWABLE BUILDING HEIGHT AT 160 MPH	MAXIMUM ALLOWABLE WEIGHT PER UNIT	UPLIFT	LATERAL	COMP.	BENDING MOMENT
CONC. DECK/STEEL JOIST	120'	350 LBS	294#	331#	605#	262 FT-LB
WOOD DECK	75'	350 LBS	294#	331#	605#	295 FT-LB

MAXIMUM DESIGN WIND PRESSURE

A/C STAND ATTACHED TO : CONCRETE OR, STEEL HOST STRUCTURE	MAX WIND PRESSURE 82.3 PSF
WOOD HOST STRUCTURE	MAX WIND PRESSURE 79.0 PSF



This plan has been digitally signed and sealed by Joseph D. Hiller, P.E., using a Digital signature. Printed copies of this document are not considered signed and sealed and the digital signature must be verified on any electronic copies.

THIS DRAWING AND ITS REPRODUCTIONS ARE THE PROPERTY OF HILLER ENGINEERING AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER.

REVISIONS

NO.	DESCRIPTION	DATE	INITIALS

PROFESSIONAL SEAL

JOSEPH D. HILLER, P.E.
No. 74583
STATE OF FLORIDA
PROFESSIONAL ENGINEER

Digitally signed by
Joseph D. Hiller
P.E.#74583
Date: 2021.01.12
17:32:04 -05'00'

JOSEPH D. HILLER, P.E.
Florida P.E. License #74583

Hiller Engineering Services

FL COA 30596

P.O. Box 290855
Port Orange, FL 32129
O: 386-248-1700
E: Hillerengineering@gmail.com


PROJECT

AC Roof Top Stands
for
THE METAL SHOP
2541 W. Dunnellon Rd.
Dunnellon, FL 34433

DRAWN BY: A. NOTO
DATE: 1/8/2021
SCALE: N/A


S-2
02 OF 04

1-UNIT SYSTEM




LEGS 6" FROM END
INSIDE LEGS MAX. 24" APART

2-UNIT SYSTEM




LEGS 12" FROM END
INSIDE LEGS MAX. 48" APART

3-UNIT SYSTEM




LEGS 12" FROM END
INSIDE LEGS MAX. 42" APART

4-UNIT SYSTEM




LEGS 12" FROM END
INSIDE LEGS MAX. 40" APART

5-UNIT SYSTEM




LEGS 12" FROM END
INSIDE LEGS MAX. 38" APART

6-UNIT SYSTEM



LEGS 12" FROM END
INSIDE LEGS MAX. 38" APART

AC UNIT BY OTHERS



TYPICAL AC MOUNTING DETAIL

NOT TO SCALE


3-UNIT SYSTEM SHOWN

BEAM MAY EXTEND 12" MAX. FROM END LEG
INSIDE LEGS MAX. 42" APART

NOTE:

MAINTAIN EQUAL LEG SPACING PER UNIT SYSTEM CONFIGURATION

UNIT/SIZE TABLE						
AC STAND LENGTH	3 FT	6 FT	9 FT	12 FT	15 FT	18 FT
ROOF TYPE	ALL	ALL	ALL	ALL	ALL	ALL
MAX # UNITS	1	2	3	4	5	6
MAX SURFACE AREA PER UNIT	9 SF	9 SF	9 SF	9 SF	9 SF	9 SF
TOTAL SURFACE AREA	9 SF	18 SF	27 SF	36 SF	45 SF	54 SF



Digitally signed
by Joseph D.
Hiller P.E.#74583
Date: 2021.07.22
16:07:33 -04'00'

This plan has been digitally signed and sealed by Joseph D. Hiller, P.E., using a Digital signature. Printed copies of this document are not considered signed and sealed and the digital signature must be verified on any electronic copies.

THIS DRAWING AND ITS REPRODUCTIONS ARE THE PROPERTY OF HILLER ENGINEERING AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER.

REVISIONS

NO.	DESCRIPTION	DATE	INITIALS

PROFESSIONAL SEAL

JOSEPH D. HILLER, P.E.
Florida P.E. License #74583
THIS DRAWING IS NOT VALID UNLESS SIGNED, SEALED AND DATED BY A REGISTERED PROFESSIONAL.

Hiller Engineering Services

FL COA 30596
P.O. Box 290855
Port Orange, FL 32129
O: 386-248-1700
E: Hillerengineering@gmail.com

PROJECT


AC Roof Top Stands
for
THE METAL SHOP
2541 W. Dunnellon Rd.
Dunnellon, FL 34433

DRAWN BY:	A. NOTO
DATE:	1/8/2021
SCALE:	N/A

S-3
03 OF 04


TYPICAL BASE PLATE CONNECTIONS

TO SLAB ON GRADE




FASTENERS:
(4) 1/4" DIA. HEX-HEAD
TAP-CONS WITH 1-1/2" EMBED

TO STD. WEIGHT CONCRETE




FASTENERS:
(4) 1/4" HILTI "KWIK BOLT II" W/ 2" EMBED OR (4) 1/4"
DIA. RAWL MUSHROOM HEAD SPIKES W/ 1-1/4" EMBED.
MIN. ANCHOR SPACING SHALL BE 2.5"
MIN. EDGE DISTANCE SHALL BE 3.0"

TO WOOD BEAM/TRUSS



FASTENERS:
(4) 3/8" LAG SCREWS W/ 2-1/2" MIN. EMBED INTO
TRUSS/BEAM (TYP. EACH BASE PLATE)
MIN. ANCHOR SPACING: 2.5"
MIN. EDGE DISTANCE: 1.0"
PRE-DRILL FOR LAG SCREWS

TYPICAL CONNECTION TO STEEL JOIST



FASTENERS:
(4) HILTI MODEL #EDS22P10
x 3/4" LG POWER DRIVEN
FASTENERS (TYP. AT EA
BASE PLATE)

OPTIONAL:
(4) #14 HEX HEAD SELF
TAPPING TEK SCREWS

ROOF TOP UNIT FRAMING


COORDINATE WITH STRUCTURAL ENGINEER PRIOR TO STARTING
CONSTRUCTION FOR LARGER ROOF TOP UNITS. STRUCTURAL
ENGINEER TO VERIFY THAT EXISTING ROOF STRUCTURE IS CAPABLE
OF SUPPORTING THE EXCESSIVE POINT LOAD.

STEEL CHANNEL OR STEEL TUBE MAY BE SUBSTITUTED FOR STEEL
ANGLE SIZES SHOWN ABOVE.

VERIFY ALL DIM'S AND DETAILS W/MECH
CONTRACTOR BEFORE FABRICATION

ROOF TOP UNIT FRAME SCHEDULE

UNIT WEIGHT	ANGLE SIZE:
0 - 675 LBS	L3x3x 3/16
676 - 1500 LBS.	L4x4x1/4
1501 - 3000 LBS.	L6x4x3/8 (L.L.H.)
3001 - 6000 LBS.	L6x6x7/16



STEEL JOIST REINFORCING DETAIL

NOT TO SCALE

This plan has been digitally signed and sealed by Joseph D. Hiller, P.E., using a
Digital signature. Printed copies of this document are not considered signed and
sealed and the digital signature must be verified on any electronic copies.

THIS DRAWING AND ITS REPRODUCTIONS ARE THE PROPERTY OF HILLER ENGINEERING AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER.

REVISIONS

NO.	DESCRIPTION	DATE	INITIALS

PROFESSIONAL SEAL

JOSEPH D. HILLER
P.E. License No. 74583
STATE OF FLORIDA
PROFESSIONAL ENGINEER

Digitally signed by
Joseph D. Hiller
P.E.#74583
Date: 2021.01.12
17:32:40 -05'00'

JOSEPH D. HILLER, P.E.
Florida P.E. License #74583
THIS DRAWING IS NOT VALID UNLESS SIGNED, SEALED
AND DATED BY A REGISTERED PROFESSIONAL

Hiller Engineering Services

FL COA 30596

P.O. Box 290855
Port Orange, FL
32129

O: 386-248-1700
E: Hillerengineering@gmail.com

PROJECT

AC Roof Top Stands
for
THE METAL SHOP
2541 W. Dunnellon Rd.
Dunnellon, FL 34433

DRAWN BY: A. NOTO

DATE: 1/8/2021

SCALE: N/A

S-4
04 OF 04