

M. A. Day Engineering, PC

3 Van Wyck Lane
Suite 2
Wappingers Falls, New York 12590
Phone: 845-223-3202
Fax: 845-223-3206

May 14, 2010

Mr. Alec Ciesluk
New York State DEC
21 South Putt Corners Road
New Paltz, New York 12561

Re: Summit Woods
Notice of Incomplete Application
WSA 11,200

Mr. Ciesluk,

In response to your Notice of Incomplete Application dated January 5, 2009, I offer the following responses:

1. Public Water Supply Demand:

A fourth production well was installed in March of 2009. This well was analyzed by Ground Water Investigations, Inc. and a subsequent report was prepared by them dated April 2010. The new well can produce 63 gallons per minute. Therefore, the MDD for the project can be met with the two lower producing wells out of service. It is my opinion that the additional production well satisfies the requirements of the Ten States Standards.

2. The GWI report found in the appendices of the revised Water Supply Report includes a "Time/Drawdown" semi-logarithmic graph extended to 180 days.
3. As you know, the Montage project to the west of the Summit Woods project had installed two wells and performed well tests on those wells. The results of those tests indicate a good result. That project was originally slated for 275 senior homes but has been downsized to 126 market rate homes. LBG did the hydrogeological analysis for the Montage project and did not impact the wells on the Summit Woods project.
4. Attached please find the "Permission to Inspect the Property" authorized by Mr. Gueron.
5. The latitude and longitude is 41°32'58"N and 73°44'50"W, respectively for the proposed location of the discharge for the proposed WWTP.

Please feel free to contact me if you have any remaining questions regarding this submission or this application.

Very truly yours,

Mark A. Day, PE