

## Wilson's Petroleum Toolbox Talk

## **Traffic Control**

This section includes identifying safety hazards and then furnishing all necessary labor, materials, tools, and equipment including, but not limited, to signs, barricades, traffic drums, cones, flashers, construction fencing, flag persons, variable message boards, uniformed police officers, warning devices, temporary pavement markings, temporary sidewalk, delineators, etc., to maintain vehicular and pedestrian traffic through and adjacent to the project area.

These measures and actions must be taken to safely maintain the accessibility of public and construction traffic by preventing potential construction hazards.

All materials, work, and incidental costs related to maintenance of traffic will be paid for at the contract lump sum price.


## Requirements:

Training shall be provided to workers involved in the planning, setup, operation, maintenance, or removal of traffic control to the level of their responsibility.

The Traffic Control Plan must conform to the following standards:

- Sequence the work in a manner that will minimize disruption of vehicular and pedestrian access through and around the construction area.
- Traffic planning and control for the maintenance and protection of pedestrian and vehicular traffic affected by this Company's work includes, but is not limited to:
  - o Construction and maintenance of any necessary detour equipment and facilities.
  - Providing necessary facilities for access to residences and businesses.
  - Furnishing, installing, and maintenance of traffic control and safety devices (e.g., signage, barricades, barriers, message boards, etc.), and flag persons as appropriate during construction.
  - Control of water runoff, dust, and any other special requirements for safe and expeditious movement of traffic.
- Planning, maintenance, and control of traffic must be provided at the Company's expense. The Company will bear all expense of maintaining the vehicle and pedestrian traffic throughout the work area.
- The Company will remove temporary equipment and facilities when no longer required, restore grounds to original, or to specified conditions.





Toolbox Talk – Traffic Control				
Date:			Job No.:	
Job Name:			Supervisor:	
Employee Safety Recommendations				
Documents Reviewed				
Attendees				
(print name)				
Supervisor Signature:				