



## RISKATA WORKSITE

DR DAN SULLIVAN


### **DAN SULLIVAN**

- 30 years involved with TTM
- Austroads Project Manager for AGTTM
- Queensland
  - TMR specialist panel
  - TMD course developer
  - TMD Open 001
  - Registered Professional Engineer Queensland (RPEQ)






## POLL 1 WHICH FACTOR IS INVOLVED IN THE HIGHEST % OF SERIOUS CRASHES






## POLL 1 WHICH FACTOR IS INVOLVED IN THE HIGHEST % OF SERIOUS CRASHES



## WHICH DRIVERS ARE DANGEROUS?

Transport



### WHICH DRIVERS ARE DANGEROUS TO YOU

## A traffic controller, 50, has been killed after being hit by a car at Redbank Plains

A traffic controller has been killed in an incident west of Brisbane. Investigations into the incident are underway.

#### Paige Carfrae

less than 2 min read September 8, 2015 - 12:05PM Quest Newspapers

0 comments





Generic photo of Queensland Ambulance.

## WHAT CAN YOU DO FOR YOUR PERSONAL SAFETY






## WHAT CAN YOU DO FOR YOUR PERSONAL SAFETY





## WHAT CAN YOU DO FOR YOUR PERSONAL SAFETY





## POLL 2 WHAT IS THE GREATEST RISK AT A WORKSITE

- Bad communication
- Sub-contractors not managed by Tier1
- Fatigue
- Plant / machinery on site
- Incompetent staff member
- Workers walking out into the live lane
- TMAs not fit for purpose
- Time pressure from clients
- Workers making bad decisions lazy / unsafe
- Clients working in the lateral

- People
- People running the red light
- Vehicle overtaking vehicles in queue (2)
- Poor drivers
- Speed
- Distracted drivers
- Traffic / Traffic through site
- Public / public road users (3)



## **RISK MANAGEMENT – STAGES**










Company Systems Planning TMP Design TGS Field TMI



## **RISK MANAGEMENT – COMPANY SYSTEMS**





### Typical elements may include

- Training / ongoing competency
- Fitness to work
- Work safety requirements e.g. fatigue
- Vehicle / equipment requirements / checks

### Outputs for TTM risk management

- Planning / design procedures
- Risk management system
- Risk register proforma Planning / Design / Field



### **RISK MANAGEMENT – PLANNING**







### AGTTM Part 2 outlines TMP process

- Every TTM task requires planning
- Major works ⇒ more complex TMP

### Risk management in the TMP

- 1st identification of foreseeable risks for works
  - Typical risks (list / template)
  - Specific risks particular works / site
  - Risks addressed in planning the works
- Risk register
  - Risks addressed in planning
  - Residual risks to be addressed in design / field

### **RISK MANAGEMENT – DESIGN**



Design TGS



### AGTTM Parts 3, 4 & 5 to design TGS

- Every TTM task requires design
- Major works ⇒ Specific TGS

### Risk management in the TGS

- Detailed evaluation of foreseeable risks
  - Typical risks (list / template)
  - Specific risks particular works / site
  - Risks (residual) identified in planning
  - Risks addressed in designing the works
- Risk register
  - Risks addressed in design
  - Residual risks to be addressed in field

### **RISK MANAGEMENT – FIELD**








### AGTTM Parts 6 & 7 for field staff and TCs

- Risk assessment required for
  - Every site
  - Every variation in TTM
  - Every key change in works

### Risk management in the Field

- Ongoing / Final evaluation of risks on site
  - Risks (residual) from planning / design
  - Specific risks particular works / site (list / template)
- Risk register
  - Risks addressed during implementation
  - Residual risks to monitor

# **AS / ISO 31000:2018 KEY TERMS**



### **COMMONLY SEEN RISK REGISTER ISSUES**

### Risks

- Irrelevant items
- Items addressed in company systems
- Vague descriptions don't describe a risk
- Lack of items related to a site

### Risk Rating

- No support for either the initial or revised risk ratings
- Every risk reduced to low with standard measures

### Control measures

- Not relevant to the risk identified
- List with no clear link to risk or "action by"
- Company system or compliance issues that address everything
- Measures that are impractical

### Action by

- List of everyone on the job with no defined actions
- Roles that are not correctly defined





### **EXAMPLE – LESS THAN ADEQUATE PRACTICE**

- Traffic Controllers
  - Risk TC being struck by vehicle
  - Risk rating High
  - Control All TC to have appropriate qualifications
  - Revised rating Low
  - Action by NTO, Principal Contractor, Supervisor, TMI, TCs

- What is wrong with this
  - Does not consider initial source of the risk.
  - Assumes qualification (training and admin) is sole fix
  - Company systems should address qualification requirements
  - Planner / Designer focus on the issues related to the planning and design of the works that will create or impact on risks
  - What actions are actually required?



### **EXAMPLE - BETTER PRACTICE**

- Traffic Controllers
  - Risk source
    - Vehicles approaching at high speed
    - Inadequate sight distance
  - Event vehicle is unable to stop
    - Drives through TC station
    - Hits queued vehicles
  - Consequence
    - TC Injured / killed
    - Crash / Injury to public
  - Likelihood depends on site specifics

- Risk rating should be based on relative risk compared to normal TC operations
- Potential control measures
- Selected control measure (examples)
  - Spotter in advance of TC station to advise TC of approaching higher risk vehicles
  - TC station to be located immediately at end of safety barrier segment to allow escape route behind barrier
- Action by
  - TMD TC & spotter location selected
  - Field TC & spotter located correctly
  - TMI ensure TC compliance with quals



### **EXAMPLE – LESS THAN ADEQUATE PRACTICE**

- Children
  - Risk Children
  - Risk rating Medium
  - Control Works to be scheduled at night
  - Revised rating Low
  - Action by Principal Contractor, Supervisor, TMI, TCs

- What is wrong with this
  - Appears to be more just ticking a box
  - No identification of what the risk actually is
  - Single measure does not actually seem related to the risk
  - What actions are actually required?



### **EXAMPLE - BETTER PRACTICE**

- Children
  - Risk source
    - Nearby school / beach / playground many children passing the site
  - Event
    - Child enters worksite struck by plant
    - Child walks on road doesn't use crossing
       & struck by road traffic
  - Consequence
    - Child injured / killed
  - Likelihood assess based on age of children, frequency, proximity to child activities etc

- Risk rating compared to normal site
- Potential control measures
- Selected control measure (examples)
  - Measures to prevent entry to site
  - Regularly check TTM devices
  - Children directed to crossing
- Action by
  - TMD design in TGS
    - Fencing / barriers around site
    - Signage for peds / crossing
  - TMI
    - Regularly inspect TTM
    - Spotter to assist direct children



Risk	d	nitial Ri	sk	Г	
Source	Event	L	C	Rating	C
Reduced sight distance on approach to worksite	Vehicle unable to stop runs into queued vehicles	L	Mod	High	
	Vehicle unable to stop runs into TC station	Р	Maj	High	38
	Vehicle hits TMI during installation of TTM	р	Maj	High	
	Vehicle enters site at speed higher than posted for worker / traffic safety	AC	Mod	High	00
Traffic travelling within the work area in lane past the worksite	Vehicle enters work area and hits TTM or road workers	P	Cat	High	
	Vehicle enters work area and hits work plant	U	Min	Low	18
	Vehicle enters work area and crashes in excavation (<500m)	U	Min	Low	
	Vehicle enters work area and hits TTM devices	L	Insig	Low	8



### Options identified

Risk		Initial Risk			Proposed Control M	Re	sk	Selected		
Source	Event	L	C	Rating	Options	Considerations	L	С	Rating	
					A) Eliminate - close road to traffic					
				B) Eliminate - remove TC station to remove queue issue						
	Vehicle unable to stop runs	ehicle unable to stop runs to queued vehicles	Mod	d High	C) Engineer - relocate queue to alternative location			9		
Reduced sight distance on approach to worksite	into queuea venicies				D) Engineer - introduce additional treatments to reduce vehicle speeds on approach					
					E) Admin - TCs to operate shuttle flow with priority to vehicles on southern approach to eliminate / reduce queues			.0		s 8



Suitable option selected – Risk closed out

Risk		Initial Risk			Proposed Control Measures		Revised Risk			Selected
Source Event		L C Rating O		Rating	Options	Considerations	L	С	Rating	
					A) Eliminate - close road to traffic	Suitable Detour avaiable	R	Mod	Low	Yes
					B) Eliminate - remove TC station to remove queue issue	Would substantially impact works efficiency and increase works duration from 1 to 3 days	R	Mod	Low	No
	Vehicle unable to stop runs into queued vehicles	L	Mod	High	C) Engineer - relocate queue to alternative location	Assess at Design phase	P	Mod	Med	No
Reduced sight					D) Engineer - introduce additional treatments to reduce vehicle speeds on approach	Assess at Design phase	P	Mod	Med	No
distance on approach to worksite			E) Admin - TCs to operate shuttle flow with priority to vehicles on southern approach to eliminate / reduce queues	Assess at Design / Implementation phases	P	Mod	Med	No		



• Suitable option needs further evaluation at design phase – Residual risk

Risk		Initial Risk		sk	Proposed Control Measures			Revised Risk		
Source Event		L C Rating (		Rating	Options	Considerations		С	Rating	
	0.00.0				A) Eliminate - close road to traffic	Not feasible - no alternative route	R	Mod	Low	No
					B) Eliminate - remove TC station to remove queue issue	Would substantially impact works efficiency and increase works duration from 1 to 3 days	R	Mod	Low	No
	Vehicle unable to stop runs into queued vehicles	L	Mod	High	C) Engineer - relocate queue to alternative location	Assess at Design phase	Р	Mod	Med	Possible
Reduced sight					D) Engineer - introduce additional treatments to reduce vehicle speeds on approach	Assess at Design phase	Р	Mod	Med	Possible
distance on approach to worksite					E) Admin - TCs to operate shuttle flow with priority to vehicles on southern approach to eliminate / reduce queues	Assess at Design / Implementation phases	Р	Mod	Med	Possible



• Suitable option needs further evaluation at design phase – Residual risk

Proposed Control Me	Re	evised R	isk	Selected	Actions				
Options	Considerations		С	Rating		Who	What		
A) Eliminate - close road to traffic	Not feasible - no alternative route	R	Mod	Low	No				
B) Eliminate - remove TC station to remove queue issue	Would substantially impact works efficiency and increase works duration from 1 to 3 days	R	Mod	Low	No				
C) Engineer - relocate queue to alternative location	Assess at Design phase	Р	Mod	Med	Possible		TCC designants foutbourses identifications		
D) Engineer - introduce additional treatments to reduce vehicle speeds on approach	Assess at Design phase	Р	Mod	Med	Possible	TMD	TGS designer to further consider these potential control measures, and any		
E) Admin - TCs to operate shuttle flow with priority to vehicles on southern approach to eliminate / reduce queues	Assess at Design / Implementation phases	Р	Mod	Med	Possible		other suitable measures, to target revised risk = LOW		



# RECOMMENDED RISK PRACTICE FOR TTM PLANNING OUTPUTS

 Company level risk assessment

#### **Risk Assessment document**

### Register of closed risk items

- Risk analysis is completed
- Always include in risk document
- Shows the risks identified, treatment applied and accept of resultant risk rating

### Residual risk register

- Risk analysis requires further consideration
- Any risks that remain to be addressed further in the design phase or in the field
- Further risk consideration is required

#### **Action List**

- Risk analysis is completed
- Actions have been identified to be addressed
- Clearly identify who is responsible



# RECOMMENDED RISK PRACTICE FOR TTM PLANNING OUTPUTS

Company level risk assessment

2. Planning stage risk assessment

#### **Risk Assessment document**

### Register of closed risk items

- Risk analysis is completed
- Always include in risk document
- Shows the risks identified, treatment applied and accept of resultant risk rating

### Residual risk register

- Risk analysis requires further consideration
- Any risks that remain to be addressed further in the design phase or in the field
- Further risk consideration is required

#### **Action List**

- Risk analysis is completed
- Actions identified to be addressed
- Clearly identify who is responsible



# RECOMMENDED RISK PRACTICE FOR TTM PLANNING OUTPUTS

- Company level risk assessment
  - 2. Planning stage risk assessment

#### Risk Assessment

- Assess residual risks
- Complete all actions
- Identify additional planning level risks

### Outputs

- Further closed risks
- Update residual risks
- Update action list



### Register of closed risk items

- Risk analysis is completed
- Always include in risk document
- Shows the risks identified, treatment applied and accept of resultant risk rating

### Residual risk register


- Risk analysis requires further consideration
- Any risks that remain to be addressed further in the design phase or in the field
- Further risk consideration is required

#### **Action List**

- Risk analysis is completed
- Actions identified to be addressed
- Clearly identify who is responsible



Transport






















### WHAT CAN YOU DO TO ADDRESS RISK



- Assume that someone may break your control
- Plan for success / Prepare for breach
- Who do you trust?
- I can only design so much
- Who experiences the risk



### TAKE AWAYS

- The final control is for staff in the field
- How do we inform them of what we want them to look out for
- How do field staff behave in the field
- Speak up if you see someone acting unsafely
- Look out for yourself look out for your mates – work as a team







## THANKYOU!



DAN.SULLIVAN@SOLUTIONSINTRANSPORT.COM.AU



HTTP://WWW. SOLUTIONSINTRANSPORT.COM.AU