

TOWN OF SAXEVILLE

Waushara County WI

PO BOX 30 Saxeville WI 54976

Class 1 Notice for Contracts

- Description of Project: 26th Rd
Full Overlay using hot mix
Estimated Cost: \$20,000
Contractor completing Project: Waushara County Highway Dept.
- Description of Project: 28th Rd North
Single Chip Seal over hard surface using hot oil and limestone chip
Estimated Cost: \$13,047
Contractor completing Project: Scott Construction INC
- Description of Project: 28th Rd South
Single Chip Seal over hard surface using hot oil and limestone chip
Estimated Cost: \$13,047
Contractor completing Project: Scott Construction INC
- Description of Project: 4th Street
Double Chip seal over gravel using hot oil and limestone chip
Estimated Cost: \$10,300
Contractor completing Project: Scott Construction INC
- Description of Project: 1st Street
Double Chip seal over gravel using hot oil and limestone chip
Estimated Cost: \$10,850
Contractor completing Project: Scott Construction INC
- Description of Project: Lake Street
Double Chip seal over gravel using hot oil and limestone chip
Estimated Cost: \$5,350
Contractor completing Project: Scott Construction INC.
- Description of Project: Ditching work on Portage Street
Digging in ditch line on North side of Portage street between W4818 & W4840 to bridge over the Pine River. Cleaning up bridge deck from sand and spoil materials. Digging in ditch on South side of Portage street from W4855 to Bridge. Installing required silt fence on each side of flowage to water way.

Notice Prepared & Posted by Angie Lund Clerk Treasurer, with approval of Bart Peterson, Chairman on May 19, 2026 at the following locations: Saxeville Town Hall, and the towns website: <https://townofsaxeville.com>

All ditch lines re worked will be seeded with grass seed and covered with straw matting. All spoil materials excavated will be hauled off site for disposal.

Estimated Cost: \$5,275

Contractor completing Project: S&G Excavating LLC

- **Description of Project: Ditching work on Pine Hill Rd**
Installing new ditch line on west side of Pine Hill road from new driveway access across the road from N7224. Excavating new ditch line up west side of roadway towards the south to top of hill. Ditch embankment will need to be excavated back to be able to install new ditch. Areas excavated will then be seeded and covered in straw matting. Silt socks will be put in place to help slow water flow down new ditch line to prevent wash outs.

Estimated Cost: \$5,650

Contractor completing Project: S&G Excavating LLC.