### ATEAM CONSTRUCTION LLC



# Project Proposal

Prepared for: Mike - Nashville house

Prepared by: Jay Dunlap

June 10, 2025 Repair proposal

#### ATEAM CONSTRUCTION LLC

## **SUMMARY**

2 zones for work include back of house damaged structurally being pulled off house assumably where power box had been attached to home prior to storm.

## Back of house & chimney stack

### **Project Outline**

- Take out damaged brick on back of house and inspect integrity of surrounding wall. Replace damaged brick and mortar and set seal over adjoining window.
- Chimney needs spot tuck point on upper 2/3 of stack. Cut out damaged older mortar and replace. Check cap and reseal if necessary

## **BUDGET**

Description	Materials	Labor	Cost
Back of house	55	\$ 500	\$ 555
Chimney stack	85	\$ 600	\$ 685
Total			\$ 1,240