## Texas Temperature Control Services, Inc. "Warm Up Corral"



- Portable 16' to 20' Bumper Pull Lowboy Trailer with non-skid steps and flooring
- Metal insulated roof and front wall
- 2-10' to 14' heavy duty benches
- Inside and outside safety lights
- Exit sign with Battery backup
- 1 stabilizing, leveling jack located on each corner
- Fold down steps with hand rails
- Fire Extinguisher
- Clear, fire retardant sidewalls
- 4 external tie down points
- 2 110V, 12,000 BTU Heat pumps wired with external fused disconnects

(9900 BTU mechanical/3500 BTU electric strip)

- 230V heat pumps available with 480V conversion package upon request
- 2 50' each 10 gauge power cord
- Requires 1 110V, 20 Amp power source for each unit





