



NOTES

1. ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE SPECIFIED.
2. ALL BLACK COTTON TO BE REMOVED FROM ALL BUILDINGS AND PAVED SURFACES.
3. FOR ALL RC WORK REFERTO STRUCTURAL ENGINEERS DETAILS.
4. DEPTH OF FOUNDATION TO BE DETERMINED ON SITE TO S,E APPROVAL.
5. ALL WALLS TO REINFORCED WITH HOOP IRON AT EVERY ALTERNATE COURSE.
6. MASONRY WALLS TO BE TIED WITH HOOP IRON AT EVERY ALTERNATE COURSE.
7. ANY DISCREPANCIES TO BE COMMUNICATED BEFORE IMPLEMENTATION.
8. ALL WALLING DETAILS TO BE RE-CHECKED UPON IMPLEMENTATION ON SITE.
9. CLASSES OF CONCRETE TO BE ADOPTED ARE M15 FOR BLINDING; 1:3:6 AND M20 FOR STRIP, BASES, STUBS, SLABS, COLUMNS AND BEAMS
10. THE STRUCTURAL DRAWING TO BE READ HANDY WITH THIS ARCHITECTURAL DRAWING.
11. THE INDEMNITY FORM TO BE FILLED BY THE ARCHITECT FOR THIS SPECIFIC PROJECT BEFORE WORKS COMMENCE.

Revision History	Revision History



COSMICON
COSMICON CO. LTD
P.O. BOX 407-80100, KAKAMUGA
EMAIL: cosmiconltd@gmail.com
COSMICON CO. LTD
CONTACT: +254-01 56-9729

PROPOSED RESIDENTIAL ESTATE
KILIFI COUNTY
PLOT NO:

CLIENT;
MS. RISPA MWENDE NJENGA

DESIGN BY: G. ENG. K.M.W. SUDI
DATE: 17/OCT/2024
CHECKED BY: ARCH. DIXTY M. OBINGO

Drawing Name; GROUND FLOOR LAYOUT-ARENAS

ARCHITECTURAL
DESIGN
DRAWING NO:
AD/24WTM/002