

NOTES:

1. Do not scale drawing
2. Unless otherwise stated, all dimensions are in meters.
3. Minimum height of entrances and exits


Class I/II	2.0m
Class III	2.4m
Class IV	3.2m
Class V/VI	2.3m
Class VII	2.4m
Class VIII	3.5m
Class IX	3.5m
Class X	3.6m
4. Minimum width of entrances and exits

Class I/II	2.4m
Class III	2.3m
Class IV	2.4m
Class V	3.5m
Class VI	3.5m
Class VII	4.2m
Class VIII	2.1m
Class IX	2.4m
Class X	3.5m
Class XI	3.8m
Class XII	4.8m
5. Minimum headroom over the bay


Class I/II	4.2m
Class III	2.1m
Class IV	2.4m
Class V	3.5m
Class VI	3.8m
Class VII	4.8m
Class VIII	5.0m
Class IX	6.0m
6. Minimum headroom over the lift

Class I/II	4.8m
Class III	5.0m
Class IV	6.0m
7. Brake tester standing area to be substantially level ($\pm 12\text{mm}$).
8. Headlight beam tester rails to be level to $\pm 2\text{mm}$.
9. Headlight tester standing area to be level to $\pm 6\text{mm}$.
10. Minimum clearance between lift post and wall of 0.5m.
11. The centreline of the MOT bay to the centreline of adjacent lift must be


Class IV	3.6m
Class VII	4.2m
12. All dimensions shown are absolute minimums to be achieved.
13. This layout is subject to VOSA approval, and therefore no civil work should be commenced until written approval has been obtained.
14. The drawing must not be scaled for civil work. Recess drawings are available for the vehicle lift and brake tester.
15. VOSA require all MOT vehicle lifts to be load tested. Provided a suitable vehicle with a current weigh bridge certificate is available during installation, GE-TECH will carry out the necessary thorough examination and issue certification FOC.



OPTION 1: IN-LINE RECESSED - (MINIMUM FLOORPLAN)



OPTION 2: SIDE BY SIDE



OPTION 3: IN LINE SURFACE MOUNTED

Rev	Revision note	Date	By
1	RE-ISSUED FOR NEW WEBSITE	23/09/13	GETECH



PO Box 203
Leeds
West Yorkshire
LS27 1BN

TEL/FAX: 0844 8009785
EMAIL:
WEB: ge-techuk.com
CO REG NO: -

STANDARD INSTALLATION ARRANGEMENTS

Ref	Class	XXX
IV	IV	

Customer	By	Signed	Date
GETECH	A.J.H.		23/09/13

PO BOX 203
LEEDS,
WEST YORKSHIRE,
LS27 1BN

Scale	Sheet	Revision
NTS	1/1	1

Site DWG No. CLASSLIFT