SANITARY SEWER PIPING REQUIREMENTS

GRINDER PUMP STATION TO BUILDING

The property owner shall connect the residences gravity sewer line from the residence to the new Grinder Pump Station. The Townships contractor (Rohde Bros. Excavating, Inc.) will leave a 4" PVC stub out from the station to connect to. The system <u>cannot</u> be put into operation until this connection is made.

The piping from the residence to the Grinder Pump Station must be watertight and only include sanitary waste. No rain or storm water is allowed in the sanitary sewer system.

If a clean out is installed it must stick up above the ground 18" and be marked with a metal fence post or steel pipe 36" above grade.

All properties with sanitary systems <u>must</u> connect to the system. If the existing septic field is removed during construction an immediate connection to the new system is required.

Construction and a permit is required in accordance with Arenac County Plumbing requirements.

- 4" PVC / SCH 40 Pipe
- #12 Sewer Tracer Wire from Grinder
 Station to Clean Out to House
 - Fittings & Reducers as required

Standish Township July 8, 2021