





TANK DESIGN SPECIFICATION CONFORMS TO LATEST ASTM DESIGNATION C1227.



- NOTES**
1. JOINT SEALANT IS BUTYL RUBBER MASTIC TYPE SEAL THAT CONFORMS TO LATEST AASHTO SPECIFICATION M-198. MEETS FEDERAL SPECIFICATION SS-S-0021(210-A).
 2. REINFORCING STEEL REBAR CONFORMS TO LATEST ASTM SPECIFICATION A615.
 3. REINFORCING STEEL WELDED WIRE FABRIC CONFORMS TO LATEST ASTM SPECIFICATION A185.
 4. CONCRETE COMPRESSIVE STRENGTH - 4500 PSI AT 28 DAYS.
 5. METHOD OF MANUFACTURE: WET CAST.
 6. SECTIONS ARE MONOLITHIC.
 7. PIPE INLET AND OUTLET SEALS CONFORM TO ASTM C 1944 OR 923.
 8. ALL CONCRETE AND PLASTIC COVERS HAVE TANK ENTRY WARNING PLACARDS. (TWO COMPARTMENT TANK AND DANGER POISON GAS)
 9. ALL PLASTIC HANDLES HAVE REBAR ATTACHED.
 10. MAXIMUM 4 FEET OF COVER OVER TANK.
 11. OUTLET FILTER CAN BE ORDERED FOR ADDITIONAL COST.
 12. USE OF SCHEDULE 40 PIPE (MEETING ASTM-D1786 OR 2665) OR INTERNAL PIPE SUPPORTS ARE REQUIRED WHEN UTILIZING SIDE ENTRY PORTS AT INLET END.
 13. CONCRETE COVERS MUST REMAIN IN PLACE UNLESS A SECONDARY SAFETY DEVICE IS INSTALLED.



SCALE: 1 / 15
ALL VIEWS

CONNECTICUT CONCRETE PRODUCTS, LLC

	DIMENSIONS ARE IN INCHES TOLERANCES UNLESS NOTED: XX ± 0.1 XXX ± 0.02 XXXX ± 0.005	DRAWN R Campbell CHECKED	12/6/2016	10 MEADOW LANE, STAFFORD SPRINGS, CT 06076 PHONE 860-851-9132 Visit: precastct.com
	ANGLES MACH ± 0.5 BEND ± 2.0	DRILLED HOLES +0.010/-0.000 SURFACE FINISH AS REQUIRED BY TOLERANCE UNLESS NOTED OTHERWISE	QA MFG APPROVED	EST MASS LBS. 10,500 ± 5%
PROPRIETARY AND CONFIDENTIAL THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF MILROY & COMPANY, LLC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF MILROY & COMPANY, LLC IS PROHIBITED.	SIZE D	DWG NO 1250 GAL-PC	REV A	SHEET 1 OF 1