



- NOTES:**
- FENCES/WALL/GATES: AVOID, IF NOT TECHNICALLY FEASIBLE TO AVOID, REMOVE AND RESET IN ORIGINAL LOCATION.
 - STEEL CURB GUARDS (SCG): RETAIN REMAINING TANGENT STEEL SECTIONS OUTSIDE ADA RAMP, IF TECHNICALLY FEASIBLE.
 - EXISTING UTILITY COVERS: SALVAGE AND RESET ORIGINAL LIDS AND FRAMES, OR REPLACE IN KIND IF TECHNICALLY FEASIBLE.
 - EXISTING CATCH BASINS: SALVAGE AND RESET ORIGINAL LIDS AND FRAMES, OR REPLACE IN KIND IF TECHNICALLY FEASIBLE.
 - REFER TO SHEETS S6 (RR034) FOR PROPOSED SEWER REPAIRS NOT SHOWN ON PLAN SHEET FOR THE 1800 BLOCK OF ADAMS STREET.
 - STREET TILES: RESET/RELAY THE ORIGINAL/EXISTING STREET NAME TILES DIRECTLY OUTSIDE PROPOSED ADA FOOTPRINT.
 - PRIOR TO AND THROUGHOUT ANY CONSTRUCTION OPERATIONS BEING CONDUCTED WITHIN THE DRIP LINE OF ANY TREE, THE CONTRACTOR SHALL HAVE AN ARBORIST PRESENT.
 - FOR INSTALLATION OF SIDEWALKS AND CURBS UNDERNEATH THE DRIP LINE OF A TREE, THE CONTRACTOR SHALL LIMIT THE SIDEWALK TO 3' WIDE MIN. WHEREVER NECESSARY AND/OR BUMP OUT THE SIDEWALK WHERE NECESSARY TO AVOID DAMAGE TO TREES.
 - CONTRACTOR SHALL ENSURE THAT THE COMMUNITY GARDENS ARE NOT DISTURBED UNLESS OTHERWISE STATED.
 - ALL EXISTING DRAINAGE STRUCTURES SHOWN IN THE PLAN SET LABELED (TBR) ARE TO BE REMOVED AT NO DIRECT PAY.
 - ALL TREES IN CONFLICT WITH PROPOSED ROADWAY PAVEMENT SHALL BE REMOVED AND REPLACED AS DIRECTED.

SHEET NUMBER		20 OF 127	
BY			
NO.		DATE	
REVISION		DESCRIPTION	
BCC			
BCG ENGINEERING & CONSULTING 3012 26TH STREET, METAIRIE, LA 70002			
DESIGNED	BCG	SCALE	AS SHOWN
CHECKED	BCG	DATE	7/19/2022
DETAILED	BCG	SHEET	RR033-PLN-PRO-01
CHECKED	BCG		
CITY OF NEW ORLEANS, DEPARTMENT OF PUBLIC WORKS PROJECT NO. RR-216			
RR216 - EAST CARROLLTON GROUP B & C			
PLAN & PROFILE SHEET - ADAMS ST 142+50-147+50			

ADAMS STREET (STA: 142+50.00 to STA: 147+50.00)
SCALE: 1"=20' HORZ. / 1"=2' VERT.