



- NOTES:
- FENCES/WALL/GATES: AVOID, IF NOT TECHNICALLY FEASIBLE TO AVOID, REMOVE AND RESET IN ORIGINAL LOCATION.
 - STEEL CURB GUARDS (SCG): RETAIN REMAINING TANGENT STEEL SECTIONS OUTSIDE ADA RAMP, IF TECHNICALLY FEASIBLE.
 - EXISTING UTILITY COVERS: SALVAGE AND RESET ORIGINAL LIDS AND FRAMES, OR REPLACE IN KIND IF TECHNICALLY FEASIBLE.
 - EXISTING CATCH BASINS: SALVAGE AND RESET ORIGINAL LIDS AND FRAMES, OR REPLACE IN KIND IF TECHNICALLY FEASIBLE.
 - REFER TO SHEETS S5 (RR034) FOR PROPOSED SEWER REPAIRS NOT SHOWN ON PLAN SHEET FOR THE 1900 BLOCK OF ADAMS STREET.
 - PRIOR TO AND THROUGHOUT ANY CONSTRUCTION OPERATIONS BEING CONDUCTED WITHIN THE DRIP LINE OF ANY TREE, THE CONTRACTOR SHALL HAVE AN ARBORIST PRESENT.
 - FOR INSTALLATION OF SIDEWALKS AND CURBS UNDERNEATH THE DRIP LINE OF A TREE, THE CONTRACTOR SHALL LIMIT THE SIDEWALK TO 3' WIDE MIN. WHEREVER NECESSARY AND/OR BUMP OUT THE SIDEWALK WHERE NECESSARY TO AVOID DAMAGE TO TREES.
 - CONTRACTOR SHALL ENSURE THAT THE COMMUNITY GARDENS ARE NOT DISTURBED UNLESS OTHERWISE STATED.
 - ALL EXISTING DRAINAGE STRUCTURES SHOWN IN THE PLAN SET LABELED (TBR) ARE TO BE REMOVED AT NO DIRECT PAY.
 - ALL TREES IN CONFLICT WITH PROPOSED ROADWAY PAVEMENT SHALL BE REMOVED AND REPLACED AS DIRECTED.

| | | | |
|---|-----------|---|--------------------|
| SHEET NUMBER | | 21 OF 127 | |
| BY | | | |
| NO. | | DATE | |
| REVISION | | DESCRIPTION | |
| | | | |
| BCC ENGINEERING & CONSULTING 3012, 26TH STREET, METAIRIE, LA 70002 | | | |
| DESIGNED | BCC | SCALE | AS SHOWN |
| CHECKED | BCC | DATE | 7/18/2022 |
| DATE | 7/18/2022 | SHEET | RR033-PLN-PRO-01 |
| DETAILED | BCC | CITY OF NEW ORLEANS, DEPARTMENT OF PUBLIC WORKS | PROJECT NO. RR-216 |
| CHECKED | BCC | RR216 - EAST CARROLLTON GROUP B & C | |
| PLAN & PROFILE SHEET - ADAMS ST 147+50-151+50 | | | |