



- NOTES:**
- FENCES/WALL/GATES: AVOID, IF NOT TECHNICALLY FEASIBLE TO AVOID, REMOVE AND RESET IN ORIGINAL LOCATION.
  - STEEL CURB GUARDS (SCG): RETAIN REMAINING TANGENT STEEL SECTIONS OUTSIDE ADA RAMP, IF TECHNICALLY FEASIBLE.
  - EXISTING UTILITY COVERS: SALVAGE AND RESET ORIGINAL LIDS AND FRAMES, OR REPLACE IN KIND IF TECHNICALLY FEASIBLE.
  - EXISTING CATCH BASINS: SALVAGE AND RESET ORIGINAL LIDS AND FRAMES, OR REPLACE IN KIND IF TECHNICALLY FEASIBLE.
  - REFER TO SHEETS S5 (RR034) FOR PROPOSED SEWER REPAIRS NOT SHOWN ON PLAN SHEET FOR THE 2000 BLOCK OF ADAMS STREET.
  - REFER TO SHEETS S5 (RR034) FOR PROPOSED SEWER REPAIRS NOT SHOWN ON PLAN SHEET FOR THE 2100 BLOCK OF ADAMS STREET.
  - PRIOR TO AND THROUGHOUT ANY CONSTRUCTION OPERATIONS BEING CONDUCTED WITHIN THE DRIP LINE OF ANY TREE, THE CONTRACTOR SHALL HAVE AN ARBORIST PRESENT.
  - FOR INSTALLATION OF SIDEWALKS AND CURBS UNDERNEATH THE DRIP LINE OF A TREE, THE CONTRACTOR SHALL LIMIT THE SIDEWALK TO 3' WIDE MIN. WHEREVER NECESSARY AND/OR BUMP OUT THE SIDEWALK WHERE NECESSARY TO AVOID DAMAGE TO TREES.
  - CONTRACTOR SHALL ENSURE THAT THE COMMUNITY GARDENS ARE NOT DISTURBED UNLESS OTHERWISE STATED.
  - ALL EXISTING DRAINAGE STRUCTURES SHOWN IN THE PLAN SET LABELED (TBR) ARE TO BE REMOVED AT NO DIRECT PAY.
  - ALL TREES IN CONFLICT WITH PROPOSED ROADWAY PAVEMENT SHALL BE REMOVED AND REPLACED AS DIRECTED.

SHEET NUMBER		22 OF 127	
BY			
NO.		DATE	
REVISION		DESCRIPTION	
BCC ENGINEERING & CONSULTING 3012 26TH STREET, METAIRIE, LA 70002			
DESIGNED	BCC	SCALE	AS SHOWN
CHECKED	BCC	DATE	7/19/2022
DATE	7/19/2022	SHEET	RR033-PLN-PRO-01
DETAILED	BCC		
CHECKED	BCC		
CITY OF NEW ORLEANS, DEPARTMENT OF PUBLIC WORKS PROJECT NO. RR-216			
RR216 - EAST CARROLLTON GROUP B & C			
PLAN & PROFILE SHEET - ADAMS ST 151+50 - 156+50			

ADAMS STREET (STA: 151+50.00 to STA: 156+50.00)  
SCALE: 1"=20' HORIZ. / 1"=2' VERT.