

Date: May 25, 2021

Roy Consultants Project Ref: KCIW Knicanewek Sports and Recreation Park

Musco Reference Project: Tobique First Nation Softball 2

To: Roy Consultants

Perth Andover, New Brunswick

Ref: 212654

Quotation Price – Materials Only Delivered to Job Site

Scan 212654A \$ 246,000.00 CDN

*Applicable taxes, bonding, labour, installation, and unloading of the equipment are not included.
Pricing furnished is effective for 60 days unless otherwise noted and is considered confidential.*

SportsCluster™ System with Total Light Control – TLC for LED™ technology

Guaranteed Light Performance

- Guaranteed light levels of 50 FC Infield / 30 FC Outfield
- BallTracker™ technology – targeted light, optimising visibility of the ball in play with no glare in the players typical line-of-sight

System Description

- (6) Factory wired poletop luminaire assemblies
- (32) Factory aimed and assembled luminaries, including BallTracker™ luminaires
- Factory wired and tested remote electrical component enclosures
- Pole length factory assembled wire harnesses
- Mounting hardware for poletop luminaire assemblies and electrical components enclosures
- Disconnects
- CUL Listed assemblies

Environmental Light Control

- Reduction of spill light and glare by 50% or more
- Spill light minimised at Property Line
- Off-site glare light minimised as per Scan 212654A

Control Systems and Services

- Control-Link® control and monitoring system to provide remote on/off and dimming (high/medium/low) control and performance monitoring with 24/7 customer support

Operation and Warranty Services

- Reduction of energy and maintenance 40% to 85% over typical 1500W metal halide equipment.
- Product assurance and warranty program that covers materials and onsite labour, eliminating 100% of your maintenance costs for 25 years
- Support from Musco's Lighting Services Team – over 170 team members dedicated to operating and maintaining your lighting system – plus a network of 1800+ contractors

Responsibilities of Buyer

- Confirm pole locations, supply voltage and phase required for lighting system prior to production.
- Provide electrical design and materials for electrical distribution system.
- Provide labour and equipment for installation of electrical distribution system.
- Provide labour and equipment for installation of bases & poles.



Quote

Musco Scope

- Provide design and layout for lighting system.
- Test and final aim equipment

Payment Terms

Final payment terms will be as approved by Musco's Credit Department.

50% With order, Balance before Load leaves the Factory

Delivery Timing

4 - 6 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole locations.

Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.

Notes

Quote is based on:

- Shipment of entire project together to one location
- 600/347 Volt, 3 Phase, 4 Wire electrical system requirement
- Structural code and wind speed = 2015 NBC, 0.40 KPA
- Owner is responsible for getting electrical power to the site, coordination with the utility, and any power company fees
- Standard soil conditions – rock, bottomless, wet or unsuitable soil may require additional engineering, special installation methods and additional cost
- Confirmation of pole locations prior to production
- **Addendum #1 & #2 Included and submitted with this Quote Closing May 25, 2021 Time: 4:00 PM**

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.

Lloyd Corkum

Sales Supervisor Atlantic Canada
Musco Sports Lighting Canada Co

Toll Free: 1-877-779-7708

Office: 902-455-6665

Mobile: 902-497-3306

E-mail: Lloyd.corkum@musco.com

Web: www.musco.com

