# Lawrence Oaks Homeowners Association ARC Application For METAL ROOFING

# PLEASE MAIL OR EMAIL THE COMPLETED FORM TO:

LAWRENCE OAKS HOMEOWNERS ASSOCIATION, INC. c/o Southern Shores Management 6801 Lake Worth, Rd. Suite 350, Greenacres, FL 33467

# FOR A QUICKER RESPONSE YOU MAY EMAIL THE FORM TO: ARC@LawrenceOaksHOA.com

	Date Received
THIS FORM MUST BE US	ED WHEN REQUESTING A CHANGE TO YOUR ROOF
Homeowners Name:	
Property Address:	
Cell number:	Home number:
Email address:	
***********	**********************
location and other pertinent data. Failure needed to complete description. Include a	<b>ifficient description.</b> Please include such details as the dimensions, materials, color, design, to complete the center section will result in your form being returned. Use additional paper if a copy of Contractor's License and Insurance with Lawrence Oak HOA 7940 Manor Forest ficate holder. Permits and other materials as deemed applicable. Work may not begin until the to you from the ARC committee.
Roof Metal Color:	
I understand that I am responsible for pair	nting the flashing to match the existing trim color. initials:
Roof work will start on	and be completed on
I will contact the ARC once the roof met	tal sheets have been made to ensure color is correct. initials:
Is the required contractor information atta	ached?:
Approval is hereby requested to make for complying with all applicable Cour	the modification(s) as described above, with detailed specifics. I hereby accept responsibility nty Ordinances and Building Codes.
Owner signature:	Printed name:
(DO NO	OT WRITE BELOW THIS LINE – FOR ARC USE ONLY)
Date Approved:	Date Disapproved:
Ву:	Comments:
R <sub>V</sub> .	

**OWNER ASSUMES FULL RESPONSIBILITY FOR OBTAINING ALL APPLICABLE PERMITS.** APPROVALS EXPIRE AFTER 90 DAYS. IF MODIFICATION NOT COMPLETED 90 DAYS AFTER APPROVAL, A NEW ARC REQUEST MUST BE SUBMITTED. PLEASE ALLOW 30 DAYS TO PROCESS.

## Lawrence Oaks Homeowners Association Requirements for Metal Roof:

- 1. Roof shall be 24ga Galvalume originating from a United States mill facility.
- 2. Galvalume panels shall utilize a Kynar PVDF finish in the accepted colors by the HOA
- 3. Roofing panels design requirements must have 1.0" seam height with an acceptable width of 16"
- 4. Roof Penetrations (Vents, Skylight flashings, etc.) must be pre-finished/pre-painted to match the roof color.
- 5. No exposed fastener panels are permitted within the community.
- 6. Approved Vendors for materials: Drexel Metals
- 7. Fabrication companies and/or Roofing companies must hold current certifications with approved vendors to include High Velocity Hurricane Zone testing. Proof to be provided with ARC application.
- 8. Panels must be fully striated to prevent "Oil Canning". Pencil ribs, Ribbon Beads, Flat panels will not be permitted.

## Colors accepted by Lawrence Oaks HOA:

- Drexel Metals Buckskin
- Drexel Metals Sierra Tan
- A. Product approvals showing High Velocity Hurricane Zone testing required to be submitted during roof replacement application.
- B. Material and heavy equipment cannot be left overnight on street without authorization in advance from Lawrence Oaks HOA.
- C. Owner is responsible for assuring that all work complies with applicable building codes and permits.
- D. Improvements shall be completed within 3 months of commencement.
- E. Contractor signage is prohibited to be placed on house, lot, and/or common areas.

Thave read the above requ	irements and ragree to compry.
Signature of Homeowner:	
Date:	

I have read the above requirements and Lagree to comply:

# **DMC 100NS PROFILE**





# **PANEL DETAILS**

#### STANDARD PANEL WIDTHS

12", 16", and 20"

Drexel Metals design pressures, wind uplifts and test reports are for specific deck attachments, material gauges, clip spacing and panel widths. A complete specification and listing is available online at www.drexelmetals.com


### SUBSTRATES AVAILABLE

- · Painted Galvalume® 24ga
- Drexlume<sup>™</sup> 24ga
- · Painted Aluminum .032"

Not seeing the gauge or material you are looking for? Contact your local Drexel Metals representative.

# IDEAL APPLICATION RESIDENTIAL

Our DMC 100NS profile offers unlimited design potential with its sleek, crisp appearance and attractive shadow lines. Eliminating the need for metal roof clips, the concealed 1" self-locking Snap Lock system creates a powerfully protective seal. Versatile and refined, this easy-to-install metal roof delivers superior beauty, durability and strength while showcasing architectural details.




# **DMC 100NS PROFILE**



#### **PROFILE OPTIONS**



## PANEL RIB OPTIONS



Contact your local Drexel Metals representative for specific rib option availability.

#### **PRODUCT INFORMATION**

#### **FINISHES**

Available in a wide variety of coatings and colors. See the Drexel Metals color charts for standard colors and paint specifications.

#### DANEI DIE

Factory made or field rolled to exact lengths options

- · Flat Panel
- · Clip Relief
- Striations
- · Bead
- · Small and Large V
- · Small and Large Pencil

#### INSTALLATION

Can be installed over plywood decking with approved underlayments. Please see Drexel Metals installation details for complete information.

#### SLOPE

Minimum slope 3:12

#### **TESTING**

- · UL 580 Wind Uplift (Class 90)
- · UL 2218 Class 4 Hail Impact
- · UL 263 Fire Certification
- · UL 790 Class A Fire Rating
- · UL Environmental SRI Third Party Verified
- · Florida Building Code Approved
- TAS 125 Wind Uplift
- · TAS 100 Wind Driven Rain
- UL1897 Extended Phase Wind Uplift
- · Miami Dade County Approved

Testing in accordance with



# WARRANTY

## 35 YEAR WARRANTY - GALVALUME AND ALUMINUM SUBSTRATES

35 year non pro-rated PVDF Paint Warranty

High-performance painted metal roofing product, carefully tensioned leveled for superior flatness.

## 25 YEAR WARRANTY - DREXLUME SUBSTRATE

Mill finished Galvalume with a two-sided, clear acrylic finish.

**SHERWIN-WILLIAMS.**Coil Coatings