

Security Project Deliverables

Detailed Stage 01–04 register
with timing, ownership and approval gates

WORKING REFERENCE

Based on SAIS SEC-14, Version 1.0

01

Risk + concept

02

Preliminary design

03

Detail design

04

Operational readiness

Four gates control project progression

Stages 01–03 clear design and execution; Stage 04 clears operation.

01

RISK + CONCEPT

SRA • 10% conceptual design
• organization / policy /
training concepts

GATE

After project initiation; before
preliminary design

PRIMARY LEAD

Security Consultant

02

BID-READY DESIGN

PD • PSI • SDD • SoW •
schedule / equipment /
waivers / drawings

GATE

After SAIS-approved COD;
before contractor bid / award

PRIMARY LEAD

Security Consultant

03

APPROVED FOR EXECUTION

Certified detail design •
device data • drawings • PoC
• readiness progress

GATE

Before procurement,
construction or installation

PRIMARY LEAD

Security Contractor +
Consultant oversight

04

READY TO OPERATE

SAT • training • SOPs • as-
built • certifications •
organization readiness

GATE

During commissioning; before
facility operation

PRIMARY LEAD

Facility Operator

Accountability shifts across four stages

SAIS remains the approval authority at every gate.

ROLE	STAGE 01	STAGE 02	STAGE 03	STAGE 04
Facility Operator	Select parties; NDA; approve SRA	Assure consultant capability + output	Support procedures / training; receive evidence	Submit package; co-sign ORC; executive compliance sign-off
Security Consultant	SRA; COD; concepts	PD; contractor RFP	Review / certify DD and device selection	Monitor T&C; review procedures; confirm initial training
Security Contractor	—	—	DD; devices; construction; installation	Test / commission; co-sign ORC; warranty ≥1 year
SAIS	Approve Stage 01	Approve Stage 02	Approve Stage 03 before execution	Approve Stage 04 before operation

CONTROL POINT FO owns party selection and submission quality; the consultant may not bid for installation on the same project.

Stage 01 establishes the design basis

Three linked parts form one SRA / COD submission package.

WHEN Project initiation → before Stage 02

LEAD Security Consultant; FO approves SRA

STAGE 01

01 Security Risk Assessment

SRA document • required drawings
• Business Criteria Analysis and supporting FSC documentation.
Cover the entire facility, including project expansion areas.

02 Concept of Design

10% Conceptual Design Document
• site-specific drawings • summary / justification of identified SAIS non-compliances and future waiver requests.

03 Organization, policy and training concepts

Concept security organization, posts and headcount • policy / procedures / post-order development concept • formal and informal training-program concept.

HANDOFF CONDITIONS

■ FO approval before submission

The FO reviews and approves the SRA before it goes to SAIS.

■ Development continues

Part 3 concepts are developed jointly by the consultant and FO through Stages 02–03.

■ Training finishes before Stage 04

Detailed training is developed in Stage 02, executed in Stage 03 and completed before Stage 04.

Stage 02 creates a bid-ready design

The Preliminary Design must be detailed enough for contractor pricing and implementation.

WHEN After SAIS-approved COD → before contractor bid / award

LEAD Qualified Security Consultant

01 General requirements

Previous SAIS comments on COD • facility / site description
• project overview and requirements

02 Design criteria

Applicable specifications, codes and standards • detailed engineering design basis

03 PSI — Stage 02

Physical infrastructure, measures, technology, human interface and procedures

04 SDD — Stage 02

SCC-integrated systems / subsystems • operational objectives • equipment identification schedule

05 Scope of Work

Construction, installation and integration scope, organized by area and linked to drawings

06 Waiver requests

Formal requests identified in SRA / COD, prepared in accordance with SEC-01

07 Drawings

Full schematic and geographic drawing set required by section 5.6 and 6.2.1.5

BINDER ORDER

General + criteria / PSI / SDD / SoW / equipment schedule / waivers / drawings

Stage 03 authorizes execution

The contractor develops the final design; the consultant independently reviews and certifies it.

WHEN After approved PD → before procurement / construction / installation

LEAD Security Contractor + Consultant oversight

- **Consultant review report + certificate**

Confirms PD comments incorporated, DD matches approved PD and SEC-01 through SEC-19.

- **Facility and project overview**

General site description, project overview and detailed execution scope.

- **Detailed Scope of Work**

All construction, installation and integration of security infrastructure and systems.

- **Security Design Document**

SCC, PSI, equipment and device parameters, specifications and requirements.

- **Certified detail drawings**

Each drawing stamped, signed and dated by the consultant for SAIS / PD compliance.

- **Vendor evidence**

Data sheets, specifications and applicable certificates for every device and component.

- **Proof of Compliance**

Directive-specific PoC as required by each applicable SEC directive.

- **Operational-readiness progress**

Progress on procedures / Security Manual and contractor / FO training programs.

- **Project schedule**

Project start date, major milestones and completion date.

Stage 03 binder: Sections 01–08

Sections 01–08 organize the certified detail design by infrastructure and system domain.

01 General requirements

Consultant review report • site / project overview • detailed description and SoW

02 SDD — Stage 03

SCC design and architecture • subsystem functions / technical descriptions • network integration

03 PSI — Stage 03

Buildings / elements / equipment design • construction drawings • materials and certifications

04 Security fencing

Design and calculations • perimeter layout • barriers, roads, penetrations and gates • data sheets

05 Security gates

Gate layouts • device / equipment installation drawings • data sheets • road-blocker / bollard test certificates

06 Security lighting

Perimeter / gate / area designs • calculations and plotter prints • installation drawings • data sheets

07 Security Control Center

Construction design • SCC layout • integrated systems / software • data sheets • manning

08 IDAS

Perimeter intrusion and CCTV layouts • field-of-view / lens calculations • data sheets

Stage 03 binder: Sections 09–16

Sections 09–16 complete system detail, compliance evidence and delivery controls.

09 Access Control System

Location-by-location component layouts and installation drawings • data sheets / specifications

10 Video assessment + surveillance

CCTV layouts and installation drawings • field-of-view / lens calculations • data sheets

11 Networks + communications

SECNET topology / capacity / interfaces / cabling • wired / radio comms • coverage map • storage and bandwidth calculations

12 Power supply

Emergency power and UPS drawings • power / UPS calculations • data sheets / specifications

13 Waiver requests

Summary of SAIS non-compliances identified in SRA / COD and previously approved in PD

14 Proof of Compliance

PoC evidence required by each applicable SEC directive

15 Operational-readiness progress

Procedure-development status • contractor / FO training-program status

16 Project schedule

Start date • major project milestones • project completion date

Stage 04 proves operational readiness

Evidence must show both the security system and the Facility Operator are ready for full operation.

WHEN During commissioning → before declaring the facility operational

LEAD Facility Operator submits; contractor + consultant support

01

CERTIFICATIONS

Operational Readiness Certification jointly signed by FO + contractor.

Security Compliance Certification signed by CEO / executive management.

02

INSTALLATION + TESTING

SAT summary and certifications.

Training program, course content and attendance.

SOP list.

As-built drawing list + soft copy.

03

SECURITY ORGANIZATION

Completed policy, procedures and post orders.

Organization chart + personnel list.

Maintenance plan.

Post manning plan.

04

LAND / WATER — IF APPLICABLE

Liaison and cooperation plan with Maritime Forces.

Communications, situational awareness, early warning and response responsibilities.

GO-LIVE GATE SAIS approval of Stage 04 documentation is required before the facility is declared operational.

Five evidence steps unlock go-live

Complete the evidence first; certify only when the operational statements are true.

01	TEST	SAT results demonstrate all implemented security systems were tested onsite.	Contractor performs / documents; consultant monitors.
02	ENABLE	Training completed; attendance evidenced; SOPs implemented; personnel can operate systems.	FO owns readiness; contractor supports training; consultant reviews.
03	CO-SIGN	ORC attests systems are operational, commissioned, supported by SOPs, trained staff and warranty / maintenance.	FO + installation contractor jointly sign.
04	CERTIFY	Compliance certificate confirms execution against approved DD and records approved non-compliances.	Facility CEO or executive management signs.
05	APPROVE	Readiness package, organization evidence, SAT summary and as-builts are submitted for approval.	FO submits to SAIS; SAIS approves before operation.

One document-control standard applies

The same format discipline applies across Stages 01–04.

PACKAGE CONTROL

- **Binder identification**
Company • project number and name • location • stage • volume
x of x
- **Document structure**
Main document plus referenced supporting drawings, schedules
and data sheets; labeled section separators
- **Language + page control**
English or English translation • company / project header on every
page • page number in footer
- **Hard + electronic copies**
Printed hard copy plus removable-media copy in the same
sequence
- **Submission data sheet**
Updated data sheet is the first page of every submission

DIGITAL + DRAWING CONTROL

- **Text documents**
One complete print-ready PDF mirroring hard copy; A4 except
drawings / large tables as needed
- **Drawings**
High-quality PDF • adequate size / resolution • related drawings
grouped into multi-page files
- **Drawing emphasis**
Non-security content greyed out; dedicated security information
kept clear and uncluttered
- **Drawing size**
Large-scale facility layouts / plot plans generally A0; A0 / A1
drawings may be rolled when required
- **Photographs + brochures**
High-quality PDF • contextual captions with company, facility and
location • brochures in color PDF

Master deliverables register

Use this page as the project manager's gate review.

STG	DELIVERABLE PACKAGE	WHEN DUE	PREPARE / EXECUTE	REVIEW / SIGN / SUBMIT	SAIS GATE
01	SRA • 10% COD • org / policy / training concepts	Initiation; before PD	Consultant; FO supports Part 3	FO approves SRA + submits	Design basis
02	Criteria • PSI • SDD • SoW • equipment • waivers • drawings	After COD; before bid	Security Consultant	FO quality check; consultant RFP	Bid-ready PD
03	Consultant certificate • DD • Sections 1–16 • PoC • readiness • schedule	After PD; before execution	Security Contractor	Consultant reviews, stamps + certifies	Final design
04	ORC • compliance certificate • SAT • training • SOPs • as-builts • organization	Commissioning; before operation	Contractor T&C; FO readiness	ORC co-sign; CEO certifies; FO submits	Operational readiness

STOP / GO RULE Do not progress to the next phase until the current deliverables are complete and the required SAIS approval is secured.