


H2O/H2U SERIES

1 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY
CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2O/H2U-1-0712	4	200	5,881	8,850	0.03	10"	14"	7/8 OD"
		400	7,927	11,930	0.09			
		600	9,223	13,880	0.17			
	WPD		.36	.54				
H2O/H2U-1-0718	4	300	8,725	13,130	0.03	10"	20"	7/8 OD"
		550	11,297	17,000	0.08			
		800	12,998	19,560	0.15			
	WPD		.39	.58				
H2O/H2U-1-0724	4	800	15,310	23,040	0.09	10"	26"	7/8 OD"
		1000	16,599	24,980	0.13			
		1200	17,669	26,590	0.17			
	WPD		.42	.63				
H2O/H2U-1-1012	5	800	12,130	18,302	0.17	12"	14"	7/8 OD"
		1000	13,060	19,750	0.24			
		1200	13,830	20,940	0.32			
	WPD		.69	.68				
H2O/H2U-1-1018	6	1000	17,310	25,990	0.13	12"	10"	7/8 OD"
		1200	18,470	27,770	0.17			
		1400	19,460	29,290	0.22			
	WPD		.98	.96				
H2O/H2U-1-1024	7	1200	22,440	33,590	0.11	12"	24"	7/8 OD"
		1400	23,760	35,590	0.14			
		1600	24,910	37,350	0.17			
	WPD		1.34	1.30				
New H2U-1-1030	7	1600	33,230	49,920	.10	12	32	7/8 OD"
		2000	36,670	55,230	.14			
		2400	39,520	59,630	.20			
			1.87	1.78				

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2O/H2U SERIES

1 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY
CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2O/H2U-1-1212	4 WPD	400 600 800	10,700 13,000 14,680 .54	16,810 20,540 23,390 .52	0.06 0.12 0.19	14.5"	14"	7/8 OD"
H2O/H2U-1-1218	4 WPD	800 1000 1200	17,940 19,750 21,210 .62	28,280 31,210 33,610 .59	0.10 0.14 0.19	14.5"	20"	7/8 OD"
H2O/H2U-1-1224	4 WPD	1200 1400 1600	24,420 25,950 27,260 .70	38,500 40,990 43,130 .66	0.12 0.15 0.19	14.5"	26"	7/8 OD"
H2O/H2U-1-1515	5 WPD	800 1000 1200	30,700 34,230 37,190 1.72	19,630 21,840 23,680 1.62	0.10 0.14 0.19	17"	17"	7/8 OD"
H2O/H2U-1-1520	5 WPD	1200 1400 1600	26,990 28,910 30,580 1.99	42,230 45,300 47,980 1.87	0.12 0.15 0.19	17"	22"	7/8 OD"
H2O/H2U-1-1524	5 WPD	1600 1800 2000	33,200 34,870 36,350 2.20	51,970 54,540 57,020 2.06	0.14 0.17 0.20	17"	26"	7/8 OD"

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2O/H2U SERIES

1 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY
CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2O/H2U-1-1718	6 WPD	1200 1400 1600	26,840 28,720 30,360 1.15	42,200 45,250 47,910 1.10	0.11 0.14 0.18	19.5"	20"	7/8 OD"
H2O/H2U-1-1724	6 WPD	1800 2000 2200	36,540 38,130 39,570 1.27	57,490 60,070 62,390 1.21	0.13 0.16 0.19	19.5"	26"	7/8 OD"
H2O/H2U-1-1730	6 WPD	2400 2600 2800	77,340 79,740 82,120 1.39	103,690 106,990 110,360 1.33	0.15 0.17 0.19	19.5"	32"	7/8 OD"
H2O/H2U-1-2024	8 WPD	2000 2200 2400	42,680 44,460 46,090 1.83	67,040 69,910 72,540 1.76	0.13 0.15 0.17	22"	26"	7/8 OD"
H2O/H2U-1-2030	8 WPD	2800 3000 3200	54,430 55,930 57,930 1.31	85,520 87,940 90,200 1.24	0.15 0.17 0.19	22"	32"	7/8 OD"
H2O/H2U-1-2036	8 WPD	3200 3600 4000	62,300 69,390 68,280 1.45	97,760 102,470 104,470 1.37	0.14 0.17 0.20	22"	38"	7/8 OD"

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2O/H2U SERIES

2 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY

CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2O/H2U-2-0712	6 WPD	300 400 500	11,300 13,300 14,900 2.90	17,600 20,600 23,200 2.60	0.12 0.18 0.26	10"	14"	7/8 OD"
H2O/H2U-2-0718	6 WPD	500 600 700	17,800 19,700 21,300 2.90	27,600 30,500 33,100 2.80	0.14 0.18 0.23	10"	20"	7/8 OD"
H2O/H2U-2-0724	6 WPD	700 800 900	24,100 25,900 27,500 3.10	37,400 40,100 42,700 3.00	0.15 0.18 0.22	10"	26"	7/8 OD"
H2O/H2U-2-1012	7.2 WPD	400 500 600	15,000 16,900 18,600 2.70	23,200 26,300 29,000 2.60	0.12 0.17 0.22	12"	14"	7/8 OD"
H2O/H2U-2-1018	7.2 WPD	700 800 900	24,100 25,900 27,600 2.90	37,500 40,200 42,800 2.80	0.15 0.18 0.22	12"	20"	7/8 OD"
H2O/H2U-2-1024	7.2 WPD	1000 1100 1200	32,900 34,600 36,100 3.10	51,100 53,700 56,100 3.00	0.17 0.19 0.22	12"	24"	7/8 OD"

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2O/H2U SERIES

2 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY
CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2O/H2U-2-1212	4 WPD	600 700 800	19,200 20,800 22,300 2.28	30,300 32,900 35,200 0.33	0.16 0.20 0.24	14.5"	20"	7/8 OD"
H2O/H2U-2-1215	4 WPD	400 600 800	16,164 20,593 23,990 1.69	25,611 32,038 37,442 1.58	0.07 0.14 0.23	14.5"	26"	7/8 OD"
H2O/H2U-2-1218	4 WPD	600 800 1000	21,896 25,669 28,718 1.87	34,016 39,970 44,805 1.74	0.10 0.17 0.25	14.5"	20"	7/8 OD"
H2O/H2U-2-1224	4 WPD	800 1000 1200	28,303 31,874 34,856 2.21	43,927 49,562 54,281 2.06	0.10 0.15 0.21	14.5"	26"	7/8 OD"
New H2U-2-1230	4 WPD	1100 1300 1500	44,050 47,920 51,240 2.55	65,620 71,470 76,500 2.73	.14 .18 .23	14.5	32	7/8 OD"
H2O/H2U-2-1515	6 WPD	900 1000 1100	29,100 30,700 32,100 2.60	45,000 47,500 49,800 2.20	0.16 0.18 0.20	17"	17"	7/8 OD"
H2O/H2U-2-1518	6 WPD	1100 1200 1300	34,900 35,500 37,900 2.40	54,000 56,400 58,700 2.30	0.16 0.18 0.20	17"	20"	7/8 OD"

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2O/H2U SERIES

2 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY

CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2U-2-1520	6 WPD	1000 1200 1400	33,843 37,317 40,327 2.48	52,612 58,103 62,879 2.33	0.15 0.21 0.27	17"	22"	7/8 OD"
H2O/H2U-2-1524	6 WPD	1200 1400 1600	39,816 43,155 46,098 2.73	61,866 67,145 71,796 2.56	0.15 0.20 0.25	17"	26"	7/8 OD"
H2O/H2U-2-1530	6 WPD	1400 1600 1800	46,590 49,919 52,882 3.11	72,317 77,557 82,228 2.91	0.14 0.17 0.21	17"	32"	7/8 OD"
New H2U-2-1536	6 WPD	1600 1800 2000	64,840 68,930 72,600 3.14	96,190 102,650 108,200 2.92	.14 .17 .21	17	38	1 1/8 OD"
H2O/H2U-2-1718	7 WPD	1000 1200 1400	34,113 37,635 40,684 1.68	53,172 58,769 63,642 1.60	0.14 0.19 0.25	19.5	20"	7/8 OD"
H2O/H2U-2-1724	7 WPD	1400 1600 1800	45,374 48,578 51,435 1.36	70,715 75,801 80,346 1.27	0.15 0.19 0.23	19.5	26"	7/8 OD"
H2O/H2U-2-1730	7 WPD	1800 2000 2200	55,854 58,788 61,451 1.55	87,014 91,656 95,882 1.45	0.16 0.19 0.23	19.5	32"	7/8 OD"

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2O/H2U SERIES

2 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY
CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2O/H2U-2-1736	8	2700	75,100	60,795	0.17	19.5"	38"	1 1/8 OD"
		3000	78,500	64,510	0.20			
	WPD	3300	81,500	67,772	0.23			
H2U-2-2020	8	1400	37,664	60,795	0.17	22"	22"	7/8 OD"
		1600	39,835	64,510	0.21			
	WPD	1800	41,727	67,772	0.25			
H2U-2-2025	8	1600	51,772	80,799	0.14	22"	27"	7/8 OD"
		1800	54,957	85,875	0.17			
	WPD	2000	57,842	90,478	0.21			
H2O/H2U-2-2030	8	2000	61,934	96,635	0.15	22"	32"	1 1/8 OD"
		2200	64,848	101,286	0.18			
	WPD	2400	67,521	105,552	0.21			
New H2U-2-2036	10	2000	84,910	126,620	.12	22	38	1 1/8 OD"
		2400	93,740	140,000	.17			
	WPD	2800	101,360	151,590	.22			
New H2U-2-2525	10	1600	70,100	104,620	.11	27	12	1 1/8 OD"
		2000	79,240	118,690	.16			
	WPD	2400	87,000	13,590	.22			

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2O/H2U SERIES

3 Row Hot Water Duct Coils



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY
CALL FOR OTHER PERFORMANCE CRITERIA RATINGS


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
New H2U-3-1224	6 WPD	600 800 1000	33,660 40,280 45,790 2.32	52,030 62,370 71,000 2.24	0.09 0.14 0.19	14.5	26	7/8 OD"
H2O/H2U-3-1520	6 WPD	600 800 1000	29,953 36,197 41,398 1.52	46,406 56,220 64,442 1.44	0.10 0.16 0.23	17"	22"	7/8 OD"
New H2U-3-1524	6 WPD	800 1000 1200	52,170 47,320 41,600 1.38	64,540 73,540 81,210 1.35	0.11 0.15 0.19	17"	26"	7/8 OD"
H2O/H2U-3-2020	7 WPD	1000 1200 1400	45,259 50,488 55,053 1.55	70,329 78,618 85,860 1.48	0.14 0.19 0.25	22"	22"	7/8 OD"
H2O/H2U-3-2025	8 WPD	1400 1600 1800	60,688 65,525 69,943 2.15	94,261 101,961 108,900 2.05	0.17 0.21 0.26	22"	27"	7/8 OD"
H2O/H2U-3-2030	8 WPD	2000 2200 2400	84,400 88,500 92,300 1.40	131,100 137,600 143,700 1.30	0.17 0.20 0.24	22"	32"	1 1/8 OD"
H2O/H2U-3-2324	8 WPD	1800 2000 2200	77,400 81,700 85,600 1.20	120,900 127,800 134,100 1.10	0.17 0.19 0.22	25.75"	26"	1 3/8 OD"

STOCK COILS

*PERFORMANCE DATA BASED ON 65° EAT

H2U SERIES

COMMERCIAL SIZES



BUILT TO ARI 410 CERTIFICATION
GALVANIZED STEEL 16 GA. FRAME
ALUMINUM FINS .0045 THICKNESS
COPPER TUBING, 1/2" W/ .017 WALL
MAX 500 PSI OPERATING PRESSURE
MAX 2500 PSI ULTIMATE PRESSURE
BTU OUTPUTS FROM 5,000 TO 50,000
HORIZONTAL & VERTICAL INSTALLATION
FULL ONE YEAR WARRANTY


Part #	GPM	CFM	140 EWT	180 EWT	APD	LENGTH (A)"	WIDTH (B)"	CONNECTION (C)"
H2O/H2U-2-2324	10 WPD	2000 2200 2400	59,830 62,609 65,147 0.87	93,981 98,459 102,560 0.84	0.17 0.20 0.23	25.75"	26"	1 3/8 OD"
New H2U-2-2330	15 WPD	2000 2400 2800	86,960 96,420 104,690 1.22	130,000 144,480 157,150 1.17	0.13 0.18 0.23	25.75"	32"	1 3/8 OD
H2O/H2U-2-2336	15 WPD	3000 3300 3600	94,560 99,212 103,496 1.32	147,626 155,037 161,869 1.29	0.17 0.20 0.23	25.75"	38"	1 3/8 OD"
H2O/H2U-2-2348	20 WPD	4000 4400 4800	136,297 143,409 149,980 2.57	212,165 223,426 233,848 2.44	0.17 0.20 0.23	25.75"	50"	1 3/8 OD"

*PERFORMANCE DATA BASED ON 55° EAT

IN STOCK

HVRF SERIES

1 ROW HOT WATER DUCT COILS



Coil below are for Mitsubishi PEAD Series
We build units for all VRF Compact AHU.
Just give us your supply dimensions.

Part #	CFM	BTU @ 180 EWT	APD	A "	B "	C "	D "	E "	F "
HVRF-1-0726-M	400	17,860	0.02	9.5"	28"	7.5"	26"	3 3/4"	7/8 OD"
HVRF-1-0733-M	500	22,180	0.02	9.5"	35"	7.5"	33"	3 3/4"	7/8 OD"
HVRF-1-0741-M	1000	34,790	0.04	9.5"	43"	7.5"	41"	3 3/4"	7/8 OD"
HVRF-1-0753-M	1200	42,110	0.04	9.5"	55"	7.5"	53"	3 3/4"	7/8 OD"
HVRF-1-0761-M	1400	47,830	0.04	9.5"	63"	7.5"	61"	3 3/4"	7/8 OD"

*PERFORMANCE DATA BASED ON 55° EAT

CHECK STOCK