



Town of Porter

71 Main Street · Porter, ME 04068
Phone: (207) 625-8344 · Fax: (207) 625-4120

Town of Porter Crossing #10403 – Cole Brook at Kennard Hill Road

The Town of Porter will accept sealed bids for the removal of a culvert and installation of a concrete box-bridge until **3:00 PM on Friday April 10, 2020** at the TOWN OFFICE, located at the Porter Town Hall, 71 Main Street, Maine 04068. Bid documents shall be in clearly marked sealed envelopes titled **Kennard Hill Road Project** – all bids will be opened and read aloud in the Selectmen's Room at **9 AM on Monday April 13, 2020**, and the contract will be awarded **at 3PM on Wednesday April 22, 2020** in the Selectmen's Room.

Scope of Work:

Install sand bag cofferdams to control the flow of water into and out of the culvert (the culvert can be left in place during most of the construction). Excavate and install abutments, remove old culvert, pump water around crossing. Install stream bed gravel and bed rocks. Install rocks for bank scour protection. Install bridge deck and finish with (6) six inches of gravel. A list of materials can be found on page 12 of the appendix.

- Contact Dig Safe
- Close road and set up detour signs. Road shall be closed for 3-4 days.
- Install sand bag cofferdams to control water flow in and out of culvert (culvert may stay in place during most of the construction).
- Excavate areas for abutment blocks.
- Furnish and install crushed stone to be used as bedding for abutment blocks.
- Furnish and install abutment blocks.
- Remove culvert and excavate for stream bottom.
- Furnish and install ¾" stone for gravel bed.
- Excavated material shall be used outside of the new stream channel.
- Furnish and install rip rap along abutment blocks to protect from scouring.
- Furnish and install concrete bridge decking.
- Furnish and install waterproofing membrane over decking.
- Furnish and install a minimum of (6) six inches of MDOT Base Type B gravel over decking to be level with existing gravel road.
- Furnish and install 6"-10" riprap at culvert ends.
- Slopes shall be stabilized with jute mesh and seeded.
- Refer to Restoration Plan for specifics.
- Review the attached Army Corps of Engineers permit and additional conditions, and the "Work-start notification form".

Insurance:

The contractor must be able to provide proof of liability insurance in the amount of \$1,000,000.00, EIN number or social security number, and a copy of certificate of workers compensation if you have employees working with you, or a predetermination certificate

from the State. Proof of insurance for all vehicles used must also be provided, and all vehicles must be properly registered. This must be done before any work can begin if you are awarded the contract.

Disclaimer

The Town of Porter reserves the right to reject any or all Bids, to waive any technical or legal deficiencies, and to accept any Bid that it may deem to be in the best interests of the Town of Porter, to negotiate the contract Price with any Bidder, and to omit any item or items deemed advisable for the interest of the Town of Porter.

MANDATORY PRE-BID CONFERENCE

A pre bid conference will be held at 9AM on Monday March 30, 2020, at the Kennard Hill Road site, to present and review elements of the project. All prospective bidders must attend.

**Bids are due in the Porter
Town Office by 3PM on
Friday April 10 , 2020**

BIDDER INFORMATION:

NAME: _____

DBA/ _____

ADDRESS: _____

TEL: _____

Email: _____

I CURRENTLY HAVE: (CIRCLE ALL THAT APPLY)

- GENERAL LIABILITY INSURANCE
- AUTO INSURANCE
- WORKERS COMP INSURANCE OR CERTIFICATE FROM WC BOARD.

I, _____, DO HEREBY PLACE THE FOLLOWING BID:

Total Bid Amount: _____

REFERENCES:

