## **RodDoors CHECKLIST**

TO HELP YOU MAKE SURE YOU'RE READY FOR UPHOLSTERY:

Good Luck on your Project and remember to have fun.

www.roddoors.com

THERE EASILY CAN BE MORE ITEMS ADDED TO THIS LIST, USE THIS LIST AS A STARTING PONIT AND ADD YOUR OWN SPECIAL ITEMS.

MAKE YOUR LIST AND CHECK IT (TWICE)!

NOT OVERLOOKING SOMETHING NOW WILL SAVE YOU MONEY, TIME AND GRIEF LATER.	
	Headliner support bows installed, if you are missing the factory bows or the top has been chopped; all original wood wall supports are in place.
	Floor pan and firewall finished and sealed. This is especially important on glass-bodied cars.
	If you are using door panels other than RodDoors, or RodDoors without integrated arm rests, be sure you have purchased arm rests and fitted them.
	Front (and rear) seat(s), if already purchased, centered and bolted to body for safety.
	Seatbelts/harnesses purchased and installed.
	Want an overhead console? Make sure it is purchased or fabricated and test fitted. Wiring should be in place and all functions tested and working.
	Wiring complete — panel purchased and installed, wires run to areas needed for courtesy lights, third brake lights, power seats and door locks, door contacts, power antenna and power windows. Extra wire length left for shrinkage in final assembly?
	AC/heating units installed and working. Defroster ducts mounted and finished, including vents.
	Wiper motors installed, wired and working.
	Power windows and door lock purchased, installed, wired and working.
	All glass and weather strips installed.
	All Interior garnish molding have been gathered, painted to match the rest of the interior or primed and ready to be covered in matching fabric.
	Radio/CD-tape/Bluetooth/video units test fitted and working. If possible, they should be mounted.
	Gas tank and fill neck sealed to prevent leakage in the shop.